

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	58,200 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (33+47.44-EBL)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (33+60.56-WBL)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	2,500 CY		
0009	0106000000-E	230	BORROW EXCAVATION	75,900 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,238 CY		
0011	0141000000-E	240	BERM DITCH CONSTRUCTION	520 LF		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,350 SY		
0013	0192000000-N	260	PROOF ROLLING	13 HR		
0014	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,650 SY		
0015	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	1,650 CY		
0016	0248000000-N	SP	GENERIC GRADING ITEM EARTHWORK FOR DRY DETENTION BASINS	Lump Sum	L.S.	
0017	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	4,200 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,340 TON		
001E	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
002C	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,700 LF		
0021	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	60 LF		
0022	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (36')	496 LF		
0023	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	76 LF		
0024	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	40 LF		
002E	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
002E	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0027	0973100000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** IN SOIL (42", 0.625", B)	92 LF		
002E	0995000000-E	340	PIPE REMOVAL	908 LF		
002E	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
003C	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	34,860 SY		
0031	1066000000-E	501	LIME FOR LIME TREATED SOIL	360 TON		
0032	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0033	1121000000-E	520	AGGREGATE BASE COURSE	20,800 TON		
0034	1176000000-E	542	SOIL CEMENT BASE	14,940 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1187000000-E	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	420 TON		
003E	1209000000-E	543	ASPHALT CURING SEAL	7,480 GAL		
0037	1220000000-E	545	INCIDENTAL STONE BASE	600 TON		
003E	1264000000-E	SP	DITCHING	30 LF		
003E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	5,400 SY		
004C	1330000000-E	607	INCIDENTAL MILLING	300 SY		
0041	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,700 TON		
0042	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	13,950 TON		
0043	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	12,100 TON		
0044	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,503 TON		
004E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	80 TON		
004E	2000000000-N	806	RIGHT OF WAY MARKERS	155 EA		
0047	2022000000-E	815	SUBDRAIN EXCAVATION	336 CY		
004E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
004E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
005C	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0051	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0052	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2143000000-E	818	BLOTTING SAND	10 TON		
0054	2209000000-E	838	ENDWALLS	12 CY		
005E	2253000000-E	840	PIPE COLLARS	3 CY		
005E	2264000000-E	840	PIPE PLUGS	1 CY		
0057	2275000000-E	SP	FLOWABLE FILL	35 CY		
005E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	107 EA		
005E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	65 LF		
006C	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	32 EA		
0061	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0062	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	6 EA		
0063	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
006E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	23 EA		
006E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	30 EA		
0067	2396000000-N	840	FRAME WITH COVER, STD 840.54	10 EA		
006E	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	31 EA		
006E	2462000000-E	SP	*** SLUICE GATE (8")	2 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	10,350 LF		
0071	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	16,200 LF		
0072	2556000000-E	846	SHOULDER BERM GUTTER	400 LF		
0073	2591000000-E	848	4" CONCRETE SIDEWALK	7,500 SY		
0074	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	5 EA		
007E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	32 EA		
0076	2612000000-E	848	6" CONCRETE DRIVEWAY	400 SY		
0077	2619000000-E	850	4" CONCRETE PAVED DITCH	30 SY		
007E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	980 SY		
007E	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
008C	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	20 EA		
0081	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1 EA		
0082	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0083	3030000000-E	862	STEEL BM GUARDRAIL	2,175 LF		
0084	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
008E	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	4 EA		
008E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0087	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
008E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5	EA	
009C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
0091	3524000000-E	SP	VINYL COATED CHAIN LINK FENCE, *** FABRIC (48")	12,450	LF	
0092	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	1,040	EA	
009E	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	120	EA	
0094	3551000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, SINGLE GATE (48")	4	EA	
009E	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 20', 20')	2	EA	
009E	3628000000-E	876	RIP RAP, CLASS I	258	TON	
0097	3649000000-E	876	RIP RAP, CLASS B	609	TON	
009E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	6,897	SY	
009E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
010C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,215	LF	
0101	4102000000-N	904	SIGN ERECTION, TYPE E	64	EA	
0102	4108000000-N	904	SIGN ERECTION, TYPE F	9	EA	
010E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11	EA	
0104	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	901	SF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	644	SF	
010E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	274	SF	
0107	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
010E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	3	EA	
010E	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	40	DAY	
011C	4430000000-N	1130	DRUMS	500	EA	
0111	4445000000-E	1145	BARRICADES (TYPE III)	144	LF	
0112	4455000000-N	1150	FLAGGER	150	MD	
011E	4480000000-N	1165	TMIA	3	EA	
0114	4510000000-N	SP	LAW ENFORCEMENT	360	HR	
011E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	368	EA	
011E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	31,170	LF	
0117	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	19,956	LF	
011E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,034	LF	
011E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,390	LF	
012C	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12	EA	
0121	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	114	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,661 LF		
0123	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	43,686 LF		
0124	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,948 LF		
012E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	790 LF		
012E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	44 EA		
0127	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	176 EA		
012E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	6,440 LF		
012E	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	95 LF		
013C	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	27 EA		
0131	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	147 EA		
0132	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0133	5691300000-E	1520	8" SANITARY GRAVITY SEWER	150 LF		
0134	5691700000-E	1520	18" SANITARY GRAVITY SEWER	142 LF		
013E	5775000000-E	1525	4' DIA UTILITY MANHOLE	3 EA		
013E	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	21 LF		
0137	5801000000-E	1530	ABANDON 8" UTILITY PIPE	177 LF		
013E	5811000000-E	1530	ABANDON 18" UTILITY PIPE	145 LF		
013E	5816000000-N	1530	ABANDON UTILITY MANHOLE	2 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014C	5882000000-N	SP	GENERIC UTILITY ITEM BREAK DOWN AND REBUILD EXISTING UTILITY MANHOLE	1	EA	
0141	6000000000-E	1605	TEMPORARY SILT FENCE	10,700	LF	
0142	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	4,200	TON	
0143	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	3,150	TON	
0144	6012000000-E	1610	SEDIMENT CONTROL STONE	4,200	TON	
014E	6015000000-E	1615	TEMPORARY MULCHING	48	ACR	
014E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	950	LB	
0147	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	6.5	TON	
014E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,600	LF	
014E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	13	EA	
015C	6029000000-E	SP	SAFETY FENCE	8,200	LF	
0151	6030000000-E	1630	SILT EXCAVATION	23,500	CY	
0152	6036000000-E	1631	MATTING FOR EROSION CONTROL	25,000	SY	
015E	6037000000-E	SP	COIR FIBER MAT	150	SY	
0154	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	500	SY	
015E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,600	LF	
015E	6070000000-N	SP	SPECIAL STILLING BASINS	36	EA	
0157	6071012000-E	SP	COIR FIBER WATTLE	1,300	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
015E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	350 LB		
015E	6071030000-E	SP	COIR FIBER BAFFLES	7,700 LF		
016C	6071050000-E	SP	*** SKIMMER (1-1/2")	9 EA		
0161	6071050000-E	SP	*** SKIMMER (4")	2 EA		
0162	6084000000-E	1660	SEEDING & MULCHING	30 ACR		
0163	6087000000-E	1660	MOWING	36 ACR		
0164	6090000000-E	1661	SEED FOR REPAIR SEEDING	400 LB		
016E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25 TON		
016E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	700 LB		
0167	6108000000-E	1665	FERTILIZER TOPDRESSING	21 TON		
016E	6114500000-N	SP	SPECIALIZED HAND MOWING	20 MHR		
016E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
017C	6123000000-E	1670	REFORESTATION	1 ACR		
0171	6126000000-E	SP	STREAMBANK REFORESTATION	0.17 ACR		
0172	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/COUNTDOWN)	18 EA		
0173	7060000000-E	1705	SIGNAL CABLE	8,400 LF		
0174	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	26 EA		
017E	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	5 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0176	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	9 EA		
0177	7252000000-E	1710	MESSENGER CABLE (1/4")	350 LF		
0178	7264000000-E	1710	MESSENGER CABLE (3/8")	2,500 LF		
0179	7279000000-E	1715	TRACER WIRE	2,400 LF		
0180	7288000000-E	1715	PAVED TRENCHING (***** (1, 2"))	170 LF		
0181	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	4,710 LF		
0182	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2"))	625 LF		
0183	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	22 EA		
0184	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	11 EA		
0185	7360000000-N	1720	WOOD POLE	6 EA		
0186	7372000000-N	1721	GUY ASSEMBLY	15 EA		
0187	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	2 EA		
0188	7408000000-E	1722	1" RISER WITH WEATHERHEAD	3 EA		
0189	7420000000-E	1722	2" RISER WITH WEATHERHEAD	6 EA		
0190	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1 EA		
0191	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,350 LF		
0192	7456000000-E	1726	LEAD-IN CABLE (***** (14-2))	11,200 LF		
0193	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	1,450 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0194	7552000000-N	1731	INTERCONNECT CENTER	3 EA		
019E	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	3 EA		
019E	7566000000-N	1733	DELINEATOR MARKER	5 EA		
0197	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIV- ER	1 EA		
019E	7576000000-N	SP	METAL STRAIN SIGNAL POLE	12 EA		
019E	7613000000-N	SP	SOIL TEST	12 EA		
020C	7614100000-E	SP	DRILLED PIER FOUNDATION	72 CY		
0201	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDA- TION	1 EA		
0202	7636000000-N	1745	SIGN FOR SIGNALS	16 EA		
020E	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0204	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
020E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	26 EA		
020E	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0207 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,632 LF		
020E AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,620 LF		
020E AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,100 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0210 AA1	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	1,732	LF	
*** OR ***						
0211 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,436	LF	
0212 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,196	LF	
0213 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,832	LF	
0214 AA2	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	1,524	LF	
0215 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	196	LF	
0216 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	424	LF	
0217 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	268	LF	
0218 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	208	LF	
*** OR ***						
0219 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,436	LF	
0220 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,196	LF	
0221 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,832	LF	
0222 AA3	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	1,524	LF	
0223 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	196	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0224 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	424 LF		
0225 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	268 LF		
0226 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (36", 0.064")	208 LF		

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0227	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (33 + 54.00-L-LT)	Lump Sum	L.S.	
0228	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	227.25 LF		
0229	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	154 LF		
0230	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	29.9 LF		
0231	8113000000-N	SP	SID INSPECTION	2 EA		
0232	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0233	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	28,396 SF		
0234	8161000000-E	420	GROOVING BRIDGE FLOORS	22,218 SF		
0235	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	331.6 CY		
0236	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (33 + 54.00-L-LT)	Lump Sum	L.S.	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0237	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (33 + 54.00-L-RT)	Lump Sum	L.S.	
023E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	108,126 LB		
023E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	18,500 LB		
024C	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	3,646.66 LF		
0241	8364000000-E	SP	HP12X53 STEEL PILES	1,035 LF		
0242	8482000000-E	460	THREE BAR METAL RAIL	720.032 LF		
0243	8503000000-E	460	CONCRETE BARRIER RAIL	735.718 LF		
0244	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,580 TON		
024E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,755 SY		
024E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0247	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1337/Apr15/Q794314.08/D1005837942000/E247

Total Amount Of Bid For Entire Project :

Contract No **C202379**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General