

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+47)	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	750 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1,110 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,500 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	480 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,650 SY		
0010	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	1,650 CY		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	100 SY		
0012	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0013	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	176 LF		
0014	0986000000-E	SP	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	80 LF		
0015	0986000000-E	SP	GENERIC PIPE ITEM 36" RC PIPE CULVERTS, CLASS III	40 LF		
0016	0995000000-E	340	PIPE REMOVAL	64 LF		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,150 TON		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	800 TON		
001E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	900 TON		
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	142 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	8 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2209000000-E	838	ENDWALLS	3.4 CY		
002E	2253000000-E	840	PIPE COLLARS	2.5 CY		
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	168 LF		
003E	3030000000-E	862	STEEL BM GUARDRAIL	537.5 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
0037	3628000000-E	876	RIP RAP, CLASS I	35	TON	
003E	3649000000-E	876	RIP RAP, CLASS B	390	TON	
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,490	SY	
004C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	45	LF	
0041	4102000000-N	904	SIGN ERECTION, TYPE E	4	EA	
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	5	EA	
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	80	SF	
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20	SF	
004E	4430000000-N	1130	DRUMS	44	EA	
0047	4435000000-N	1135	CONES	44	EA	
004E	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
004E	4450000000-N	1150	FLAGGER	2,400	HR	
005C	4516000000-N	1180	SKINNY DRUM	72	EA	
0051	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	47	EA	
0052	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,700	LF	
0053	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,700	LF	

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	600	LF	
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,800	LF	
005E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	23	EA	
0057	6000000000-E	1605	TEMPORARY SILT FENCE	4,650	LF	
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	230	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	650	TON	
006C	6012000000-E	1610	SEDIMENT CONTROL STONE	230	TON	
0061	6015000000-E	1615	TEMPORARY MULCHING	9.5	ACR	
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300	LB	
0063	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2	TON	
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	350	LF	
006E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
006E	6029000000-E	SP	SAFETY FENCE	650	LF	
0067	6030000000-E	1630	SILT EXCAVATION	1,150	CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,000	SY	
006E	6037000000-E	SP	COIR FIBER MAT	450	SY	
007C	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,100	SY	
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	400	LF	

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6071020000-E	SP	POLYACRYLAMIDE (PAM)	130 LB		
0073	6071030000-E	SP	COIR FIBER BAFFLES	650 LF		
0074	6071050000-E	SP	*** SKIMMER (1-1/2")	6 EA		
0075	6084000000-E	1660	SEEDING & MULCHING	9 ACR		
0076	6087000000-E	1660	MOWING	6 ACR		
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0078	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0079	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		
0080	6108000000-E	1665	FERTILIZER TOPDRESSING	4.75 TON		
0081	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0083	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0084	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+47.00-L-)	Lump Sum	L.S.	
0085	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+47.00-L-)	Lump Sum	L.S.	
0086	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+47.00-L-)	Lump Sum	L.S.	
0087	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,988 SF		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8161000000-E	420	GROOVING BRIDGE FLOORS	4,668 SF		
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	40 CY		
009C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20 + 47.00-L)	Lump Sum	L.S.	
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,264 LB		
0092	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	207,000 LS		
0093	8384000000-E	SP	HP14X73 STEEL PILES	360 LF		
0094	8503000000-E	460	CONCRETE BARRIER RAIL	296.67 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,295 TON		
009E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,435 SY		
0097	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1142/Apr27/Q286021.67/D425286900000/E98

Total Amount Of Bid For Entire Project :

Contract No **C202551**

County (ies): **Chatham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General