

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (14 + 34.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	2,400 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	50 SY		
0009	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	50 CY		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	60 SY		
0011	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0012	0335200000-E	SP	15" DRAINAGE PIPE	48 LF		
0013	0986000000-E	SP	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	132 LF		
0014	1121000000-E	520	AGGREGATE BASE COURSE	110 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0016	1275000000-E	600	PRIME COAT	73.5 GAL		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	120 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	260 TON		

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2275000000-E	SP	FLOWABLE FILL	2 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
0031	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	125 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	4 EA		
0033	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	3 EA		
0034	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (SHOP CURVED, TYPE III)	2 EA		
0035	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	1 EA		

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3435000000-N	SP	GENERIC GUARDRAIL ITEM IMPACT ATTENUATOR UNIT, TYPE 350 (TL-2)	1 EA		
0037	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0038	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,180 SY		
0039	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	70 LF		
0040	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0041	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4 EA		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	385 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	141 SF		
0046	4435000000-N	1135	CONES	23 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	180 LF		
0048	4450000000-N	1150	FLAGGER	96 HR		
0049	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,764 LF		
0050	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	76 LF		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	1,325 LF		
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	330 TON		
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	170 TON		

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	370 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
006C	6029000000-E	SP	SAFETY FENCE	1,350 LF		
0061	6030000000-E	1630	SILT EXCAVATION	310 CY		
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,460 SY		
006E	6037000000-E	SP	COIR FIBER MAT	10 SY		
0064	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	175 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	650 LF		
006E	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0067	6071010000-E	SP	WATTLE	100 LF		
006E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
006E	6071030000-E	SP	COIR FIBER BAFFLES	180 LF		
007C	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0071	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0072	6087000000-E	1660	MOWING	3 ACR		

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0074	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0077	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
007E	6123000000-E	1670	REFORESTATION	0.15 ACR		

**WALL ITEMS**

008C	8847000000-E	SP	GENERIC RETAINING WALL ITEM COBBLE FACED RETAINING WALL	785 SF		
------	--------------	----	--	-----------	--	--

**STRUCTURE ITEMS**

0081	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14 + 34.00-L-)	Lump Sum	L.S.	
0082	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 34.00-L-)	Lump Sum	L.S.	
0083	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,14 + 34.00-L-)	Lump Sum	L.S.	
0084	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2,14 + 34.00-L-)	Lump Sum	L.S.	
008E	8096000000-E	SP	PILE EXCAVATION IN SOIL	20 LF		
008E	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	25 LF		

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	101.4 CY		
008E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	16,270 LB		
008E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,394 LB		
009C	8364000000-E	SP	HP12X53 STEEL PILES	213 LF		
0091	8391000000-N	SP	STEEL PILE POINTS	5 EA		
0092	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	414.8 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	430 TON		
0094	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	475 SY		
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009E	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	2,071.15 LF		

1618/Apr29/Q45457.7/D431058910000/E96

Total Amount Of Bid For Entire Project :

**Contract No**      **C202428**

**County (ies):**    **Graham**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General