

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	12,600 CY		
0004	0038000000-E	SP	SHALLOW UNDERCUT	20 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	20 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	710 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	750 SY		
0010	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	100 CY		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	90 SY		
0012	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0013	0938000000-E	320	*** X *** CS STRUCTURAL PLATE PIPE ARCH, ** GAUGE (154" X 100", 12)	52 LF		
0014	0995000000-E	340	PIPE REMOVAL	111 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	1,271 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	113 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	70 TON		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	500 TON		
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	39 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	9 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2199000000-E	SP	SANDBAG HEADWALL	340 SF		
003C	2473000000-N	SP	GENERIC DRAINAGE ITEM ROCK INLET SILL	2 EA		
0031	3030000000-E	862	STEEL BM GUARDRAIL	762.5 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0034	3360000000-E	863	REMOVE EXISTING GUARDRAIL	818 LF		
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	837.5 LF		
003E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	410	LF	
003E	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	20	EA	
003E	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	20	EA	
004C	3563000000-E	SP	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (48")	130	LF	
0041	3628000000-E	876	RIP RAP, CLASS I	30	TON	
0042	3649000000-E	876	RIP RAP, CLASS B	110	TON	
0043	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,750	SY	
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	220	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	72	SF	
0047	4430000000-N	1130	DRUMS	30	EA	
004E	4435000000-N	1135	CONES	125	EA	
004E	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
005C	4450000000-N	1150	FLAGGER	960	HR	
0051	4480000000-N	1165	TMIA	1	EA	
0052	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	18	EA	
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	27,007	LF	
0054	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	5,452	LF	

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	17	EA	
005E	6000000000-E	1605	TEMPORARY SILT FENCE	2,000	LF	
0057	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	270	TON	
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	135	TON	
006C	6015000000-E	1615	TEMPORARY MULCHING	10.5	ACR	
0061	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300	LB	
0062	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2	TON	
0063	6024000000-E	1622	TEMPORARY SLOPE DRAINS	375	LF	
0064	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5	EA	
006E	6029000000-E	SP	SAFETY FENCE	950	LF	
006E	6030000000-E	1630	SILT EXCAVATION	900	CY	
0067	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,500	SY	
006E	6037000000-E	SP	COIR FIBER MAT	100	SY	
006E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	600	SY	
007C	6042000000-E	1632	1/4" HARDWARE CLOTH	100	LF	
0071	6069000000-E	1638	STILLING BASINS	135	CY	
0072	6070000000-N	SP	SPECIAL STILLING BASINS	3	EA	
0073	6071010000-E	SP	WATTLE	110	LF	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6071020000-E	SP	POLYACRYLAMIDE (PAM)	30 LB		
007E	6071030000-E	SP	COIR FIBER BAFFLES	775 LF		
007E	6071050000-E	SP	*** SKIMMER (1-1/2")	7 EA		
0077	6084000000-E	1660	SEEDING & MULCHING	9 ACR		
007E	6087000000-E	1660	MOWING	6 ACR		
007E	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
008C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	5.25 TON		
008E	6111000000-E	SP	IMPERVIOUS DIKE	175 LF		
0084	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
008E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
008E	6120000000-E	SP	CULVERT DIVERSION CHANNEL	175 CY		
0087	6123000000-E	1670	REFORESTATION	0.5 ACR		

---

**CULVERT ITEMS**


---

008E	8049000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+91.50-L-)	Lump Sum	L.S.	
008E	8126000000-N	414	CULVERT EXCAVATION, STA ***** (17+91.50-L-)	Lump Sum	L.S.	
009C	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	170 TON		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8196000000-E	420	CLASS A CONCRETE (CULVERT)	281.7 CY		
0092	8245000000-E	425	REINFORCING STEEL (CULVERT)	57,229 LB		
			<b>Total Amount Of Bid For Entire Project :</b>			

1049/Apr28/Q132014.2/D366398210000/E92

**Contract No**     **C202550**

**County (ies):**   **McDowell**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General