



WE Design Your Tomorrow . . .

Project: B-4610 County: Randolph

PROJECT SPECIAL PROVISIONS

Utilities by Others

GENERAL:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) **Progress Energy Carolinas, Inc.(Power/Distribution)**
Alan Dasen (910) 944-5274
- B) **Time Warner Cable (Cable TV)**
Scott Bivens (336) 629-5184
- C) **CenturyLink (Telephone)**
Tony Ingold (336) 626-3155
- D) **Westside VFD (Dry Hydrant)**
Recil Williamson (336) 736-0191

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the NCDOT "Standard Specifications for Roads and Structures" dated January 2006.

Utilities Requiring Adjustments:

- A) **Progress Energy Carolinas, Inc. (Power/Distribution)**
 - 1. A new aerial distribution power pole line, with cable TV and telephone attached, will be installed further right of Line-L- between Sta.14+35 and Sta.21+25. The power pole relocation work will be completed by May 1, 2010. See Utilities By Others Plans for details.
- B) **Time Warner Cable (Cable TV)**
 - 1. Time Warner Cable is attached to Progress Energy Power poles and will be relocated with Progress Energy Power. Time Warner requires 30 (thirty) days notice prior to Progress Energy completing their work and 10 (ten) days to complete their work. See Utilities By Others Plans for details.



WE Design Your Tomorrow . . .

I 75

Transportation
Planning
Bridge/Structural
Civil/Site
Construction Observation

C) CenturyLink (Telephone)

1. CenturyLink telephone is attached to Progress Energy Power poles crossing Lake Lucas and will be relocated with Progress Energy Power crossing Lake Lucas. A new buried telephone cable will be installed further right of Line-L- between Sta. 14+35 and Sta. 17+09 and further left and right of Line-L- between Sta. 21+25 and Sta. 26+85. CenturyLink telephone requires 30 (thirty) days notice prior to Time Warner completing their work and 20 (twenty) days to complete their work. See Utilities By Others Plans for details.

D) Westside VFD (Dry Hydrant)

1. Westside Volunteer Fire Hydrant has a 6" dry hydrant connector attached to the bridge located right of Line-L- at Sta.18+00. The dry hydrant is no longer functional and will be demolished during construction of the new bridge.