


PROJECT SPECIAL PROVISIONS
Utility Construction



All proposed utility construction shall meet the applicable requirements of the Department of Transportation's "Standard Specifications for Roads and Structures" dated July 2006. Division 15 of the Standard Specifications is revised as follows:

Page 15-1, Paragraph 4

Provide access for Department personnel and the owner's representatives to all phases of construction. Notify Department personnel and the utility owner two weeks prior to commencement of any work and one week prior to service interruption. Keep utility owner's representatives informed of work progress and provide opportunity for inspection of construction and testing. The water lines on this project belong to Robeson County Public Works Department. The contact person for the owner is Mr. Henry Harris and he can be reached by phone at (910) 671-3485. Any work on the utility owner's lines must be coordinated through the Engineer and the utility owner before beginning.

Page 15-9 Section 1515-2

In addition to the water line materials specified under Section 1036, the water line can be High Density Polyethylene (HDPE) pipe conforming to AWWA C906 with an SDR of 9 and a pressure rating of 200 PSI.

The proposed water line on this project shall be SDR 21 PVC pipe installed under the toe of slope as noted on the utility construction plan sheets. Pipe used for the trenchless installation shall be HDPE installed in accordance with Section 1550 of the Standard Specifications.

The existing water line is shown on the utility construction plan sheets as being SDR 26 PVC pipe. This is based on the best available information. Should the Contractor determine that the existing line is of material other than as stated on the plans, the Contractor shall immediately notify the Engineer and the acceptability of the existing pipe shall be evaluated and verified prior to installation of the proposed water line.

COMPENSATION:

No direct payment will be made for utility construction work required by the preceding provisions, which are general requirements applying to utility construction, and all of the requirements stated will be considered incidental work, paid for at the contract unit prices of the various utility items included in the contract.

PROJECT SPECIAL PROVISIONS

Utility

UTILITIES BY OTHERS

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) Lumbee River EMC – Power (Distribution)
- B) AT&T – Telephone
- C) Piedmont Natural Gas Company – Gas
- D) Time Warner Cable – Cable TV

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A) Lumbee River EMC - Power (Distribution)
 - 1) See Utilities by Others Plans.
 - 2) Lumbee River EMC temporary line will be complete prior to date of availability. DOT contractor to give Lumbee River EMC 3 weeks notice prior to shifting traffic from Detour onto –L– and allow 3 weeks to build permanent line and remove temporary poles. Contact person is Mr. Bernard Jones(910-827-2134).
- B) AT&T – Telephone
 - 1) See Utilities by Others Plans.
- C) Piedmont Natural Gas Company – Gas
 - 1) See Utilities by Others Plans.
- D) Time Warner Cable – Cable TV
 - 1) See Utilities by Others Plans.

- 2) Time Warner Cable to follow Lumbee River EMC on the temporary pole line relocation. Time Warner will also relocate (by directional bore) a fiber optic cable along the proposed right of way(south side of -L-) throughout project. This work should be complete by the date of availability. Contact person is Mr. John McMillan (910-308-8392).

NOTE: All other utilities will remain in place and will be adjusted as necessary.