

PROJECT SPECIAL PROVISIONS
Utility Construction


Revise the *2006 Standard Specifications* as follows:

Page 10-10, Subarticle 1000-7, Flowable Fill, add following paragraph:

This work shall consist of furnishing and placing ready-mixed or volumetric mixed flowable fill to fill voids under pipe invert as specified in the plans or as directed by the Engineer. Pipe invert subsurface voids shall be flat/smooth on the bottom of the pipe when construction is complete and shall be approved by the Engineer. Backfill shall not be placed on flowable fill prior to final set or hardening as determined by the Engineer. The flowable fill materials shall meet the requirements of Section 340-2.

Page 3-13, Subarticle 340-4, Measurement and Payment, add following paragraph:

The quantity of flowable fill placed and accepted will be measured and paid for at the contract unit price per cubic yard for "Flowable Fill." Such price and payment will be full compensation for all work covered by this special provision including but not limited to the mix design, furnishing, hauling, labor, placing the flowable fill, containing the flowable fill, and incidentals necessary to complete the work as required.



PROJECT SPECIAL PROVISIONS

Utilities by Others

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. Duke Energy (Power)
- B. Embarq (Telephone)

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A. Duke Energy (Power)
 - 1. All Duke Energy work within the limits of this project will be completed by the date of availability. See "Utilities By Others" Plans for details.

Contact person: Mr. Ted Plummer @ 336-209-6773

- B. Embarq (Telephone)
 - 1. All Time Warner Cable work within the limits of this project will be completed by the date of availability. See "Utilities By Others" Plans for details.

Contact person: Mr. Glenn Maxey @ 336-526-3318