

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000910000-N	SP	GENERIC MISCELLANEOUS ITEM EXPLORATORY EXCAVATION - STANDARD	6 HR		
0004	0000910000-N	SP	GENERIC MISCELLANEOUS ITEM EXPLORATORY EXCAVATION - VACU- UM	6 HR		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (30 + 63.00)	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	1,400 CY		
0008	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0009	0106000000-E	230	BORROW EXCAVATION	69,000 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	4,462 CY		
0011	0195000000-E	SP	SELECT GRANULAR MATERIAL	1,200 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,200 SY		
0013	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	572 TON		
0014	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	1,814 SY		
0015	0342000000-E	SP	*** SIDE DRAIN PIPE (72")	60 LF		
0016	0343000000-E	SP	15" SIDE DRAIN PIPE	1,092 LF		
0017	0344000000-E	SP	18" SIDE DRAIN PIPE	72 LF		
0018	0345000000-E	SP	24" SIDE DRAIN PIPE	188 LF		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0348000000-E	SP	*** SIDE DRAIN PIPE ELBOWS (15")	2	EA	
0020	0372000000-E	SP	18" RC PIPE CULVERTS, CLASS III	64	LF	
0021	0448000000-E	SP	***** RC PIPE CULVERTS, CLASS IV (48")	192	LF	
0022	0448000000-E	SP	***** RC PIPE CULVERTS, CLASS IV (72")	80	LF	
0023	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	732	LF	
0024	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	28	LF	
0025	0448600000-E	SP	36" RC PIPE CULVERTS, CLASS IV	12	LF	
0026	0995000000-E	340	PIPE REMOVAL	211	LF	
0027	1077000000-E	SP	#57 STONE	170	TON	
0028	1308000000-E	607	MILLING ASPHALT PAVEMENT, ***** TO ***** DEPTH (0" TO 1-1/2")	2,250	SY	
0029	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	4,600	TON	
0030	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,850	TON	
0031	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	4,260	TON	
0032	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	335	TON	
0033	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	260	TON	
0034	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	54	TON	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2209000000-E	838	ENDWALLS	12 CY		
003E	2220000000-E	838	REINFORCED ENDWALLS	7.5 CY		
0037	2253000000-E	840	PIPE COLLARS	0.399 CY		
003E	2264000000-E	840	PIPE PLUGS	0.09 CY		
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	25 EA		
004C	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	27.6 CY		
0041	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5.52 LF		
0042	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2 EA		
004E	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	10 EA		
0044	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
004E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
004E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0047	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
004E	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	4 EA		
004E	2535000000-E	846	***X *** CONCRETE CURB (8" x 12")	320 LF		
005C	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,250 LF		
0051	2556000000-E	846	SHOULDER BERM GUTTER	205 LF		
005Z	2612000000-E	848	6" CONCRETE DRIVEWAY	11 SY		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	350 SY		
0054	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0055	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA		
0056	3030000000-E	862	STEEL BM GUARDRAIL	2,175 LF		
0057	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0058	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0059	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0060	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0061	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
0062	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,870 LF		
0063	3628000000-E	876	RIP RAP, CLASS I	255 TON		
0064	3635000000-E	876	RIP RAP, CLASS II	130 TON		
0065	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0066	3651000000-E	SP	BOULDERS	80 TON		
0067	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,105 SY		
0068	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	768 LF		
0069	4096000000-N	904	SIGN ERECTION, TYPE D	6 EA		
0070	4102000000-N	904	SIGN ERECTION, TYPE E	33 EA		
0071	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	31 EA		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2	EA	
0073	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	525	SF	
0074	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	288	SF	
007E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	115	SF	
007E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0077	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4	EA	
007E	4430000000-N	1130	DRUMS	200	EA	
007E	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
008C	4455000000-N	1150	FLAGGER	60	MD	
0081	4480000000-N	1165	TMIA	2	EA	
0082	4510000000-N	SP	LAW ENFORCEMENT	80	HR	
0083	4516000000-N	1180	SKINNY DRUM	200	EA	
0084	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	320	EA	
008E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	7,181	LF	
008E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	6,210	LF	
0087	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,002	LF	
008E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	100	LF	
008E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	5	EA	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	788	LF	
0091	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	4,314	LF	
0092	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	78,858	LF	
0093	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,848	LF	
0094	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	64	LF	
009E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	120	EA	
0096	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	21,120	LF	
0097	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,000	LF	
009E	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	10	EA	
009E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	97	EA	
010C	5325600000-E	1510	6" WATER LINE	1,603	LF	
0101	5327000000-E	1510	20" WATER LINE	1,142	LF	
0102	5540000000-E	1515	6" VALVE	3	EA	
0103	5559000000-E	1515	20" VALVE	8	EA	
0104	5606800000-E	1515	8" BLOW OFF	1	EA	
010E	5648000000-N	1515	RELOCATE WATER METER	3	EA	
010E	5649000000-N	1515	RECONNECT WATER METER	3	EA	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	5691000000-E	1520	*** SANITARY GRAVITY SEWER (48")	443 LF		
010E	5691500000-E	1520	12" SANITARY GRAVITY SEWER	243 LF		
010E	5776000000-E	1525	5' DIA UTILITY MANHOLE	3 EA		
011C	5777000000-E	1525	6' DIA UTILITY MANHOLE	2 EA		
0111	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	30 LF		
0112	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	16.9 LF		
011E	5783000000-E	1525	UTILITY MANHOLE WALL, 6' DIA	11.5 LF		
0114	5798000000-E	1530	ABANDON *** UTILITY PIPE (48")	384 LF		
011E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	255 LF		
011E	5812000000-E	1530	ABANDON 20" UTILITY PIPE	943 LF		
0117	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		
011E	5882000000-N	SP	GENERIC UTILITY ITEM BREAKDOWN AND REBUILD MANHOLE	1 EA		
011E	5882000000-N	SP	GENERIC UTILITY ITEM STEEL PILE PIER	5 EA		
012C	6000000000-E	1605	TEMPORARY SILT FENCE	15,000 LF		
0121	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	705 TON		
0122	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,350 TON		
012E	6012000000-E	1610	SEDIMENT CONTROL STONE	1,630 TON		
0124	6015000000-E	1615	TEMPORARY MULCHING	16 ACR		
012E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	350 LB		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.25	TON	
0127	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,070	LF	
0128	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	11	EA	
0129	6029000000-E	SP	SAFETY FENCE	6,650	LF	
0130	6030000000-E	1630	SILT EXCAVATION	1,115	CY	
0131	6036000000-E	1631	MATTING FOR EROSION CONTROL	15,500	SY	
0132	6037000000-E	SP	COIR FIBER MAT	70	SY	
0133	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	4,000	SY	
0134	6042000000-E	1632	1/4" HARDWARE CLOTH	1,630	LF	
0135	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	400	SY	
0136	6070000000-N	SP	SPECIAL STILLING BASINS	20	EA	
0137	6071010000-E	SP	WATTLE	255	LF	
0138	6071020000-E	SP	POLYACRYLAMIDE (PAM)	126	LB	
0139	6071030000-E	SP	COIR FIBER BAFFLES	2,485	LF	
0140	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
0141	6084000000-E	1660	SEEDING & MULCHING	15	ACR	
0142	6087000000-E	1660	MOWING	15	ACR	
0143	6090000000-E	1661	SEED FOR REPAIR SEEDING	150	LB	
0144	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	350 LB		
014E	6108000000-E	1665	FERTILIZER TOPDRESSING	10 TON		
0147	6114500000-N	SP	SPECIALIZED HAND MOWING	50 MHR		
014E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
014E	6118000000-N	SP	ROOTWADS	12 EA		
015C	6123000000-E	1670	REFORESTATION	0.75 ACR		
0151	6126000000-E	SP	STREAMBANK REFORESTATION	1.27 ACR		
0152	6132000000-N	SP	GENERIC EROSION CONTROL ITEM LOG	40 EA		
015E	6138000000-E	SP	GENERIC EROSION CONTROL ITEM BORROW PIT DEWATERING BASIN	6,800 CY		
0154	7980000000-N	SP	GENERIC SIGNAL ITEM PORTABLE TRAFFIC SIGNAL SYSTEM	2 EA		
STRUCTURE ITEMS						
015E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (30 + 63.00-SBL-)	Lump Sum	L.S.	
015E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (30 + 63.00-SBL-)	Lump Sum	L.S.	
0157	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	110 LF		
015E	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	123 LF		
015E	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	127 LF		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
016C	8113000000-N	SP	SID INSPECTION	5 EA		
0161	8115000000-N	SP	CROSSHOLE SONIC LOGGING	5 EA		
0162	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	26,628 SF		
0163	8161000000-E	420	GROOVING BRIDGE FLOORS	20,865 SF		
0164	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	315.5 CY		
0165	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (30 + 63.00-SBL-)	Lump Sum	L.S.	
0166	8217000000-E	425	REINFORCING STEEL (BRIDGE)	79,002 LB		
0167	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	10,932 LB		
0168	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	3,117.92 LF		
0169	8364000000-E	SP	HP12X53 STEEL PILES	495 LF		
017C	8475000000-E	460	TWO BAR METAL RAIL	620.02 LF		
0171	8503000000-E	460	CONCRETE BARRIER RAIL	678 LF		
0172	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	627.81 LF		
0173	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	940 TON		
0174	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,045 SY		
017E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0176	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0177	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
017E	8860000000-N	SP	GENERIC STRUCTURE ITEM TELEPHONE CONDUIT AND HANGER SYSTEM	Lump Sum	L.S.	

1137/Jun07/Q447106.529/D784403850000/E178

Total Amount Of Bid For Entire Project :

Contract No **C202335**

County (ies): **Harnett**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General