

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	13,800 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (32+50 -L-)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	700 CY		
0008	0038000000-E	SP	SHALLOW UNDERCUT	100 CY		
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0010	0106000000-E	230	BORROW EXCAVATION	283,000 CY		
0011	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2,880 CY		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	7,700 SY		
0013	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	10,500 SY		
0014	0195000000-E	SP	SELECT GRANULAR MATERIAL	500 CY		
0015	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0016	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	314 TON		
0017	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	990 SY		
0018	0343000000-E	SP	15" SIDE DRAIN PIPE	80 LF		
0019	0344000000-E	SP	18" SIDE DRAIN PIPE	104 LF		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	212 LF		
0021	0372000000-E	SP	18" RC PIPE CULVERTS, CLASS III	260 LF		
0022	0378000000-E	SP	24" RC PIPE CULVERTS, CLASS III	260 LF		
0023	0384000000-E	SP	30" RC PIPE CULVERTS, CLASS III	108 LF		
0024	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	1,168 LF		
0025	0546000000-E	SP	*** CAA PIPE CULVERTS, ***** THICK (15", 0.060")	204 LF		
0026	0564000000-E	SP	*** CAA PIPE ELBOWS, ***** THICK (15", 0.060")	4 EA		
0027	0588000000-E	SP	18" CS PIPE CULVERTS, 0.064" THICK	220 LF		
0028	0594000000-E	SP	24" CS PIPE CULVERTS, 0.064" THICK	208 LF		
0029	0995000000-E	340	PIPE REMOVAL	480 LF		
0030	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0031	1000000000-E	462	6" SLOPE PROTECTION	220 SY		
0032	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0033	1110000000-E	510	STABILIZER AGGREGATE	4,000 TON		
0034	1121000000-E	520	AGGREGATE BASE COURSE	9,550 TON		
0035	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0036	1275000000-E	600	PRIME COAT	2,075 GAL		
0037	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,750 TON		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	6,750	TON	
0039	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,600	TON	
0040	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	7,250	TON	
0041	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,750	TON	
0042	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	6,400	TON	
0043	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,205	TON	
0044	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	385	TON	
0045	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200	TON	
0046	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	18,200	LF	
0047	2022000000-E	SP	SUBDRAIN EXCAVATION	84	CY	
0048	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	84	CY	
0049	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	500	LF	
0050	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
0051	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0052	2253000000-E	840	PIPE COLLARS	2	CY	
0053	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7	EA	
0054	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	3	EA	
0055	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4	EA	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	180 LF		
0057	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,390 SY		
0058	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	140 LF		
0059	2739000000-E	852	GENERIC PAVING ITEM 3" CONCRETE ISLAND COVER	25 SY		
0060	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0061	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0062	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0063	3030000000-E	862	STEEL BM GUARDRAIL	975 LF		
0064	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0065	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0066	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0067	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0068	3389200000-E	865	CABLE GUIDERAIL	4,450 LF		
0069	3389500000-N	SP	ADDITIONAL GUIDERAIL POSTS	5 EA		
0070	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	6 EA		
0071	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	770 LF		
0072	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	44 EA		
0073	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	30 EA		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	3628000000-E	876	RIP RAP, CLASS I	250	TON	
0075	3649000000-E	876	RIP RAP, CLASS B	25	TON	
0076	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,590	SY	
0077	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	10	CY	
0078	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1	CY	
0079	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	8,208	LB	
0080	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,170	LF	
0081	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	2	EA	
0082	4096000000-N	904	SIGN ERECTION, TYPE D	8	EA	
0083	4102000000-N	904	SIGN ERECTION, TYPE E	34	EA	
0084	4108000000-N	904	SIGN ERECTION, TYPE F	12	EA	
0085	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	6	EA	
0086	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	2	EA	
0087	4114000000-N	904	SIGN ERECTION, MILEMARKERS	2	EA	
0088	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	41	EA	
0089	4360000000-N	SP	GENERIC SIGNING ITEM DISPOSAL OF FLASHER SYSTEM	4	EA	
0090	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,247	SF	
0091	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	531	SF	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	284	SF	
0093	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4	EA	
0094	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	5	EA	
0095	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	10	DAY	
0096	4430000000-N	1130	DRUMS	225	EA	
0097	4435000000-N	1135	CONES	42	EA	
0098	4445000000-E	1145	BARRICADES (TYPE III)	288	LF	
0099	4450000000-N	1150	FLAGGER	2,000	HR	
0100	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4	EA	
0101	4480000000-N	1165	TMIA	2	EA	
0102	4485000000-E	1170	PORTABLE CONCRETE BARRIER	730	LF	
0103	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	240	LF	
0104	4510000000-N	SP	LAW ENFORCEMENT	240	HR	
0105	4516000000-N	1180	SKINNY DRUM	68	EA	
0106	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	612	EA	
0107	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	28,127	LF	
0108	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	7,551	LF	
0109	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	4,461	LF	
0110	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	55	LF	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	46 EA		
0112	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,232 LF		
0113	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	832 LF		
0114	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (III)	54 LF		
0115	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	81,639 LF		
0116	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	8,754 LF		
0117	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	470 LF		
0118	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	132 EA		
0119	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	6,577 LF		
0120	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	262 LF		
0121	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	19 EA		
0122	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	655 EA		
0123	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	30 EA		
0124	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	30 EA		
0125	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	10 EA		
0126	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	10 EA		
0127	5648000000-N	1515	RELOCATE WATER METER	1 EA		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0128	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0129	5709100000-E	1520	2" FORCE MAIN SEWER	70 LF		
0130	6000000000-E	1605	TEMPORARY SILT FENCE	32,750 LF		
0131	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,040 TON		
0132	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	4,930 TON		
0133	6012000000-E	1610	SEDIMENT CONTROL STONE	2,825 TON		
0134	6015000000-E	1615	TEMPORARY MULCHING	52.5 ACR		
0135	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	950 LB		
0136	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	4.75 TON		
0137	6024000000-E	1622	TEMPORARY SLOPE DRAINS	10,000 LF		
0138	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	150 EA		
0139	6029000000-E	SP	SAFETY FENCE	7,200 LF		
0140	6030000000-E	1630	SILT EXCAVATION	3,730 CY		
0141	6036000000-E	1631	MATTING FOR EROSION CONTROL	16,600 SY		
0142	6037000000-E	SP	COIR FIBER MAT	120 SY		
0143	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	820 SY		
0144	6042000000-E	1632	1/4" HARDWARE CLOTH	1,400 LF		
0145	6070000000-N	SP	SPECIAL STILLING BASINS	2 EA		
0146	6071010000-E	SP	WATTLE	2,330 LF		
0147	6071020000-E	SP	POLYACRYLAMIDE (PAM)	1,165 LB		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0148	6071030000-E	SP	COIR FIBER BAFFLES	2,500 LF		
0149	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0150	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0151	6084000000-E	1660	SEEDING & MULCHING	48 ACR		
0152	6087000000-E	1660	MOWING	40 ACR		
0153	6090000000-E	1661	SEED FOR REPAIR SEEDING	400 LB		
0154	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2 TON		
0155	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,125 LB		
0156	6108000000-E	1665	FERTILIZER TOPDRESSING	33.25 TON		
0157	6114500000-N	SP	SPECIALIZED HAND MOWING	50 MHR		
0158	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0159	6123000000-E	1670	REFORESTATION	1.5 ACR		
0160	6138000000-E	SP	GENERIC EROSION CONTROL ITEM BORROW PIT DEWATERING BASIN	58,200 CY		
0161	7060000000-E	1705	SIGNAL CABLE	840 LF		
0162	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	10 EA		
0163	7264000000-E	1710	MESSENGER CABLE (3/8")	620 LF		
0164	7300000000-E	1715	UNPAVED TRENCHING (***** (NO CONDUIT)	510 LF		
0165	7360000000-N	1720	WOOD POLE	4 EA		
0166	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0167	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0168	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0169	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,420 LF		
0170	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	2,290 LF		
0171	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0172	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	4 EA		
0173	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1 EA		
STRUCTURE ITEMS						
0174	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 32+50.00 -L-)	Lump Sum	L.S.	
0175	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	11,086 SF		
0176	8161000000-E	420	GROOVING BRIDGE FLOORS	12,083 SF		
0177	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	180.9 CY		
0178	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (32+50.00 -L-)	Lump Sum	L.S.	
0179	8217000000-E	425	REINFORCING STEEL (BRIDGE)	29,632 LB		
0180	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,602 LB		
0181	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	1,385.56 LF		
0182	8364000000-E	SP	HP12X53 STEEL PILES	4,305 LF		
0183	8393000000-N	SP	PILE REDRIVES	34 EA		
0184	8503000000-E	460	CONCRETE BARRIER RAIL	401.29 LF		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0185	8531000000-E	462	4" SLOPE PROTECTION	804 SY		
0186	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0187	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0924/Jul02/Q775534.75/D761562960000/E187			Total Amount Of Bid For Entire Project :			

Contract No **C202555**

County (ies): **Columbus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General