

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	660 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	155 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	29.56 SMI		
0005	1330000000-E	607	INCIDENTAL MILLING	4,770 SY		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	830 TON		
0007	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,415 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,075 TON		
0009	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	26,390 TON		
0010	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	454 TON		
0011	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,583 TON		
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,550 TON		
0013	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	139,400 LF		
0014	2612000000-E	848	6" CONCRETE DRIVEWAY	200 SY		
0015	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	15 EA		
0016	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0017	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	48 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	1,780	LF	
001E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	50,500	LF	
002C	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	144,000	LF	
0021	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	34,110	LF	
0022	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	161,430	LF	
0023	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (HIGHLY REFLECTIVE ELEMENTS)	500	LF	
0024	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)	3,000	LF	
002E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	172	EA	
002E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,280	EA	
0027	6000000000-E	1605	TEMPORARY SILT FENCE	1,150	LF	
002E	6071010000-E	SP	WATTLE	475	LF	
002E	6084000000-E	1660	SEEDING & MULCHING	21.39	ACR	
003C	6090000000-E	1661	SEED FOR REPAIR SEEDING	1,150	LB	
0031	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	4.75	TON	

**Contract No**     **C202608**

**County (ies):**   **Chatham**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General