

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0004	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0005	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0015000000-N	205	SEALING ABANDONED WELLS	3 EA		
0007	0022000000-E	225	UNCLASSIFIED EXCAVATION	307,760 CY		
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (33 + 30.00 -L-)	Lump Sum	L.S.	
0009	0036000000-E	225	UNDERCUT EXCAVATION	405 CY		
0010	0038000000-E	SP	SHALLOW UNDERCUT	50 CY		
0011	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	100 TON		
0012	0134000000-E	240	DRAINAGE DITCH EXCAVATION	120 CY		
0013	0141000000-E	240	BERM DITCH CONSTRUCTION	450 LF		
0014	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	6,720 SY		
0015	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	1,135 SY		
0016	0195000000-E	SP	SELECT GRANULAR MATERIAL	100 CY		
0017	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0018	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION AND STOCKPILING CONTAMINATED SOIL	50 TON		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	391	TON	
002C	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	750	SY	
0021	0973100000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** IN SOIL (60", 0.875", B)	66	LF	
0022	0973300000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** NOT IN SOIL (60", 0.875", B)	66	LF	
0023	0986000000-E	SP	GENERIC PIPE ITEM 16" DUCTILE IRON PIPE	30	LF	
0024	0986000000-E	SP	GENERIC PIPE ITEM 60" WELDED STEEL PIPE, 0.875" THICK, GRADE B	48	LF	
0025	0987000000-E	310	GENERIC PIPE ITEM 15" BIT COAT CS PIPE CULVERTS, TYPE B, 0.064" THICK	188	LF	
0026	0987000000-E	310	GENERIC PIPE ITEM 15" RC PIPE CULVERTS, CLASS III	268	LF	
0027	0987000000-E	310	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	176	LF	
0028	0987000000-E	310	GENERIC PIPE ITEM 18" RC PIPE CULVERTS, CLASS III	392	LF	
0029	0987000000-E	310	GENERIC PIPE ITEM 24" BIT COAT CS PIPE CULVERTS, TYPE B, 0.064" THICK	204	LF	
003C	0987000000-E	310	GENERIC PIPE ITEM 36" BIT COAT CS PIPE CULVERTS, TYPE B, 0.079" THICK	24	LF	
0031	0987000000-E	310	GENERIC PIPE ITEM 60" RC PIPE CULVERTS, CLASS IV	24	LF	
0032	0988000000-E	310	GENERIC PIPE ITEM 15" BIT COAT CS PIPE ELBOWS, TYPE B, 0.064" THICK	6	EA	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	0988000000-E	310	GENERIC PIPE ITEM 15" PIPE END SECTION	2 EA		
0034	0988000000-E	310	GENERIC PIPE ITEM 18" PIPE END SECTION	6 EA		
003E	0988000000-E	310	GENERIC PIPE ITEM 24" BIT COAT CS PIPE ELBOWS, TYPE B, 0.064 THICK	6 EA		
003E	0988000000-E	310	GENERIC PIPE ITEM 24" PIPE END SECTION	2 EA		
0037	0995000000-E	340	PIPE REMOVAL	667 LF		
003E	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0039	1121000000-E	520	AGGREGATE BASE COURSE	13,490 TON		
004C	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0041	1231000000-E	560	SHOULDER BORROW	5,400 CY		
0042	1275000000-E	600	PRIME COAT	633.5 GAL		
0043	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,050 TON		
0044	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	730 TON		
004E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,680 TON		
004E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	260 TON		
0047	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,830 TON		
004E	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	950 TON		
004E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	500 TON		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	632 TON		
0051	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	57 TON		
0052	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	295 TON		
0053	2022000000-E	SP	SUBDRAIN EXCAVATION	67 CY		
0054	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	50 CY		
005E	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	300 LF		
0056	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0057	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
005E	2264000000-E	840	PIPE PLUGS	0.784 CY		
0059	2275000000-E	SP	FLOWABLE FILL	50 CY		
006C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	16 EA		
0061	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	38.8 CY		
0062	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	22.02 LF		
0063	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.33)	4 EA		
0064	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2 EA		
006E	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
006E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	7 EA		
0067	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
006E	2462000000-E	SP	*** SLUICE GATE (15")	1 EA		
007C	2462000000-E	SP	*** SLUICE GATE (24")	1 EA		
0071	2535000000-E	846	***X *** CONCRETE CURB (9" x 18")	180 LF		
0072	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	260 LF		
0073	2556000000-E	846	SHOULDER BERM GUTTER	607 LF		
0074	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	491 LF		
007E	2619000000-E	850	4" CONCRETE PAVED DITCH	22 SY		
007E	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	402 SY		
0077	2738000000-E	SP	GENERIC PAVING ITEM 7" CONCRETE TRUCK APRON	271 SY		
007E	3030000000-E	862	STEEL BM GUARDRAIL	1,712.5 LF		
007E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	130 LF		
008C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0081	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0082	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0083	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0084	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,665 LF		
008E	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	715 LF		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	44	EA	
0087	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	14	EA	
008E	3557000000-E	866	ADDITIONAL BARBED WIRE	100	LF	
008E	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	900	LF	
009C	3635000000-E	876	RIP RAP, CLASS II	405	TON	
0091	3649000000-E	876	RIP RAP, CLASS B	470	TON	
0092	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,725	SY	
0093	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	958	LF	
0094	4096000000-N	904	SIGN ERECTION, TYPE D	7	EA	
009E	4102000000-N	904	SIGN ERECTION, TYPE E	60	EA	
009E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	3	EA	
0097	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	1	EA	
009E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	14	EA	
009E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2	EA	
010C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	551	SF	
0101	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	288	SF	
0102	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114	SF	
0103	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
010E	4430000000-N	1130	DRUMS	115 EA		
010E	4445000000-E	1145	BARRICADES (TYPE III)	400 LF		
0107	4450000000-N	1150	FLAGGER	2,800 HR		
010E	4480000000-N	1165	TMIA	2 EA		
010E	4516000000-N	1180	SKINNY DRUM	30 EA		
011C	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	145 EA		
0111	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	148,832 LF		
0112	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	638 LF		
011E	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	140 LF		
0114	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	946 LF		
011E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	142 EA		
011E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	98 EA		
0117	5325000000-E	1510	*** WATER LINE (1-1/2")	193 LF		
011E	5326000000-E	1510	10" WATER LINE	2,481 LF		
011E	5552000000-E	1515	10" VALVE	4 EA		
012C	5589100000-E	1515	1" AIR RELEASE VALVE	3 EA		
0121	5666000000-M	1515	FIRE HYDRANT	3 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	5709000000-E	1520	*** FORCE MAIN SEWER (3")	193	LF	
0123	5709200000-E	1520	4" FORCE MAIN SEWER	1,231	LF	
0124	5802000000-E	1530	ABANDON 10" UTILITY PIPE	1,082	LF	
012E	5835000000-E	1540	*** ENCASEMENT PIPE (4")	75	LF	
012E	5835400000-E	1540	6" ENCASEMENT PIPE	75	LF	
0127	6000000000-E	1605	TEMPORARY SILT FENCE	16,000	LF	
012E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,350	TON	
012E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	4,700	TON	
013C	6012000000-E	1610	SEDIMENT CONTROL STONE	2,600	TON	
0131	6015000000-E	1615	TEMPORARY MULCHING	52	ACR	
0132	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,100	LB	
0133	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	6.25	TON	
0134	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,500	LF	
013E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	50	EA	
013E	6029000000-E	SP	SAFETY FENCE	1,500	LF	
0137	6030000000-E	1630	SILT EXCAVATION	8,250	CY	
013E	6036000000-E	1631	MATTING FOR EROSION CONTROL	100,000	SY	
013E	6037000000-E	SP	COIR FIBER MAT	75	SY	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014C	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	14,760 SY		
0141	6042000000-E	1632	1/4" HARDWARE CLOTH	1,910 LF		
0142	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0143	6071010000-E	SP	WATTLE	315 LF		
0144	6071020000-E	SP	POLYACRYLAMIDE (PAM)	360 LB		
0145	6071030000-E	SP	COIR FIBER BAFFLES	5,000 LF		
0146	6071050000-E	SP	*** SKIMMER (1-1/2")	6 EA		
0147	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0148	6084000000-E	1660	SEEDING & MULCHING	45 ACR		
0149	6087000000-E	1660	MOWING	48 ACR		
015C	6090000000-E	1661	SEED FOR REPAIR SEEDING	400 LB		
0151	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.5 TON		
0152	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,075 LB		
0153	6108000000-E	1665	FERTILIZER TOPDRESSING	31.75 TON		
0154	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
015E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0156	6123000000-E	1670	REFORESTATION	0.5 ACR		
0157	7060000000-E	1705	SIGNAL CABLE	3,700 LF		
015E	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	16 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
015E	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	2 EA		
016C	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0161	7264000000-E	1710	MESSENGER CABLE (3/8")	320 LF		
0162	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	730 LF		
0163	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	380 LF		
0164	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	4 EA		
016E	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	4 EA		
016E	7360000000-N	1720	WOOD POLE	1 EA		
0167	7372000000-N	1721	GUY ASSEMBLY	2 EA		
016E	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1 EA		
016E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,060 LF		
017C	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	1,690 LF		
0171	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	4 EA		
0172	7613000000-N	SP	SOIL TEST	4 EA		
0173	7614100000-E	SP	DRILLED PIER FOUNDATION	20 CY		
0174	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	4 EA		
017E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	2 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
017E AA1	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	732	LF	
0177 AA1	0987000000-E	310	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	188	LF	
*** OR ***						
017E AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	224	LF	
017E AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.079")	132	LF	
018C AA2	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	508	LF	
0181 AA2	0987000000-E	310	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	56	LF	
*** OR ***						
0182 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	224	LF	
0183 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	132	LF	
0184 AA3	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	508	LF	
018E AA3	0987000000-E	310	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	56	LF	
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
018E	8105500000-E	SP	***_*** DIA DRILLED PIERS IN SOIL (5'-6")	104.17	LF	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0187	8105600000-E	SP	***'-***" DIA DRILLED PIERS NOT IN SOIL (5'-6")	61 LF		
018E	8111000000-E	SP	PERMANENT STEEL CASING FOR ***'-***" DIA DRILLED PIER (5'-6")	63.97 LF		
018E	8113000000-N	SP	SID INSPECTION	1 EA		
019C	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0191	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	18,598 SF		
0192	8161000000-E	420	GROOVING BRIDGE FLOORS	16,639 SF		
0193	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	293.9 CY		
0194	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (33+30.00-L-)	Lump Sum	L.S.	
019E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	59,041 LB		
019E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	12,153 LB		
0197	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	955,300 LS		
019E	8364000000-E	SP	HP12X53 STEEL PILES	1,175 LF		
019E	8503000000-E	460	CONCRETE BARRIER RAIL	1,055.41 LF		
020C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	4,033 TON		
0201	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	4,481 SY		
0202	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0203	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0204	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
020E	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (33+30.00-L-)	Lump Sum	L.S.	
020E	8860000000-N	SP	GENERIC STRUCTURE ITEM INSTALL 10" D.I.R.J. WATER MAI N	Lump Sum	L.S.	
			1032/Aug12/Q1776054.554/D819100260000/E206	Total Amount Of Bid For Entire Project :		

Contract No **C202556**

County (ies): **Macon**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General