

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	8,850 CY		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (54 + 63.6 RT)	Lump Sum	L.S.	
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (54 + 67.22 LT)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (58 + 92.53 LT)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (58 + 93.75 RT)	Lump Sum	L.S.	
0009	0036000000-E	225	UNDERCUT EXCAVATION	4,430 CY		
0010	0038000000-E	SP	SHALLOW UNDERCUT	5,859 CY		
0011	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	20,465 TON		
0012	0106000000-E	230	BORROW EXCAVATION	336,350 CY		
0013	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2,610 CY		
0014	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	3,420 SY		
0015	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	210 SY		
0016	0195000000-E	SP	SELECT GRANULAR MATERIAL	4,140 CY		
0017	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	36,250 SY		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0241000000-E	SP	GENERIC GRADING ITEM PERMANENT TURF REINFORCEMENT MAT	4,580	SY	
001E	0241000000-E	SP	GENERIC GRADING ITEM PRIMARY GEOGRID REINFORCEMENT	8,180	SY	
002C	0241000000-E	SP	GENERIC GRADING ITEM SECONDARY GEOGRID REINFORCE- MENT	3,880	SY	
0021	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,273	TON	
0022	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	2,600	SY	
0023	0973100000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** IN SOIL (60", 0.875", B)	80	LF	
0024	0973300000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** NOT IN SOIL (60", 0.875", B)	80	LF	
002E	0987000000-E	310	GENERIC PIPE ITEM 15" CS PIPE CULVERTS, 0.064" THICK	408	LF	
002E	0987000000-E	310	GENERIC PIPE ITEM 15" RC PIPE CULVERTS, CLASS III	3,644	LF	
0027	0987000000-E	310	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	48	LF	
002E	0987000000-E	310	GENERIC PIPE ITEM 18" CS PIPE CULVERTS, 0.064" THICK	100	LF	
002E	0987000000-E	310	GENERIC PIPE ITEM 18" RC PIPE CULVERTS, CLASS III	1,088	LF	
003C	0987000000-E	310	GENERIC PIPE ITEM 18" RC PIPE CULVERTS, CLASS IV	284	LF	
0031	0987000000-E	310	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	192	LF	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0032	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	904 LF		
0033	0987000000-E	310	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	864 LF		
0034	0987000000-E	310	GENERIC PIPE ITEM 36" RC PIPE CULVERTS, CLASS III	24 LF		
003E	0987000000-E	310	GENERIC PIPE ITEM 42" RC PIPE CULVERTS, CLASS III	68 LF		
003E	0987000000-E	310	GENERIC PIPE ITEM 42" RC PIPE CULVERTS, CLASS IV	212 LF		
0037	0987000000-E	310	GENERIC PIPE ITEM 60" RC PIPE CULVERTS, CLASS III	28 LF		
003E	0987000000-E	310	GENERIC PIPE ITEM 66" RC PIPE CULVERTS, CLASS III	24 LF		
003E	0988000000-E	310	GENERIC PIPE ITEM 15" CS PIPE ELBOWS, 0.064" THICK	9 EA		
004C	0988000000-E	310	GENERIC PIPE ITEM 18" CS PIPE ELBOWS, 0.064" THICK	1 EA		
0041	0995000000-E	340	PIPE REMOVAL	2,241 LF		
0042	1000000000-E	462	6" SLOPE PROTECTION	162 SY		
004E	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0044	1220000000-E	545	INCIDENTAL STONE BASE	3,500 TON		
004E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	14,100 TON		
004E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	12,780 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0047	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,250 TON		
004E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,825 TON		
004E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	500 TON		
005C	2000000000-N	806	RIGHT OF WAY MARKERS	46 EA		
0051	2022000000-E	SP	SUBDRAIN EXCAVATION	168 CY		
0052	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	84 CY		
005C	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	500 LF		
0054	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
005E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
005E	2209000000-E	838	ENDWALLS	7.82 CY		
0057	2220000000-E	838	REINFORCED ENDWALLS	11.9 CY		
005E	2253000000-E	840	PIPE COLLARS	10.17 CY		
005E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	90 EA		
006C	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	4.739 CY		
0061	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	36.15 LF		
0062	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	34 EA		
006C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	34 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	19 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	2396000000-N	840	FRAME WITH COVER, STD 840.54	1		EA
006E	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	4		EA
0067	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	17		EA
006E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	6,390		LF
006E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	13,920		LF
007C	2556000000-E	846	SHOULDER BERM GUTTER	240		LF
0071	2591000000-E	848	4" CONCRETE SIDEWALK	6,300		SY
0072	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	28		EA
007E	2612000000-E	848	6" CONCRETE DRIVEWAY	260		SY
0074	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	2,620		SY
007E	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1		EA
007E	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2		EA
0077	3030000000-E	862	STEEL BM GUARDRAIL	5,662.5		LF
007E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	487.5		LF
007E	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	4		EA
008C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0081	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	3		EA
0082	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8		EA

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0083	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9	EA	
0084	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8	EA	
008E	3628000000-E	876	RIP RAP, CLASS I	105	TON	
008E	3649000000-E	876	RIP RAP, CLASS B	150	TON	
0087	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,220	SY	
008E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
008E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	2,075	LF	
009C	4096000000-N	904	SIGN ERECTION, TYPE D	7	EA	
0091	4102000000-N	904	SIGN ERECTION, TYPE E	56	EA	
0092	4108000000-N	904	SIGN ERECTION, TYPE F	13	EA	
0093	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1	EA	
0094	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	54	EA	
009E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	8	EA	
009E	4237000000-N	907	STOCKPILE SIGN, D, E OR F	12	EA	
0097	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,647	SF	
009E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	746	SF	
009E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	242	SF	
010C	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0101	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	3	EA	
0102	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	18	DAY	
0103	4430000000-N	1130	DRUMS	250	EA	
0104	4435000000-N	1135	CONES	75	EA	
0105	4445000000-E	1145	BARRICADES (TYPE III)	216	LF	
0106	4455000000-N	1150	FLAGGER	1,250	MD	
0107	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6	EA	
0108	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
0109	4480000000-N	1165	TMIA	2	EA	
0110	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	1,260	LF	
0111	4506000000-E	1170	RESET PORTABLE CONCRETE BARRIER (DRAINAGE)	720	LF	
0112	4516000000-N	1180	SKINNY DRUM	75	EA	
0113	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM WARNING FLAGS	34	EA	
0114	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	558	EA	
0115	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,402	LF	
0116	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	21,905	LF	
0117	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	993	LF	
0118	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	431	LF	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
011E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	2 EA		
012C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	50 EA		
0121	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	760 LF		
0122	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	2,679 LF		
0123	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	115,929 LF		
0124	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	272 LF		
012E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	668 LF		
0126	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	16 EA		
0127	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	242 EA		
012E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	12,625 LF		
012E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	174 LF		
013C	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	14 EA		
0131	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	205 EA		
0132	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	260 EA		
0133	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
0134	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		



County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
013E	5325200000-E	1510	2" WATER LINE	6 LF		
013E	5325600000-E	1510	6" WATER LINE	4,178 LF		
0137	5536000000-E	1515	2" VALVE	2 EA		
013E	5540000000-E	1515	6" VALVE	7 EA		
013E	5648000000-N	1515	RELOCATE WATER METER	20 EA		
014C	5672000000-N	1515	RELOCATE FIRE HYDRANT	4 EA		
0141	5882000000-N	SP	GENERIC UTILITY ITEM ADJUST MANHOLE	14 EA		
0142	6000000000-E	1605	TEMPORARY SILT FENCE	10,000 LF		
0143	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	2,225 TON		
0144	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	8,500 TON		
014E	6012000000-E	1610	SEDIMENT CONTROL STONE	6,000 TON		
014E	6015000000-E	1615	TEMPORARY MULCHING	40 ACR		
0147	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	700 LB		
014E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	4.75 TON		
014E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	5,000 LF		
015C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	100 EA		
0151	6029000000-E	SP	SAFETY FENCE	460 LF		
0152	6030000000-E	1630	SILT EXCAVATION	13,000 CY		
0153	6036000000-E	1631	MATTING FOR EROSION CONTROL	31,000 SY		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0154	6037000000-E	SP	COIR FIBER MAT	100 SY		
015E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	950 SY		
015E	6042000000-E	1632	1/4" HARDWARE CLOTH	9,200 LF		
0157	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
015E	6071010000-E	SP	WATTLE	2,250 LF		
015E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	850 LB		
016C	6071030000-E	SP	COIR FIBER BAFFLES	4,000 LF		
0161	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0162	6084000000-E	1660	SEEDING & MULCHING	70 ACR		
016E	6087000000-E	1660	MOWING	66 ACR		
0164	6090000000-E	1661	SEED FOR REPAIR SEEDING	300 LB		
016E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2.25 TON		
016E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,275 LB		
0167	6108000000-E	1665	FERTILIZER TOPDRESSING	38.25 TON		
016E	6114500000-N	SP	SPECIALIZED HAND MOWING	25 MHR		
016E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
017C	6123000000-E	1670	REFORESTATION	0.5 ACR		
0171	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/ COUNTDOWN)	8 EA		
0172	7060000000-E	1705	SIGNAL CABLE	4,130 LF		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0173	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	15	EA	
0174	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	3	EA	
0175	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2	EA	
0176	7264000000-E	1710	MESSENGER CABLE (3/8")	730	LF	
0177	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	260	LF	
0178	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	340	LF	
0179	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	260	LF	
0180	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	5	EA	
0181	7360000000-N	1720	WOOD POLE	8	EA	
0182	7372000000-N	1721	GUY ASSEMBLY	14	EA	
0183	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	2	EA	
0184	7408000000-E	1722	1" RISER WITH WEATHERHEAD	4	EA	
0185	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3	EA	
0186	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,650	LF	
0187	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	3,630	LF	
0188	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	2	EA	
0189	7613000000-N	SP	SOIL TEST	2	EA	
0190	7614100000-E	SP	DRILLED PIER FOUNDATION	16	CY	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0191	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	2	EA	
0192	7636000000-N	1745	SIGN FOR SIGNALS	1	EA	
0193	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2	EA	
0194	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2	EA	
0195	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	13	EA	
0196	7901000000-N	1753	CABINET BASE EXTENDER	2	EA	
0197	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	3	EA	
0198	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	2	EA	
0199	7972000000-N	SP	METAL POLE REMOVAL	2	EA	

**STRUCTURE ITEMS**

020C	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 54 + 69.91-L-LT)	Lump Sum	L.S.	
0201	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 54 + 69.91-L-RT)	Lump Sum	L.S.	
0202	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 54 + 69.91-L-LT)	Lump Sum	L.S.	
0203	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 54 + 69.91-L-RT)	Lump Sum	L.S.	
0204	8112730000-N	SP	PDA TESTING	2	EA	
0205	8112740000-N	SP	PDA ASSISTANCE	2	EA	
0206	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	28,504	SF	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0207	8161000000-E	420	GROOVING BRIDGE FLOORS	23,936 SF		
020E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	428.2 CY		
020E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (54 + 69.91-L-LT)	Lump Sum	L.S.	
021C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (54 + 69.91-L-RT)	Lump Sum	L.S.	
0211	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (58 + 97.14-L-LT)	Lump Sum	L.S.	
0212	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (58 + 97.14-L-RT)	Lump Sum	L.S.	
021E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	59,452 LB		
0214	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,652 LB		
021E	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	1,014,800 LS		
021E	8364000000-E	SP	HP12X53 STEEL PILES	7,850 LF		
0217	8393000000-N	SP	PILE REDRIVES	56 EA		
021E	8482000000-E	460	THREE BAR METAL RAIL	751.96 LF		
021E	8503000000-E	460	CONCRETE BARRIER RAIL	782.76 LF		
022C	8524000000-E	SP	*** CHAIN LINK FENCE (104")	422 LF		
0221	8531000000-E	462	4" SLOPE PROTECTION	2,575 SY		
0222	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0223	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
<hr/>						
1102/Sep07/Q1963759.449/D976356580000/E223			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202557**

**County (ies):**   **Alamance**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General