

County : Bertie, Hertford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	360 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	605 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	16.38 SMI		
000E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	2,400 SY		
000E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1" TO 1-1/2")	9,335 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3-1/2")	17,750 SY		
000E	1330000000-E	607	INCIDENTAL MILLING	625 SY		
000E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,024 TON		
001C	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	12,250 TON		
0011	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	1,530 TON		
0012	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	13,863 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,825 TON		
0014	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	350 TON		
001E	2830000000-N	858	ADJUSTMENT OF MANHOLES	6 EA		
001E	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	4 EA		

County : Bertie, Hertford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
001E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	92,664 LF		
001S	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	58,826 LF		
002C	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	150 LF		
0021	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	4 EA		
0022	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	14 EA		
0023	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	104 LF		
0024	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	333,112 LF		
002E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	565 EA		
002E	6000000000-E	1605	TEMPORARY SILT FENCE	500 LF		
0027	6036000000-E	1631	MATTING FOR EROSION CONTROL	64 SY		
002E	6071010000-E	SP	WATTLE	160 LF		
002S	6071020000-E	SP	POLYACRYLAMIDE (PAM)	14 LB		
003C	6084000000-E	1660	SEEDING & MULCHING	12 ACR		
0031	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	520 LF		
0032	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	100 LF		

**Contract No**     **C202629**

**County (ies):**   **Bertie & Hertford**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**