

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	2,145 CY		
0003	0234000000-E	SP	GENERIC GRADING ITEM BORROW EXCAVATION (STATE FURNISHED SOURCES)	1,834 CY		
0004	0257000000-E	SP	GENERIC GRADING ITEM 2'-6" CURB & GUTTER, REMOVE AND REPLACE	50 LF		
0005	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	12 TON		
0006	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	35 SY		
0007	0335300000-E	SP	18" DRAINAGE PIPE	62 LF		
0008	0335400000-E	SP	24" DRAINAGE PIPE	40 LF		
0009	1220000000-E	545	INCIDENTAL STONE BASE	2,200 TON		
0010	1245000000-E	SP	SHOULDER RECONSTRUCTION	35.8 SMI		
0011	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	13,771 SY		
0012	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	13,165 SY		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	240,566 SY		
0014	1330000000-E	607	INCIDENTAL MILLING	2,935 SY		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	14,342 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	38,024 TON		

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	33,729 TON		
001E	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	100 TON		
001S	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,434 TON		
002C	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	150 TON		
0021	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	935 TON		
002Z	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
002Z	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3 LF		
0024	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
002E	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	12 EA		
002E	2738000000-E	SP	GENERIC PAVING ITEM INCIDENTAL CONCRETE	675 SY		
0027	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
002E	2815000000-N	858	ADJUSTMENT OF DROP INLETS	5 EA		
002S	2830000000-N	858	ADJUSTMENT OF MANHOLES	19 EA		
003C	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	14 EA		
0031	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING DROP INLET TO TRAFFIC BEARING JUNCTION BOX	3 EA		
003Z	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	244,043 LF		

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	194,293	LF	
0034	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	800	LF	
003E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	50	LF	
003E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	315	LF	
0037	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	14	EA	
003E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	45	EA	
0039	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	438,153	LF	
004C	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	700	LF	
0041	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	50	LF	
0042	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	315	LF	
0043	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	14	EA	
0044	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	45	EA	
004E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,429	EA	
004E	6000000000-E	1605	TEMPORARY SILT FENCE	2,978	LF	
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,068	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	420	TON	
0049	6015000000-E	1615	TEMPORARY MULCHING	29.78	ACR	

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,491	LB	
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	7.44	TON	
0052	6036000000-E	1631	MATTING FOR EROSION CONTROL	320	SY	
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	1,491	LF	
0054	6084000000-E	1660	SEEDING & MULCHING	26.69	ACR	
005E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	700	LF	
005E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	100	LF	

0826/Sep30/Q1258203.71/D183467800000/E56

Total Amount Of Bid For Entire Project :

Contract No **C202625**

County (ies): **Duplin & Sampson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General