

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (17+88.50)	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	225 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	425 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	250 CY		
0009	0195000000-E	SP	SELECT GRANULAR MATERIAL	450 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	450 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	200 SF		
0012	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	50 TON		
0013	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	150 SY		
0014	0335200000-E	SP	15" DRAINAGE PIPE	116 LF		
001E	0335300000-E	SP	18" DRAINAGE PIPE	80 LF		
0016	0343000000-E	SP	15" SIDE DRAIN PIPE	32 LF		
0017	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	68 LF		
001E	0654000000-E	SP	**** X **** CS PIPE ARCH CULVERTS, ***** THICK (53" X 41", 0.109")	136 LF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0995000000-E	340	PIPE REMOVAL	134		LF
002C	1121000000-E	520	AGGREGATE BASE COURSE	613		TON
0021	1220000000-E	545	INCIDENTAL STONE BASE	300		TON
0022	1275000000-E	600	PRIME COAT	450		GAL
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	575		TON
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	265		TON
002E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	520		TON
002E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	71		TON
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25		TON
002E	2000000000-N	806	RIGHT OF WAY MARKERS	21		EA
002E	2022000000-E	SP	SUBDRAIN EXCAVATION	140		CY
003C	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	105		CY
0031	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	600		LF
0032	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	2		EA
0033	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	12		LF
0034	2209000000-E	838	ENDWALLS	9		CY
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4		EA
003E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1		EA

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
003E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
003E	2556000000-E	846	SHOULDER BERM GUTTER	35 LF		
004C	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0041	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0042	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
004E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0044	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
004E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
004E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	225 LF		
0047	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	25 LF		
004E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	1 EA		
004E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4 EA		
005C	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	3 EA		
0051	3566000000-E	867	WOVEN WIRE FENCE RESET	335 LF		
0052	3628000000-E	876	RIP RAP, CLASS I	60 TON		
005E	3635000000-E	876	RIP RAP, CLASS II	75 TON		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3649000000-E	876	RIP RAP, CLASS B	40 TON		
005E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,205 SY		
005E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	27 LF		
0057	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
005E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8 EA		
005E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	209 SF		
006C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0061	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	55 SF		
0062	4430000000-N	1130	DRUMS	15 EA		
006E	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0064	4450000000-N	1150	FLAGGER	160 HR		
006E	4609000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC SIGNAL SYSTEM	300 DAY		
006E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	15 EA		
0067	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,638 LF		
006E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,678 LF		
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	17,160 LF		
007C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	45 LF		
0071	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	20	EA	
0073	6000000000-E	1605	TEMPORARY SILT FENCE	5,300	LF	
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	560	TON	
007E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180	TON	
007E	6012000000-E	1610	SEDIMENT CONTROL STONE	470	TON	
0077	6015000000-E	1615	TEMPORARY MULCHING	5	ACR	
007E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
007E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5	TON	
008C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0081	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0082	6029000000-E	SP	SAFETY FENCE	2,200	LF	
008E	6030000000-E	1630	SILT EXCAVATION	450	CY	
0084	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,500	SY	
008E	6037000000-E	SP	COIR FIBER MAT	490	SY	
008E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	80	SY	
0087	6042000000-E	1632	1/4" HARDWARE CLOTH	2,000	LF	
008E	6071030000-E	SP	COIR FIBER BAFFLES	350	LF	
008E	6071050000-E	SP	*** SKIMMER (1-1/2")	6	EA	
009C	6084000000-E	1660	SEEDING & MULCHING	5	ACR	

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6087000000-E	1660	MOWING	3.5 ACR		
0092	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0093	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0094	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
009E	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
009E	6114500000-N	SP	SPECIALIZED HAND MOWING	12 MHR		
0097	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
009E	6123000000-E	1670	REFORESTATION	0.5 ACR		
009E	6126000000-E	SP	STREAMBANK REFORESTATION	0.2 ACR		
STRUCTURE ITEMS						
010C	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (17+88.50-L-)	Lump Sum	L.S.	
0101	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+88.50-L-)	Lump Sum	L.S.	
0102	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+88.50-L-)	Lump Sum	L.S.	
0103	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	44.5 CY		
0104	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+88.50-L-)	Lump Sum	L.S.	
010E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,528 LB		
010E	8364000000-E	SP	HP12X53 STEEL PILES	1,183 LF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8475000000-E	460	TWO BAR METAL RAIL	147.945 LF		
0108	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-8")	164.792 LF		
0109	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	340 TON		
0110	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	380 SY		
0111	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0112	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	988.75 LF		
0904/Nov15/Q62124.687/D445750580000/E112			Total Amount Of Bid For Entire Project :			

Contract No **C202326**

County (ies): **Buncombe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General