

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	300 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	480 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	14.9 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	11,960 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 2-1/2")	9,300 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")	9,500 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	1,200 SY		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,620 TON		
001C	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	12,650 TON		
0011	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	12,090 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,728 TON		
0013	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	400 TON		
0014	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S4.75A (LEVELING COURSE)	360 TON		
001E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	300 LF		
0016	2591000000-E	848	4" CONCRETE SIDEWALK	54 SY		

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	4 EA		
001E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	10 EA		
001E	2830000000-N	858	ADJUSTMENT OF MANHOLES	44 EA		
002C	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	35 EA		
0021	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0022	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	81,900 LF		
0023	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	51,350 LF		
0024	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	400 LF		
002E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	100 LF		
002E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
0027	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2 EA		
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	329,262 LF		
002E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	548 EA		
003C	6000000000-E	1605	TEMPORARY SILT FENCE	500 LF		
0031	6036000000-E	1631	MATTING FOR EROSION CONTROL	64 SY		
0032	6071012000-E	SP	COIR FIBER WATTLE	160 LF		
0033	6071020000-E	SP	POLYACRYLAMIDE (PAM)	14 LB		

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	6084000000-E	1660	SEEDING & MULCHING	10.9	ACR	

0908/Nov03/Q528374.8/D106285132000/E34

Total Amount Of Bid For Entire Project :

Contract No **C202642**

County (ies): **Northampton**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General