

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	1,817 CY		
0003	0234000000-E	SP	GENERIC GRADING ITEM BORROW EXCAVATION (STATE FURNISHED SOURCES)	3,601 CY		
0004	1220000000-E	545	INCIDENTAL STONE BASE	980 TON		
0005	1245000000-E	SP	SHOULDER RECONSTRUCTION	22.26 SMI		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	157,157 SY		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	24,693 SY		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	77,228 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	13,644 SY		
0010	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,790 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	46,217 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	11,397 TON		
0013	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	630 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	470 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,981 TON		
0016	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	724 TON		
0017	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	2,850 LF		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	905 TON		
0019	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	3,565 TON		
0020	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0021	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0022	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0023	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	58 EA		
0024	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	5 EA		
0025	2738000000-E	SP	GENERIC PAVING ITEM REMOVE & REPLACE 5' SIDEWALK	47 SY		
0026	2739000000-E	852	GENERIC PAVING ITEM INCIDENTAL CONCRETE	80 SY		
0027	2752000000-E	SP	GENERIC PAVING ITEM 2'-6" CURB & GUTTER, REMOVE & REPLACE	430 LF		
0028	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	6 EA		
0029	2830000000-N	858	ADJUSTMENT OF MANHOLES	88 EA		
0030	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	82 EA		
0031	2850000000-N	858	GENERIC DRAINAGE ITEM ADJUSTMENT OF MONUMENTS	9 EA		
0032	3030000000-E	862	STEEL BM GUARDRAIL	6,687.5 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	6 EA		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3360000000-E	863	REMOVE EXISTING GUARDRAIL	6,800 LF		
0036	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	106,857 LF		
0038	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	173,611 LF		
0039	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,358 LF		
0040	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	882 LF		
0041	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	150 LF		
0042	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,229 LF		
0043	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	50 EA		
0044	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	577 EA		
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	377,793 LF		
0046	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,110 LF		
0047	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	200 LF		
0048	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,383 LF		
0049	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	40 EA		
0050	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	472 EA		
0051	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	4,250 LF		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,800 LF		
0053	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	100 LF		
0054	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	800 LF		
0055	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	46 EA		
0056	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	798 EA		
0057	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	3,320 EA		
0058	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0059	6000000000-E	1605	TEMPORARY SILT FENCE	2,200 LF		
0060	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	519 TON		
0061	6012000000-E	1610	SEDIMENT CONTROL STONE	716 TON		
0062	6015000000-E	1615	TEMPORARY MULCHING	25.81 ACR		
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	180 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	841 LF		
0065	6071010000-E	SP	WATTLE	310 LF		
0066	6084000000-E	1660	SEEDING & MULCHING	16.52 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	1,294 LB		
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	6.47 TON		
0069	7060000000-E	1705	SIGNAL CABLE	1,250 LF		
0070	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	6 EA		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	6 EA		
0072	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,100 LF		
0073	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	38 EA		
0074	7420000000-E	1722	2" RISER WITH WEATHERHEAD	12 EA		
0075	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	17,042 LF		
0076	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	15,885 LF		
1340/Jan12/Q1085256.56/D298279110000/E76			Total Amount Of Bid For Entire Project :			

**Contract No**      **C202680**

**County (ies):**    **Brunswick, New Hanover, Pender**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General