


PROJECT SPECIAL PROVISIONS
Utility Construction



Revise the *2006 Standard Specifications* as follows:

Utility Owners' Contact Information:

Page 15-1, Subarticle 1500-2 Cooperation with the Utility Owner, paragraph 2, add the following sentences:

City of Sanford is owner of the 12" water facilities. The contractor must contact the owner before any work begins. .
The contact person is Michael Lamping (Phone: 919-775-8233)

Page 15-3, Subarticle 1500-9 Placing Pipelines Into Service:

Paragraph 2:

Delete: "Schedule and notify owners and customers in advance of any interruptions of water service with ample time to make arrangements. Provide temporary connections as needed."

Paragraph 2:

Change: "Limit of interruption of service to water customers to a maximum of 8 hours unless otherwise required or approved."

To: "No. interruption of service to water customers."

Page 15-9, Subarticle 1515-2 Materials, add the following sentences:

In addition to the water line materials specified under Section 1036, the water line can be High Density Polyethylene (HDPE) pipe conforming to AWWA C906 with an SDR of 9 and pressure rating of 200 # WP.

The proposed utility construction shall meet the applicable requirements (i.e. material specifications, standard details, testing, policies, etc.) of the NCDOT's "Standard Specifications for Roads and Structures" (dated July, 2006).

11/15/2011

County: Lee
Project: R-2417AA**PROJECT SPECIAL PROVISIONS****UTILITIES BY OTHERS:****General:**

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) CENTRAL ELECTRIC MEMBERSHIP CORPORATION-POWER
- B) PROGRESS ENERGY-POWER
- C) WINDSTREAM-TELEPHONE
- D) CITY OF SANFORD-ENCASEMENTS FOR FUTURE USE

The conflicting facilities of these concerns will be adjusted prior to the date of availability unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A) Central EMC
Central EMC will remove the poles in conflict by date of availability.
After the completion of -L- line between Sta. 146+00 to Sta. 149+00. They will need two weeks notice and two weeks to reinstall the service line.
See Utilities by Others Plans for details.
Contact: Eddie Oldham-Central EMC- Office: (919) 774-4900
- B) Progress Energy
Progress Energy will relocate the aerial power line and will complete by May 1, 2011. See Utilities By others Plans for details.
Contact: JB Jones-Progress Energy-Office: (919) 481-6153
- C) Windstream
Windstream will complete the relocation of the telephone line by date of availability.
See Utilities By others Plans for details
- D) City of Sanford
City of Sanford will install the encasements by date of availability.
See Utilities By others Plans for details