

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	6,120 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	1,055 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	40.8 SMI		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	1,843 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	12,000 SY		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	19,565 TON		
0008	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	5,430 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,527 TON		
0010	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	4 EA		
0011	2830000000-N	858	ADJUSTMENT OF MANHOLES	21 EA		
0012	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	16 EA		
0013	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	889,106 LF		
0014	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	200 LF		
0015	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	386 LF		
0016	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	20 EA		
0017	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	60 EA		
0018	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	903 EA		

County : Surry, Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	6084000000-E	1660	SEEDING & MULCHING	24.48	ACR	
0020	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,025	LF	
1240/Jan12/Q939347.28/D60859100000/E20			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202711**

**County (ies):**   **Surry, Yadkin**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General