



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE  
GOVERNOR

EUGENE A. CONTI, JR.  
SECRETARY

March 3, 2011

**Addendum No. 1**

RE: Contract ID C202242

WBS # 34440.3.6

F. A. # NHF-0017(87)

**Beaufort County (R-2510C)**

US-17 From North of SR-1509 (Springs Road) To North of NC-171

**March 15, 2011 Letting**

To Whom It May Concern:

Reference is made to the proposal furnished to you on this project.

The following revision has been made to the Proposal:

On Page No. 37 the project special provision entitled "Select Granular Material" has been revised to change the first sentence under "265-3 Construction Methods". Please void Page No. 37 in your proposal and staple the revised Page No. 37 thereto.

Sincerely,

A handwritten signature in black ink, appearing to read "R. A. Garriss".

R. A. Garriss, PE  
Contract Officer

RAG/jag  
Attachments

cc: Mr. Jon Nance, PE  
Mr. Ron Hancock, PE  
Mr. C. E. Lassiter, PE  
Ms. D. M. Barbour, PE  
Mr. Art McMillan, PE  
Mr. J. V. Barbour, PE  
Project File (2)

Mr. R.E. Davenport, PE  
Ms. Natalie Roskam, PE  
Mr. Larry Strickland  
Mr. Ronnie Higgins  
Ms. Marsh Sample  
Ms. Lori Strickland

**MAILING ADDRESS:**  
NC DEPARTMENT OF TRANSPORTATION  
CONTRACT STANDARDS AND DEVELOPMENT UNIT  
1591 MAIL SERVICE CENTER  
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128  
FAX: 919-250-4119  
WEBSITE: [www.NCDOT.ORG](http://www.NCDOT.ORG)

**LOCATION:**  
CENTURY CENTER COMPLEX  
ENTRANCE B-2  
1020 BIRCH RIDGE DRIVE  
RALEIGH NC 27610

**265-2 Materials**

Refer to Division 10 of the *Standard Specifications*.

<b>Item</b>	<b>Section</b>
Select Material, Class III	1016

**265-3 Construction Methods**

Use material for embankment in water.

Place select granular material to 3 ft above fabric and water level.

**265-4 Measurement and Payment**

Select granular material will be paid for as *Select Granular Material, Class III*.

Select granular material will be measured by in place measurement in accordance with Article 230-5 of the *Standard Specifications* or by weighing material in trucks in accordance with Article 106-7 of the *Standard Specifications* as determined by the Engineer. When select granular material is weighed in trucks, a unit weight of 135 pcf will be used to convert the weight of select granular material to cubic yards. At the Engineer's discretion, truck measurement in accordance with Article 230-5 of the *Standard Specifications* may be used in lieu of weighing material in trucks.

The contract unit price for *Select Granular Material, Class III* will be full compensation for furnishing, hauling, handling, placing, compacting and maintaining select granular material in water. Payment will be made under "Select Granular Material, Class III".

Placement and compensation for Select Granular Material placed in areas of Undercut Excavation will be as specified in the Project Special Provision "Backfilling Undercut Areas", included elsewhere in this project.

**ROCK PLATING:**

(7-21-09) (Rev 10-19-10)

SP2 R85

**Description**

Construct rock plating in accordance with the contract. Rock plating is required to stabilize slopes at locations shown on the plans.

**Materials**

Refer to Division 10 of the *Standard Specifications*:

<b>Item</b>	<b>Section</b>
Select Material	1016
Plain Riprap	1042
Subsurface Drainage Materials	1044
Filter Fabric for Rock Plating, Type 2	1056