

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+26.00)	Lump Sum	L.S.	
0004	0038000000-E	SP	SHALLOW UNDERCUT	100 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0057000000-E	226	UNDERCUT EXCAVATION	120 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	100 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	6 CY		
0009	0195000000-E	SP	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	260 SY		
0011	0220000000-E	SP	ROCK EMBANKMENTS	75 TON		
0012	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VI)	40 TON		
0013	0345000000-E	SP	24" SIDE DRAIN PIPE	20 LF		
0014	0995000000-E	340	PIPE REMOVAL	48 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	100 . TON		
0016	1330000000-E	607	INCIDENTAL MILLING	10 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	83 TON		
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	150 TON		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	15 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0022	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4 CY		
0023	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8 CY		
0024	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
0025	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0026	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2556000000-E	846	SHOULDER BERM GUTTER	38 LF		
0028	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0029	2619000000-E	850	4" CONCRETE PAVED DITCH	5 SY		
0030	3420000000-E	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED STEEL BM GUARDRAIL	25 LF		
0031	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED ADDITIONAL GUARDRAIL POST	5 EA		
0032	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED GUARDRAIL ANCHOR UNITS, TYPE 350, TL-2	3 EA		
0033	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0034	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0035	3649000000-E	876	RIP RAP, CLASS B	21 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	785 SY		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3677000000-E	SP	GENERIC EROSION CONTROL ITEM FILTER FABRIC FOR ROCK EMBANK- MENT	160 SY		
0038	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	52 LF		
0039	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0040	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6 EA		
0041	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	4 EA		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	270 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	67 SF		
0044	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,780 LF		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	225 LF		
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250 TON		
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75 TON		
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		
0050	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0054	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0055	6029000000-E	SP	SAFETY FENCE	350 LF		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6030000000-E	1630	SILT EXCAVATION	100 CY		
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	510 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0060	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	225 SY		
0061	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0062	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		
0063	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0064	6087000000-E	1660	MOWING	0.5 ACR		
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0069	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0070	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0071	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0072	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+26.00-L-)	Lump Sum	L.S.	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+26.00-L-)	Lump Sum	L.S.	
0074	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	38.67 LF		
0075	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	22 LF		
0076	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	39.26 LF		
0077	8113000000-N	SP	SID INSPECTION	1 EA		
0078	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0079	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+26.00-L-)	Lump Sum	L.S.	
0080	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	42.4 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+26.00-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,216 LB		
0083	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,289 LB		
0084	8364000000-E	SP	HP12X53 STEEL PILES	205 LF		
0085	8391000000-N	SP	STEEL PILE POINTS	10 EA		
0086	8517000000-E	460	1'-**X ***** CONCRETE PARA- PET (1'-0" X 2-9 3/4")	205.5 LF		
0087	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	297 TON		
0088	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	330 SY		
0089	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,026.25 LF		
0091	8867000000-E	SP	GENERIC STRUCTURE ITEM 2 BAR ANODIZED RAIL	190.5 LF		
1523/Feb02/Q22931.13/D417809200000/E91			Total Amount Of Bid For Entire Project :			

Contract No **C202432**

County (ies): **Macon**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General