

County Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	1,188 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	485 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	19.8 SMI		
0005	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,418 TON		
0006	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	20,493 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	12,044 TON		
0008	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,961 TON		
0009	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0010	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	85,004 LF		
0011	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	52,140 LF		
0012	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	79,856 LF		
0013	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	654 EA		
0014	6000000000-E	1605	TEMPORARY SILT FENCE	1,300 LF		
0015	6012000000-E	1610	SEDIMENT CONTROL STONE	20 TON		
0016	6042000000-E	1632	1/4" HARDWARE CLOTH	1,000 LF		
0017	6071010000-E	SP	WATTLE	200 LF		

County **Beaufort**

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	6084000000-E	1660	SEEDING & MULCHING	19	ACR	

0927/Mar04/Q262803.8/D62521110000/E18

Total Amount Of Bid For Entire Project :

Contract No **C202758**

County (ies): **Beaufort**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General