

County Clay

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0030000000-N | SP | BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (19+09.50 -L-) | Lump Sum | L.S. | |
| 0003 | 0038000000-E | SP | SHALLOW UNDERCUT | 35 CY | | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0006 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 100 CY | | |
| 0007 | 0080000000-E | SP | CLASS IV SUBGRADE STABILIZA- TION | 65 TON | | |
| 0008 | 0195000000-E | SP | SELECT GRANULAR MATERIAL | 100 CY | | |
| 0009 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 200 SY | | |
| 0010 | 0318000000-E | SP | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 7.5 TON | | |
| 0011 | 0320000000-E | SP | FOUNDATION CONDITIONING FABRIC | 35 SY | | |
| 0012 | 0335200000-E | SP | 15" DRAINAGE PIPE | 24 LF | | |
| 0013 | 0335300000-E | SP | 18" DRAINAGE PIPE | 32 LF | | |
| 0014 | 0448200000-E | SP | 15" RC PIPE CULVERTS, CLASS IV | 12 LF | | |
| 0015 | 0995000000-E | 340 | PIPE REMOVAL | 14 LF | | |
| 0016 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 60 TON | | |
| 0017 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 50 TON | | |
| 0018 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 192 TON | | |

County Clay

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|------------|-----------|--------|
| 001E | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 200 TON | | |
| 002C | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 22 TON | | |
| 0021 | 2022000000-E | SP | SUBDRAIN EXCAVATION | 23 CY | | |
| 0022 | 2033000000-E | SP | SUBDRAIN FINE AGGREGATE | 17 CY | | |
| 0023 | 2044000000-E | SP | 6" PERFORATED SUBDRAIN PIPE | 100 LF | | |
| 0024 | 2070000000-N | SP | SUBDRAIN PIPE OUTLETS | 1 EA | | |
| 002E | 2077000000-E | SP | 6" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 002E | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 3 EA | | |
| 0027 | 2364200000-N | 840 | FRAME WITH TWO GRATES, STD 840.20 | 3 EA | | |
| 002E | 2556000000-E | 846 | SHOULDER BERM GUTTER | 162 LF | | |
| 002E | 3030000000-E | 862 | STEEL BM GUARDRAIL | 150 LF | | |
| 003C | 3045000000-E | 862 | STEEL BM GUARDRAIL, SHOP CURVED | 12.5 LF | | |
| 0031 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0032 | 3165000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2) | 3 EA | | |
| 0033 | 3195000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE AT-1 | 1 EA | | |
| 0034 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 003E | 3559000000-E | 866 | ** STRAND BARBED WIRE FENCE WITH POSTS (1) | 90 LF | | |

County Clay

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0036 | 3559000000-E | 866 | ** STRAND BARBED WIRE FENCE WITH POSTS (4) | 90 | LF | |
| 0037 | 3564000000-E | 866 | SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 10', 10') | 2 | EA | |
| 003E | 3569000000-E | 867 | BARBED WIRE FENCE RESET | 640 | LF | |
| 003E | 3580000000-E | 866 | GENERIC FENCING ITEM TEMPORARY 1 STRAND BARDED WIRE FENCE | 206 | LF | |
| 004C | 3580000000-E | 866 | GENERIC FENCING ITEM TEMPORARY 3 STRAND BARDED WIRE FENCE | 210 | LF | |
| 0041 | 3580000000-E | 866 | GENERIC FENCING ITEM TEMPORARY 4 STRAND BARDED WIRE FENCE | 140 | LF | |
| 0042 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 475 | SY | |
| 0043 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 2 | EA | |
| 0044 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 448 | SF | |
| 004E | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 116 | SF | |
| 004E | 4430000000-N | 1130 | DRUMS | 20 | EA | |
| 0047 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 128 | LF | |
| 004E | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 3,012 | LF | |
| 004E | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 435 | LF | |
| 005C | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 225 | TON | |
| 0051 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 65 | TON | |

County Clay

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0052 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 50 TON | | |
| 0053 | 6015000000-E | 1615 | TEMPORARY MULCHING | 0.5 ACR | | |
| 0054 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 50 LB | | |
| 005E | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 1.25 TON | | |
| 005E | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 200 LF | | |
| 0057 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 4 EA | | |
| 005E | 6029000000-E | SP | SAFETY FENCE | 240 LF | | |
| 005E | 6030000000-E | 1630 | SILT EXCAVATION | 100 CY | | |
| 006C | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 2,500 SY | | |
| 0061 | 6037000000-E | SP | COIR FIBER MAT | 10 SY | | |
| 0062 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 27 SY | | |
| 0063 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 175 LF | | |
| 0064 | 6071010000-E | SP | WATTLE | 25 LF | | |
| 006E | 6071020000-E | SP | POLYACRYLAMIDE (PAM) | 25 LB | | |
| 006E | 6071030000-E | SP | COIR FIBER BAFFLES | 55 LF | | |
| 0067 | 6071050000-E | SP | *** SKIMMER (1-1/2") | 1 EA | | |
| 006E | 6084000000-E | 1660 | SEEDING & MULCHING | 0.5 ACR | | |
| 006E | 6087000000-E | 1660 | MOWING | 0.5 ACR | | |
| 007C | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |

County · Clay

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|---|-------------|-----------|--------|
| 0071 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0072 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 0073 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 0.25 TON | | |
| 0074 | 6114500000-N | SP | SPECIALIZED HAND MOWING | 10 MHR | | |
| 007E | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 18 EA | | |
| 007E | 6123000000-E | 1670 | REFORESTATION | 0.25 ACR | | |
| STRUCTURE ITEMS | | | | | | |
| 0077 | 8017000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (19+09.50-L-) | Lump Sum | L.S. | |
| 007E | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+09.50-L-) | Lump Sum | L.S. | |
| 007E | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (19+09.50-L-) | Lump Sum | L.S. | |
| 008C | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 50.2 CY | | |
| 0081 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (19+09.50-L-) | Lump Sum | L.S. | |
| 0082 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 7,494 LB | | |
| 0083 | 8364000000-E | SP | HP12X53 STEEL PILES | 500 LF | | |
| 0084 | 8384200000-E | SP | HP14X73 GALVANIZED STEEL PILES | 765 LF | | |
| 008E | 8505000000-E | SP | VERTICAL CONCRETE BARRIER RAIL | 265.5 LF | | |
| 008E | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 161 TON | | |

County . Clay

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|---------------------------------------|--------------|-------|---|---------------|-----------|--------|
| 0087 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 179 SY | | |
| 008E | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 008E | 8762000000-E | 430 | 3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS | 1,457.5 LF | | |
| 1010/Mar07/Q22417.7/D379633810000/E89 | | | Total Amount Of Bid For Entire Project | | | |

Contract No **C202430**

County (ies): **Clay**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General