

County Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	500 CY		
0003	1110000000-E	510	STABILIZER AGGREGATE	785 TON		
0004	1220000000-E	545	INCIDENTAL STONE BASE	590 TON		
0005	1243000000-E	SP	SHOULDER CONSTRUCTION	4.6 SMI		
0006	1245000000-E	SP	SHOULDER RECONSTRUCTION	17.6 SMI		
0007	1264000000-E	SP	DITCHING	400 LF		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	63,000 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	210 SY		
0010	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,975 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,925 TON		
0012	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	690 TON		
0013	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	15,300 TON		
0014	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	366 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	487 TON		
0016	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	942 TON		
0017	1704000000-E	SP	PATCHING EXISTING PAVEMENT	4,290 TON		
0018	2612000000-E	848	6" CONCRETE DRIVEWAY	252 SY		

County Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2815000000-N	858	ADJUSTMENT OF DROP INLETS	2 EA		
0020	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0021	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0022	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0023	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	70,140 LF		
0024	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	75,427 LF		
0025	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	120 LF		
0026	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	550 LF		
0027	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	360 LF		
0028	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	150 LF		
0029	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	9 EA		
0030	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	68 EA		
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	184,298 LF		
0032	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,779 EA		
0033	6000000000-E	1605	TEMPORARY SILT FENCE	2,009 LF		
0034	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	250 TON		
0035	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		

County Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6071010000-E	SP	WATTLE	1,664	LF	
0037	6071020000-E	SP	POLYACRYLAMIDE (PAM)	4.2	LB	
003E	6084000000-E	1660	SEEDING & MULCHING	2.2	ACR	

1111/Mar23/Q432697.6/D120476130000/E38

Total Amount Of Bid For Entire Project .

**Contract No**     **C202765**

**County (ies):**   **Anson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General