

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-M	200	CLEARING & GRUBBING .. HECTARE(S)	Lump Sum	L.S.	
0003	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB- BING	0.4 HA		
0004	0022000000-M	225	UNCLASSIFIED EXCAVATION	14,500 M3		
0005	0036000000-M	225	UNDERCUT EXCAVATION	9,150 M3		
0006	0038000000-M	SP	SHALLOW UNDERCUT	29,100 M3		
0008	0106000000-M	230	BORROW EXCAVATION	95,000 M3		
0009	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	28 EA		
0010	0134000000-M	240	DRAINAGE DITCH EXCAVATION	2,400 M3		
0011	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	9,300 M2		
0012	0194000000-M	SP	SELECT GRANULAR MATERIAL, CLASS III	11,525 M3		
0013	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	70,600 M2		
0014	0199000000-M	SP	TEMPORARY SHORING	304 M2		
0015	0234000000-M	SP	GENERIC GRADING ITEM MASS SOIL MIXING	45,250 M3		
0016	0234000000-M	SP	GENERIC GRADING ITEM OBSTRUCTION REMOVAL FOR MASS SOIL MIXING	5,000 M3		
0017	0241000000-M	SP	GENERIC GRADING ITEM NONWOVEN FABRIC FOR SOIL SEPARATION	10,450 M2		
0018	0255000000-M	SP	GENERIC GRADING ITEM EXCAVATION AND STOCKPILING CONTAMINATED SOIL	100 MTN		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0257000000-M	SP	GENERIC GRADING ITEM IMPERVIOUS DIKE FOR MASS SOIL MIXING	560 M		
0020	0262000000-N	SP	GENERIC GRADING ITEM CONTAMINATED WATER STORAGE VESSEL DAILY RENTAL	5 EA		
0021	0318000000-M	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	2,340 MTN		
0022	0320000000-M	SP	FOUNDATION CONDITIONING FABRIC	5,120 M2		
0023	0962000000-M	320	*** X ***MM CAA STRUCTURAL PLATE PIPE ARCH, ****MM THICK (1524MM X 1168MM , 2.77MM)	18 M		
0024	0986000000-M	SP	GENERIC PIPE ITEM 375MM DI PIPE	24 M		
0025	0987000000-M	310	GENERIC PIPE ITEM 1500MM RC PIPE CULVERTS, CLASS III	9.6 M		
0026	0987000000-M	310	GENERIC PIPE ITEM 300MM SIDE DRAIN PIPE	14.4 M		
0027	0987000000-M	310	GENERIC PIPE ITEM 375MM SIDE DRAIN PIPE	78.4 M		
0028	0987000000-M	310	GENERIC PIPE ITEM 450MM SIDE DRAIN PIPE	7.2 M		
0029	0987000000-M	310	GENERIC PIPE ITEM 600MM SIDE DRAIN PIPE	14.4 M		
0030	0988000000-M	310	GENERIC PIPE ITEM 375MM X 375MM X 375MM RC PIPE TEES, CLASS III	3 EA		
0031	0988000000-M	310	GENERIC PIPE ITEM 450MM X 450MM X 375MM RC PIPE TEES, CLASS III	2 EA		
0032	0988000000-M	310	GENERIC PIPE ITEM 600MM X 600MM X 375MM RC PIPE TEES, CLASS III	1 EA		
0033	0995000000-M	340	PIPE REMOVAL	1,500 M		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0035	1121000000-M	520	AGGREGATE BASE COURSE	625 MTN		
0036	1220000000-M	545	INCIDENTAL STONE BASE	1,000 MTN		
0037	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,250 MTN		
0038	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	26,500 MTN		
0039	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	440 MTN		
0040	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	23,150 MTN		
0041	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,720 MTN		
0042	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	21,100 MTN		
0043	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,449 MTN		
0044	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,266 MTN		
0045	1693000000-M	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	490 MTN		
0046	2022000000-M	SP	SUBDRAIN EXCAVATION	9,650 M3		
0047	2033000000-M	SP	SUBDRAIN FINE AGGREGATE	4,830 M3		
0048	2044000000-M	SP	150MM PERFORATED SUBDRAIN PIPE	11,648 M		
0049	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	78 EA		
0050	2077000000-M	SP	150MM OUTLET PIPE (SUBDRAINS)	156 M		
0051	2209000000-M	838	ENDWALLS	4 M3		
0052	2253000000-M	840	PIPE COLLARS	2 M3		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2264000000-M	840	PIPE PLUGS	1 M3		
0054	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	192 EA		
0055	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	10 M		
0056	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	39 EA		
0057	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0058	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	33 EA		
0059	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	48 EA		
0060	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	71 EA		
0061	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	5 EA		
0062	2535000000-M	846	*** X ***MM CONCRETE CURB (200MM X 400MM)	30 M		
0063	2535000000-M	846	*** X ***MM CONCRETE CURB (200MM X 450MM)	1,400 M		
0064	2549000000-M	846	750MM CONCRETE CURB & GUTTER	9,160 M		
0065	2591000000-M	848	100MM CONCRETE SIDEWALK	580 M2		
0066	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	29 EA		
0067	2612000000-M	848	150MM CONCRETE DRIVEWAY	600 M2		
0068	2655000000-M	852	125MM MONOLITHIC CONCRETE IS- LANDS (KEYED IN)	1,200 M2		
0069	3030000000-M	862	STEEL BM GUARDRAIL	434.34 M		
0070	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	6 EA		
0072	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0073	3360000000-M	863	REMOVE EXISTING GUARDRAIL	42 M		
0074	3380000000-M	862	TEMPORARY STEEL BM GUARDRAIL	87.63 M		
0075	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
0076	3572000000-M	867	CHAIN LINK FENCE RESET	230 M		
0077	3574000000-M	867	GENERIC FENCING ITEM WOOD FENCE RESET	23 M		
0078	3628000000-M	876	RIP RAP, CLASS I	185 MTN		
0079	3649000000-M	876	RIP RAP, CLASS B	125 MTN		
0080	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	5,250 M2		
0081	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0082	4082000000-M	903	SUPPORTS, WOOD	610 M		
0083	4096000000-N	904	SIGN ERECTION, TYPE D	7 EA		
0084	4102000000-N	904	SIGN ERECTION, TYPE E	52 EA		
0085	4108000000-N	904	SIGN ERECTION, TYPE F	21 EA		
0086	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	75 EA		
0087	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	57 M2		
0088	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	39 M2		
0089	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	13 M2		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0091	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	60 DAY		
0092	4430000000-N	1130	DRUMS	482 EA		
0093	4435000000-N	1135	CONES	482 EA		
0094	4445000000-M	1145	BARRICADES (TYPE III)	30 M		
0095	4455000000-N	1150	FLAGGER	540 MD		
0096	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	5 EA		
0097	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	4 EA		
0098	4480000000-N	1165	TMIA	2 EA		
0099	4485000000-M	1170	PORTABLE CONCRETE BARRIER	772 M		
0100	4510000000-N	SP	LAW ENFORCEMENT	16 HR		
0101	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	272 EA		
0102	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	2,135 M		
0103	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	15,813 M		
0104	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	500 M		
0105	4705000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (400MM, 3.1MM)	80 M		
0106	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	362 M		
0107	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	23 EA		
0108	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	219 EA		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (100MM) (IV)	305	M	
0110	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	15,112	M	
0111	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	80	M	
0112	4825000000-M	1205	PAINT PAVEMENT MARKING LINES (300MM)	100	M	
0113	4830000000-M	1205	PAINT PAVEMENT MARKING LINES (400MM)	30	M	
0114	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	246	M	
0115	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	4	EA	
0116	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	29	EA	
0117	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	3,061	M	
0118	4870000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (600MM)	18	M	
0119	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	11	EA	
0120	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	989	EA	
0121	5325200000-M	1510	50MM WATER LINE	95	M	
0122	5325600000-M	1510	150MM WATER LINE	153	M	
0123	5325800000-M	1510	200MM WATER LINE	228	M	
0124	5326000000-M	1510	250MM WATER LINE	716	M	
0125	5326200000-M	1510	300MM WATER LINE	1,036	M	
0126	5536000000-M	1515	50MM VALVE	1	EA	

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	5540000000-M	1515	150MM VALVE	2 EA		
0128	5546000000-M	1515	200MM VALVE	1 EA		
0129	5552000000-M	1515	250MM VALVE	4 EA		
0130	5558000000-M	1515	300MM VALVE	3 EA		
0131	5648000000-N	1515	RELOCATE WATER METER	54 EA		
0132	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0133	5672000000-N	1515	RELOCATE FIRE HYDRANT	10 EA		
0134	5709000000-M	1520	***MM FORCE MAIN SEWER (40MM)	19 M		
0135	5709000000-M	1520	***MM FORCE MAIN SEWER (75MM)	286 M		
0136	5709100000-M	1520	50MM FORCE MAIN SEWER	30 M		
0137	5709200000-M	1520	100MM FORCE MAIN SEWER	29 M		
0138	5798000000-M	1530	ABANDON ***MM UTILITY PIPE (50MM)	112 M		
0139	5800000000-M	1530	ABANDON 150MM UTILITY PIPE	101 M		
0140	5801000000-M	1530	ABANDON 200MM UTILITY PIPE	188 M		
0141	5802000000-M	1530	ABANDON 250MM UTILITY PIPE	667 M		
0142	5804000000-M	1530	ABANDON 300MM UTILITY PIPE	899 M		
0143	5871200000-M	1550	TRENCHLESS INSTALLATION OF 75MM IN SOIL	63 M		
0144	5871210000-M	1550	TRENCHLESS INSTALLATION OF 75MM NOT IN SOIL	62 M		
0145	5871600000-M	1550	TRENCHLESS INSTALLATION OF 250MM IN SOIL	64 M		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	5871610000-M	1550	TRENCHLESS INSTALLATION OF 250MM NOT IN SOIL	64 M		
0147	5871700000-M	1550	TRENCHLESS INSTALLATION OF 300MM IN SOIL	148 M		
0148	5871710000-M	1550	TRENCHLESS INSTALLATION OF 300MM NOT IN SOIL	147 M		
0149	6000000000-M	1605	TEMPORARY SILT FENCE	15,000 M		
0150	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	4,070 MTN		
0151	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	7,780 MTN		
0152	6012000000-M	1610	SEDIMENT CONTROL STONE	6,080 MTN		
0153	6015000000-M	1615	TEMPORARY MULCHING	50 HA		
0154	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	825 KG		
0155	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	6.75 MTN		
0156	6024000000-M	1622	TEMPORARY SLOPE DRAINS	1,000 M		
0157	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	50 EA		
0158	6029000000-M	SP	SAFETY FENCE	300 M		
0159	6030000000-M	1630	SILT EXCAVATION	10,800 M3		
0160	6036000000-M	1631	MATTING FOR EROSION CONTROL	12,900 M2		
0161	6037000000-M	SP	COIR FIBER MAT	200 M2		
0162	6042000000-M	1632	6.4MM HARDWARE CLOTH	4,200 M		
0163	6045000000-M	SP	***MM TEMPORARY PIPE (450MM)	160 M		
0164	6048000000-M	SP	FLOATING TURBIDITY CURTAIN	50 M2		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0165	6069000000-M	1638	STILLING BASINS	275		M3
0166	6070000000-N	SP	SPECIAL STILLING BASINS	15		EA
0167	6071010000-M	SP	WATTLE	100		M
0168	6071020000-M	SP	POLYACRYLAMIDE (PAM)	50		KG
0169	6071030000-M	SP	COIR FIBER BAFFLE	2,000		M
0170	6071050000-M	SP	***MM SKIMMER (38MM)	16		EA
0171	6084000000-M	1660	SEEDING & MULCHING	30		HA
0172	6087000000-M	1660	MOWING	30		HA
0173	6090000000-M	1661	SEED FOR REPAIR SEEDING	1,550		KG
0174	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	5.25		MTN
0175	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	1,300		KG
0176	6108000000-M	1665	FERTILIZER TOPDRESSING	77		MTN
0177	6111000000-M	SP	IMPERVIOUS DIKE	460		M
0178	6114500000-N	SP	SPECIALIZED HAND MOWING	20		MHR
0179	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	75		EA
0180	6123000000-M	1670	REFORESTATION	5		HA
0181	6138000000-M	SP	GENERIC EROSION CONTROL ITEM BORROW PIT DEWATERING BASIN	8,000		M3
0182	6147000000-M	SP	GENERIC EROSION CONTROL ITEM 1500MM TEMPORARY PIPE (AT MASS SOIL MIXING AREA)	200		M
0183	6890000000-M	SP	CONCRETE STEPS	3		M3

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0184	7000000000-M	1705	PEDESTRIAN SIGNAL HEAD (**MM, ** SECTION) (400MM, 1 SECTION W/COUNTDOWN)	2 EA		
0185	7060000000-M	1705	SIGNAL CABLE	2,268 M		
0186	7108000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 1 SECTION)	16 EA		
0187	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	30 EA		
0188	7132000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)	9 EA		
0189	7144000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	9 EA		
0190	7264000000-M	1710	MESSENGER CABLE (9.52MM)	516 M		
0191	7300000000-M	1715	UNPAVED TRENCHING (*****) (1, 50MM)	628 M		
0192	7300000000-M	1715	UNPAVED TRENCHING (*****) (2, 50MM)	32 M		
0193	7301000000-M	1715	DIRECTIONAL DRILL (*****) (2, 50MM)	138 M		
0194	7301000000-M	1715	DIRECTIONAL DRILL (*****) (3, 50MM)	177 M		
0195	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	16 EA		
0196	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	10 EA		
0197	7360000000-N	1720	WOOD POLE	14 EA		
0198	7372000000-N	1721	GUY ASSEMBLY	26 EA		
0199	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	3 EA		
0200	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	11 EA		
0201	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	1,459 M		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0202	7456000000-M	1726	LEAD-IN CABLE (***** (14-2)	3,848 M		
0203	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	6 EA		
0204	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	2 EA		
0205	7613000000-N	SP	SOIL TEST	8 EA		
0206	7614100000-M	SP	DRILLED PIER FOUNDATION	43 M3		
0207	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	8 EA		
0208	7636000000-N	1745	SIGN FOR SIGNALS	6 EA		
0209	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0210	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
0211	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	16 EA		
0212	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
0213	7912000000-N	1755	BEACON CONTROLLER ASSEMBLY & CABINET (***** (F1)	1 EA		
0214	7980000000-N	SP	GENERIC SIGNAL ITEM OPTICAL PREEMPTION DETECTOR	10 EA		
0215	7980000000-N	SP	GENERIC SIGNAL ITEM OPTICAL PREEMPTION PHASE SE- LECTOR	3 EA		
***** BEGIN SCHEDULE AA ***** ***** (2 ALTERNATES) *****						
0216	0987000000-M	310	GENERIC PIPE ITEM 375MM RC PIPE CULVERTS, CLASS III	2,931.6 M		
AA1						
0217	0987000000-M	310	GENERIC PIPE ITEM 450MM RC PIPE CULVERTS, CLASS III	1,353.6 M		
AA1						

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0218 AA1	0987000000-M	310	GENERIC PIPE ITEM 600MM RC PIPE CULVERTS, CLASS III	740.4 M		
0219 AA1	0987000000-M	310	GENERIC PIPE ITEM 750MM RC PIPE CULVERTS, CLASS III	224.4 M		
0220 AA1	0987000000-M	310	GENERIC PIPE ITEM 900MM RC PIPE CULVERTS, CLASS III	65.2 M		
*** OR ***						
0221 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (375MM)	376.8 M		
0222 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (450MM)	240 M		
0223 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (600MM)	118.8 M		
0224 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (750MM)	63.6 M		
0225 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (900MM)	25.2 M		
0226 AA2	0987000000-M	310	GENERIC PIPE ITEM 375MM RC PIPE CULVERTS, CLASS III	2,554.8 M		
0227 AA2	0987000000-M	310	GENERIC PIPE ITEM 450MM RC PIPE CULVERTS, CLASS III	1,113.6 M		
0228 AA2	0987000000-M	310	GENERIC PIPE ITEM 600MM RC PIPE CULVERTS, CLASS III	621.6 M		
0229 AA2	0987000000-M	310	GENERIC PIPE ITEM 750MM RC PIPE CULVERTS, CLASS III	160.8 M		
0230 AA2	0987000000-M	310	GENERIC PIPE ITEM 900MM RC PIPE CULVERTS, CLASS III	40 M		

***** END SCHEDULE AA *****

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0237	0255000000-M	SP	GENERIC GRADING ITEM CLASS IV SUBGRADE STABILIZA- TION	116,100 MTN		
CULVERT ITEMS						
0231	8126000000-N	414	CULVERT EXCAVATION, STA ***** (55+81.000-L-)	Lump Sum	L.S.	
0232	8126000000-N	414	CULVERT EXCAVATION, STA ***** (73+49.000-L-)	Lump Sum	L.S.	
0233	8126000000-N	414	CULVERT EXCAVATION, STA ***** (89+00.500-L-)	Lump Sum	L.S.	
0234	8804000000-N	SP	GENERIC CULVERT ITEM ALUMINUM BOX CULVERT	Lump Sum	L.S.	
0235	8818000000-M	SP	GENERIC CULVERT ITEM CULVERT BACKFILL	1,508 MTN		
0236	8818000000-M	SP	GENERIC CULVERT ITEM FOUNDATION MATERIAL	306 MTN		

1402/June14/Q702967.77/D982142040000/E236

Total Amount Of Bid For Entire Project :

Contract No: C202760

County: Camden

**ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION**

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General