

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
000E	0134000000-E	240	DRAINAGE DITCH EXCAVATION	140 CY		
0007	0141000000-E	240	BERM DITCH CONSTRUCTION	703 LF		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
000E	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	352 TON		
001C	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	443 SY		
0011	0335200000-E	SP	15" DRAINAGE PIPE	2,221 LF		
0012	0335300000-E	SP	18" DRAINAGE PIPE	528 LF		
0013	0335400000-E	SP	24" DRAINAGE PIPE	543 LF		
0014	0594000000-E	SP	24" CS PIPE CULVERTS, 0.064" THICK	25 LF		
001E	0995000000-E	340	PIPE REMOVAL	196 LF		
001E	1121000000-E	520	AGGREGATE BASE COURSE	102 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	450 TON		
001E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	1,500 SY		
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,710 TON		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,880	TON	
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,160	TON	
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	520	TON	
0023	1891000000-E	SP	GENERIC PAVING ITEM 4" STAMPED CONCRETE FOR ROUNDAABOUT	787	SY	
0024	1891000000-E	SP	GENERIC PAVING ITEM 8" CONCRETE TRUCK APRON	413	SY	
002E	2000000000-N	806	RIGHT OF WAY MARKERS	36	EA	
002E	2022000000-E	SP	SUBDRAIN EXCAVATION	16.6	CY	
0027	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	12.4	CY	
002E	2043000000-E	SP	4" PERFORATED SUBDRAIN PIPE	74	LF	
0029	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
003C	2076000000-E	SP	4" OUTLET PIPE (SUBDRAINS)	6	LF	
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	39	EA	
0032	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	28.99	LF	
0033	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3	EA	
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	17	EA	
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	14	EA	
003E	2396000000-N	840	FRAME WITH COVER, STD 840.54	5	EA	

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	2 EA		
003E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	400 LF		
003E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	5,600 LF		
004C	2591000000-E	848	4" CONCRETE SIDEWALK	2,430 SY		
0041	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	20 EA		
0042	2612000000-E	848	6" CONCRETE DRIVEWAY	220 SY		
0043	2619000000-E	850	4" CONCRETE PAVED DITCH	26 SY		
0044	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,490 SY		
004E	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
004E	3030000000-E	862	STEEL BM GUARDRAIL	270 LF		
0047	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
004E	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (BRIDGE ANCHOR)	2 EA		
004E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
005C	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0051	3360000000-E	863	REMOVE EXISTING GUARDRAIL	247 LF		
0052	3642000000-E	876	RIP RAP, CLASS A	4 TON		
0053	3649000000-E	876	RIP RAP, CLASS B	217 TON		
0054	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,055 SY		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	3990000000-E	SP	GENERIC WALL ITEM REMOVE & RESET BRICK WALL	10 LF		
005E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	350 SF		
0057	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	600 LF		
005E	4102000000-N	904	SIGN ERECTION, TYPE E	46 EA		
005E	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
006C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,778 LF		
0061	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	9,444 LF		
0062	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	476 LF		
0063	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	756 LF		
0064	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	18 EA		
006E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	43 EA		
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,900 LF		
0067	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	12 LF		
006E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	225 EA		
006E	5648000000-N	1515	RELOCATE WATER METER	1 EA		
007C	5691300000-E	1520	8" SANITARY GRAVITY SEWER	71 LF		
0071	5776000000-E	1525	5' DIA UTILITY MANHOLE	2 EA		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	5780000000-E	1525	UTILITY MANHOLE WALL, *** DIA (5')	74	LF	
0073	5888000000-E	SP	GENERIC UTILITY ITEM 4" PVC CONDUIT, SCHD 80	180	LF	
0074	6000000000-E	1605	TEMPORARY SILT FENCE	7,115	LF	
007E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50	TON	
007E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	189	TON	
0077	6012000000-E	1610	SEDIMENT CONTROL STONE	100	TON	
007E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	425	LB	
007E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2	TON	
008C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	20	LF	
0081	6029000000-E	SP	SAFETY FENCE	750	LF	
0082	6030000000-E	1630	SILT EXCAVATION	4,500	CY	
0083	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,636	SY	
0084	6037000000-E	SP	COIR FIBER MAT	50	SY	
008E	6042000000-E	1632	1/4" HARDWARE CLOTH	420	LF	
008E	6071030000-E	SP	COIR FIBER BAFFLES	250	LF	
0087	6071050000-E	SP	*** SKIMMER (3")	1	EA	
008E	6071050000-E	SP	*** SKIMMER (4")	1	EA	
008E	6084000000-E	1660	SEEDING & MULCHING	9	ACR	

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	6087000000-E	1660	MOWING	3 ACR		
0091	6114500000-N	SP	SPECIALIZED HAND MOWING	50 MHR		
0092	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	50 EA		
0093	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION DEVICE	5 EA		
0094	7060000000-E	1705	SIGNAL CABLE	1,950 LF		
009E	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	11 EA		
009E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0097	7264000000-E	1710	MESSENGER CABLE (3/8")	350 LF		
009E	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	1,130 LF		
009E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	10 EA		
010C	7360000000-N	1720	WOOD POLE	2 EA		
0101	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0102	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0103	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2 EA		
0104	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,595 LF		
010E	7456000000-E	1726	LEAD-IN CABLE (***** (14-2))	14,630 LF		
010E	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0107	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	17	EA	
010E	7901000000-N	1753	CABINET BASE EXTENDER	1	EA	
1208/May11/Q91626.39/D429435330000/E109			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202769**

**County (ies):**   **Gaston**

**ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION**

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**