

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21 + 88.20)	Lump Sum	L.S.	
0004	0038000000-E	SP	SHALLOW UNDERCUT	175 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	350 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	60 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	600 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	1,100 SF		
0012	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	60 TON		
0013	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	190 SY		
0014	0343000000-E	SP	15" SIDE DRAIN PIPE	236 LF		
0015	0344000000-E	SP	18" SIDE DRAIN PIPE	104 LF		
0016	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	92 LF		
0017	0372000000-E	SP	18" RC PIPE CULVERTS, CLASS III	80 LF		
0018	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	44 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
002C	0995000000-E	340	PIPE REMOVAL	85 LF		
0021	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	480 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	410 TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	390 TON		
002E	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	65 TON		
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0027	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
002E	2022000000-E	SP	SUBDRAIN EXCAVATION	56 CY		
0029	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	42 CY		
003C	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	250 LF		
0031	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0032	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0033	2264000000-E	840	PIPE PLUGS	0.045 CY		
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
003E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.86 LF		
003E	2355000000-N	840	FRAME WITH GRATE, STD 840.29	1 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	3 EA		
004C	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	760 LF		
0041	2612000000-E	848	6" CONCRETE DRIVEWAY	110 SY		
0042	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	84 LF		
0043	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0044	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
004E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
004E	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	4 EA		
0047	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
004E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
004E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
005C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	597 LF		
0051	3628000000-E	876	RIP RAP, CLASS I	80 TON		
0052	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0053	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	590 SY		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	75 LF		
005E	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
005E	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0057	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	13 EA		
005E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	355 SF		
005E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	384 SF		
006C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	47 SF		
0061	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0062	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0063	4430000000-N	1130	DRUMS	66 EA		
0064	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		
006E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
006E	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0067	4480000000-N	1165	TMIA	2 EA		
006E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	470 LF		
006E	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	470 LF		
007C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	847 LF		
0071	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,124 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	564	LF	
0073	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,892	LF	
0074	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	9	EA	
007E	6000000000-E	1605	TEMPORARY SILT FENCE	1,200	LF	
007E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	270	TON	
0077	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	215	TON	
007E	6012000000-E	1610	SEDIMENT CONTROL STONE	125	TON	
007E	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
008C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0081	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0082	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0083	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0084	6029000000-E	SP	SAFETY FENCE	50	LF	
008E	6030000000-E	1630	SILT EXCAVATION	360	CY	
008E	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500	SY	
0087	6037000000-E	SP	COIR FIBER MAT	10	SY	
008E	6042000000-E	1632	1/4" HARDWARE CLOTH	300	LF	
008E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10	LB	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	6071030000-E	SP	COIR FIBER BAFFLE	100 LF		
0091	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0092	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0093	6087000000-E	1660	MOWING	1.5 ACR		
0094	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
009E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
009E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0097	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
009E	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		

STRUCTURE ITEMS

010C	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21 + 88.20-L-)	Lump Sum	L.S.	
0101	8084000000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ***** (1, 21 + 88.20-L-)	Lump Sum	L.S.	
0102	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 21 + 88.20-L-)	Lump Sum	L.S.	
0103	8112730000-N	SP	PDA TESTING	1 EA		
0104	8112740000-N	SP	PDA ASSISTANCE	1 EA		
010E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21 + 88.20-L-)	Lump Sum	L.S.	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8161000000-E	420	GROOVING BRIDGE FLOORS	5,667 SF		
0107	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	207 CY		
0108	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 88.20-L-)	Lump Sum	L.S.	
0109	8217000000-E	425	REINFORCING STEEL (BRIDGE)	21,124 LB		
0110	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	865 LB		
0111	8364000000-E	SP	HP12X53 STEEL PILES	175 LF		
0112	8391000000-N	SP	STEEL PILE POINTS	10 EA		
0113	8475000000-E	460	TWO BAR METAL RAIL	335.5 LF		
0114	8531000000-E	462	4" SLOPE PROTECTION	665 SY		
0115	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0116	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0117	8867000000-E	SP	GENERIC STRUCTURE ITEM 1'-2" X 2'-6" CONCRETE PARAPET (ALL LIGHTWEIGHT CONCRETE)	350.56 LF		
0118	8867000000-E	SP	GENERIC STRUCTURE ITEM 45" PRESTRESSED CONCRETE GIRDE R (SAND LIGHTWEIGHT CONCRETE)	694.7 LF		
0119	8892000000-E	SP	GENERIC STRUCTURE ITEM REINFORCED CONCRETE DECK SLAB (ALL LIGHTWEIGHT CONCRETE)	6,065 SF		

Contract No **C202438**

County (ies): **Davidson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General