

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0036000000-E	225	UNDERCUT EXCAVATION	915 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	25 CY		
0007	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	670 SY		
0008	0192000000-N	260	PROOF ROLLING	220 HR		
0009	0195000000-E	SP	SELECT GRANULAR MATERIAL	500 CY		
0010	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, AND DISPOSAL OF CONTAMINATED SOIL	350 TON		
0011	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	2,880 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	7,540 SY		
0013	0335200000-E	SP	15" DRAINAGE PIPE	1,800 LF		
0014	0335300000-E	SP	18" DRAINAGE PIPE	516 LF		
0015	0335400000-E	SP	24" DRAINAGE PIPE	364 LF		
0016	0335500000-E	SP	30" DRAINAGE PIPE	92 LF		
0017	0335600000-E	SP	36" DRAINAGE PIPE	92 LF		
0018	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0019	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (30")	2 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0448000000-E	SP	***** RC PIPE CULVERTS, CLASS IV (48")	12 LF		
0021	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	14,432 LF		
0022	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	3,104 LF		
0023	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	1,636 LF		
0024	0448500000-E	SP	30" RC PIPE CULVERTS, CLASS IV	104 LF		
0025	0448700000-E	SP	42" RC PIPE CULVERTS, CLASS IV	128 LF		
0026	0576000000-E	SP	*** CS PIPE CULVERTS, ***** THICK (30", 0.109")	116 LF		
0027	0576000000-E	SP	*** CS PIPE CULVERTS, ***** THICK (36", 0.109")	36 LF		
0028	0576000000-E	SP	*** CS PIPE CULVERTS, ***** THICK (54", 0.109")	12 LF		
0029	0588000000-E	SP	18" CS PIPE CULVERTS, 0.064" THICK	48 LF		
0030	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (30", 0.109")	2 EA		
0031	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (36", 0.109")	2 EA		
0032	0973100000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** IN SOIL (15", 0.5", B)	96 LF		
0033	0973300000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** NOT IN SOIL (15", 0.5", B)	32 LF		
0034	0995000000-E	340	PIPE REMOVAL	6,350 LF		
0035	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0037	1220000000-E	545	INCIDENTAL STONE BASE	5,000 TON		
0038	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	70,550 SY		
0039	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,750 TON		
0040	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,450 TON		
0041	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	29,160 TON		
0042	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,240 TON		
0043	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	29,700 TON		
0044	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	500 TON		
0045	2000000000-N	806	RIGHT OF WAY MARKERS	135 EA		
0046	2022000000-E	SP	SUBDRAIN EXCAVATION	171 CY		
0047	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	85 CY		
0048	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	500 LF		
0049	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0050	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0051	2253000000-E	840	PIPE COLLARS	7 CY		
0052	2264000000-E	840	PIPE PLUGS	2 CY		
0053	2275000000-E	SP	FLOWABLE FILL	80 CY		
0054	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	241 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	4 CY		
0056	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	88 LF		
0057	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	48 EA		
0058	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0059	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	10 EA		
0060	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	17 EA		
0061	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	79 EA		
0062	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	75 EA		
0063	2396000000-N	840	FRAME WITH COVER, STD 840.54	7 EA		
0064	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	36 EA		
0065	2535000000-E	846	***X*** CONCRETE CURB (8" X 18")	580 LF		
0066	2538000000-E	846	***_*** CONCRETE CURB & GUTTER (2'-9")	3,600 LF		
0067	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	12,130 LF		
0068	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	38,850 LF		
0069	2591000000-E	848	4" CONCRETE SIDEWALK	17,850 SY		
0070	2612000000-E	848	6" CONCRETE DRIVEWAY	2,570 SY		
0071	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	8,810 SY		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	2759000000-N	SP	GENERIC PAVING ITEM CONCRETE CURB RAMPS	116 EA		
0073	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	3 EA		
0074	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	2 EA		
0075	3030000000-E	862	STEEL BM GUARDRAIL	1,350 LF		
0076	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0077	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0078	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0079	3360000000-E	863	REMOVE EXISTING GUARDRAIL	909 LF		
0080	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	100 LF		
0081	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0082	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	1,000 LF		
0083	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	50 EA		
0084	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	50 EA		
0085	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	240 LF		
0086	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	20 EA		
0087	3548000000-E	866	MÉTAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	4 EA		
0088	3628000000-E	876	RIP RAP, CLASS I	80 TON		
0089	3649000000-E	876	RIP RAP, CLASS B	430 TON		
0090	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,285 SY		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	7 EA		
0092	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	4,517 LF		
0093	4096000000-N	904	SIGN ERECTION, TYPE D	8 EA		
0094	4102000000-N	904	SIGN ERECTION, TYPE E	159 EA		
0095	4108000000-N	904	SIGN ERECTION, TYPE F	9 EA		
0096	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	9 EA		
0097	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	11 EA		
0098	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	122 EA		
0099	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	20 EA		
0100	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,913 SF		
0101	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,887 SF		
0102	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	790 SF		
0103	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
0104	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0105	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	36 DAY		
0106	4430000000-N	1130	DRUMS	990 EA		
0107	4435000000-N	1135	CONES	50 EA		
0108	4445000000-E	1145	BARRICADES (TYPE III)	1,420 LF		
0109	4450000000-N	1150	FLAGGER	2,500 HR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0111	4480000000-N	1165	TMIA	2 EA		
0112	4485000000-E	1170	PORTABLE CONCRETE BARRIER	670 LF		
0113	4507000000-E	SP	WATER FILLED BARRIER	670 LF		
0114	4516000000-N	1180	SKINNY DRUM	450 EA		
0115	4520000000-N	1266	TUBULAR MARKERS (FIXED)	15 EA		
0116	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM WARNING FLAGS	14 EA		
0117	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	981 EA		
0118	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	33,930 LF		
0119	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	35,048 LF		
0120	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	6,226 LF		
0121	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	2,380 LF		
0122	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	400 LF		
0123	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,433 LF		
0124	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	49 EA		
0125	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	264 EA		
0126	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	432,649 LF		
0127	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	1,500 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0128	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,490 LF		
0129	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	7,130 LF		
0130	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	260 LF		
0131	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	3,343 LF		
0132	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	52 EA		
0133	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	783 EA		
0134	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	46,981 LF		
0135	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,812 LF		
0136	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	40 LF		
0137	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	798 LF		
0138	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	126 EA		
0139	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,244 EA		
0140	5325600000-E	1510	6" WATER LINE	95 LF		
0141	5325800000-E	1510	8" WATER LINE	216 LF		
0142	5326200000-E	1510	12" WATER LINE	2,074 LF		
0143	5326600000-E	1510	16" WATER LINE	346 LF		
0144	5546000000-E	1515	8" VALVE	1 EA		
0145	5558000000-E	1515	12" VALVE	7 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	5558600000-E	1515	16" VALVE	2 EA		
0147	5606000000-E	1515	2" BLOW OFF	1 EA		
0148	5648000000-N	1515	RELOCATE WATER METER	6 EA		
0149	5653000000-E	1515	*** DCV BACK-FLOW PREVENTOR (3/4")	1 EA		
0150	5666000000-E	1515	FIRE HYDRANT	3 EA		
0151	5672000000-N	1515	RELOCATE FIRE HYDRANT	29 EA		
0152	5709300000-E	1520	6" FORCE MAIN SEWER	1,729 LF		
0153	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	2 EA		
0154	5775000000-E	1525	4' DIA UTILITY MANHOLE	1 EA		
0155	5804000000-E	1530	ABANDON 12" UTILITY PIPE	1,155 LF		
0156	5835600000-E	1540	12" ENCASEMENT PIPE	41 LF		
0157	5882000000-N	SP	GENERIC UTILITY ITEM BREAKDOWN AND CAP MANHOLE	1 EA		
0158	6000000000-E	1605	TEMPORARY SILT FENCE	75,000 LF		
0159	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	4,000 TON		
0160	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,665 TON		
0161	6012000000-E	1610	SEDIMENT CONTROL STONE	5,070 TON		
0162	6015000000-E	1615	TEMPORARY MULCHING	33 ACR		
0163	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,100 LB		
0164	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	5.5 TON		
0165	6024000000-E	1622	TEMPORARY SLOPE DRAINS	500 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0166	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	10 EA		
0167	6029000000-E	SP	SAFETY FENCE	1,600 LF		
0168	6030000000-E	1630	SILT EXCAVATION	3,400 CY		
0169	6036000000-E	1631	MATTING FOR EROSION CONTROL	59,000 SY		
0170	6037000000-E	SP	COIR FIBER MAT	15 SY		
0171	6042000000-E	1632	1/4" HARDWARE CLOTH	21,000 LF		
0172	6070000000-N	SP	SPECIAL STILLING BASINS	5 EA		
0173	6071012000-E	SP	COIR FIBER WATTLE	2,750 LF		
0174	6071020000-E	SP	POLYACRYLAMIDE (PAM)	2,200 LB		
0175	6071030000-E	SP	COIR FIBER BAFFLE	400 LF		
0176	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0177	6084000000-E	1660	SEEDING & MULCHING	33 ACR		
0178	6087000000-E	1660	MOWING	33 ACR		
0179	6090000000-E	1661	SEED FOR REPAIR SEEDING	600 LB		
0180	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.75 TON		
0181	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	775 LB		
0182	6108000000-E	1665	FERTILIZER TOPDRESSING	23 TON		
0183	6111000000-E	SP	IMPERVIOUS DIKE	430 LF		
0184	6114500000-N	SP	SPECIALIZED HAND MOWING	25 MHR		
0185	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	150 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0186	6123000000-E	1670	REFORESTATION	0.25	ACR	
0187	7060000000-E	1705	SIGNAL CABLE	12,950	LF	
0188	7108000000-E	1705	VEHICLE SIGNAL HEAD (12", 1 SECTION)	8	EA	
0189	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	67	EA	
0190	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	17	EA	
0191	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	13	EA	
0192	7252000000-E	1710	MESSENGER CABLE (1/4")	10,320	LF	
0193	7264000000-E	1710	MESSENGER CABLE (3/8")	5,780	LF	
0194	7279000000-E	1715	TRACER WIRE	2,700	LF	
0195	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	220	LF	
0196	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	5,720	LF	
0197	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	1,400	LF	
0198	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	46	EA	
0199	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	12	EA	
0200	7360000000-N	1720	WOOD POLE	22	EA	
0201	7372000000-N	1721	GUY ASSEMBLY	50	EA	
0202	7408000000-E	1722	1" RISER WITH WEATHERHEAD	14	EA	
0203	7420000000-E	1722	2" RISER WITH WEATHERHEAD	52	EA	
0204	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	5	EA	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0205	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	12,500 LF		
0206	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	28,040 LF		
0207	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (24)	13,500 LF		
0208	7528000000-E	1730	DROP CABLE	3,400 LF		
0209	7540000000-N	1731	SPLICE ENCLOSURE	6 EA		
0210	7552000000-N	1731	INTERCONNECT CENTER	5 EA		
0211	7566000000-N	1733	DELINEATOR MARKER	10 EA		
0212	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	8,250 LF		
0213	7575180000-N	1735	CABLE TRANSFER	5 EA		
0214	7576000000-N	SP	METAL STRAIN SIGNAL POLE	28 EA		
0215	7613000000-N	SP	SOIL TEST	28 EA		
0216	7614100000-E	SP	DRILLED PIER FOUNDATION	224 CY		
0217	7636000000-N	1745	SIGN FOR SIGNALS	22 EA		
0218	7675000000-N	SP	LED BLANKOUT SIGN	4 EA		
0219	7684000000-N	1750	SIGNAL CABINET FOUNDATION	6 EA		
0220	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	6 EA		
0221	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	36 EA		
0222	7901000000-N	1753	CABINET BASE EXTENDER	6 EA		
0223	7912000000-N	1755	BEACON CONTROLLER ASSEMBLY & CABINET (***** (TYPE F1)	2 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0224	7912000000-N	1755	BEACON CONTROLLER ASSEMBLY & CABINET (*****) (TYPE F2)	1 EA		
0225	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	3 EA		
0226	7980000000-N	SP	GENERIC SIGNAL ITEM MODIFY RADIO INSTALLATION	1 EA		
0227	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	1,480 SF		
0228	8802030000-E	SP	SEGMENTAL GRAVITY RETAINING WALLS	165 SF		
***** BEGIN SCHEDULE AB ***** ***** (2 ALTERNATES) *****						
0229 AB1	0022000000-E	225	UNCLASSIFIED EXCAVATION	29,650 CY		
0230 AB1	0038000000-E	SP	SHALLOW UNDERCUT	17,000 CY		
0231 AB1	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	45,700 TON		
0232 AB1	0106000000-E	230	BORROW EXCAVATION	75,100 CY		
0233 AB1	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	87,950 SY		
0234 AB1	1121000000-E	520	AGGREGATE BASE COURSE	40,100 TON		
0235 AB1	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	6,950 TON		
0236 AB1	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	4,075 TON		
*** OR ***						
0237 AB2	0022000000-E	225	UNCLASSIFIED EXCAVATION	27,500 CY		
0238 AB2	0038000000-E	SP	SHALLOW UNDERCUT	16,710 CY		
0239 AB2	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	44,500 TON		
0240 AB2	0106000000-E	230	BORROW EXCAVATION	82,100 CY		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0241 AB2	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	85,260 SY		
0242 AB2	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	21,310 TON		
0243 AB2	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	4,740 TON		
***** END SCHEDULE AB *****						
CULVERT ITEMS						
0244	8126000000-N	414	CULVERT EXCAVATION, STA ***** (192+04.20 -L-)	Lump Sum	L.S.	
0245	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	131 TON		
0246	8196000000-E	420	CLASS A CONCRETE (CULVERT)	230.8 CY		
0247	8245000000-E	425	REINFORCING STEEL (CULVERT)	29,557 LB		
1212/Jul11/Q1791004.3/D1010699796000/E247			Total Amount Of Bid For Entire Project :			

Contract No **C202648**

County (ies): **Guilford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General