

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26 + 70.50 -L-)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0195000000-E	SP	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0008	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	12 TON		
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	40 SY		
0010	0335200000-E	SP	15" DRAINAGE PIPE	44 LF		
0011	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	56 LF		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	200 TON		
0013	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	165 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	205 TON		
0015	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	35 TON		
0016	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
0017	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4 CY		
0018	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8 CY		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
002C	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0021	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	180 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,050 SY		
003C	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0031	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	3 EA		
0032	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	3 EA		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	460 SF		
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,998 LF		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
004C	6012000000-E	1610	SEDIMENT CONTROL STONE	430 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
004E	6029000000-E	SP	SAFETY FENCE	1,000 LF		
0047	6030000000-E	1630	SILT EXCAVATION	100 CY		
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,700 SY		
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,300 LF		
005C	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	100 SY		
0051	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0052	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0053	6087000000-E	1660	MOWING	1.5 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
005E	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0059	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
006C	6123000000-E	1670	REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
0061	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26 + 70.50-L-)	Lump Sum	L.S.	
0062	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	81.67 LF		
0063	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	31 LF		
0064	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	77.5 LF		
006E	8113000000-N	SP	SID INSPECTION	1 EA		
006E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0067	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (26 + 70.50-L-)	Lump Sum	L.S.	
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	70.1 CY		
0069	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26 + 70.50-L-)	Lump Sum	L.S.	
007C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	19,315 LB		
0071	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,066 LB		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8364000000-E	SP	HP12X53 STEEL PILES	300 LF		
0073	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	337.5 LF		
0074	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	482 TON		
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	536 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,853.5 LF		

0654/Jun29/Q42511.32/D360241820000/E77

Total Amount Of Bid For Entire Project :

**Contract No**     **C202437**

**County (ies):**   **Halifax**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General