

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (18 + 16.70-L-)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	450 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	3,830 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	530 CY		
0008	0195000000-E	SP	SELECT GRANULAR MATERIAL	450 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	650 SY		
0010	0223000000-E	SP	ROCK PLATING	90 SY		
0011	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	20 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	40 SY		
0013	0335200000-E	SP	15" DRAINAGE PIPE	72 LF		
0014	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	36 LF		
0015	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0016	0986000000-E	SP	GENERIC PIPE ITEM 4" PVC PIPE	50 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	80 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	585 TON		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	545 TON		
002C	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	65 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0022	2022000000-E	SP	SUBDRAIN EXCAVATION	16.8 CY		
0023	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	12.6 CY		
0024	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	75 LF		
002E	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
002E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0029	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
003C	3030000000-E	862	STEEL BM GUARDRAIL	425 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0034	3360000000-E	863	REMOVE EXISTING GUARDRAIL	760 LF		
003E	3635000000-E	876	RIP RAP, CLASS II	230 TON		
003E	3649000000-E	876	RIP RAP, CLASS B	360 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,255 SY		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	61	LF	
004C	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
0041	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	10	EA	
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	278	SF	
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144	SF	
0044	4445000000-E	1145	BARRICADES (TYPE III)	112	LF	
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,080	LF	
004E	6000000000-E	1605	TEMPORARY SILT FENCE	1,450	LF	
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	450	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	490	TON	
005C	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.5	TON	
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	250	LF	
0054	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
005E	6029000000-E	SP	SAFETY FENCE	700	LF	

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6030000000-E	1630	SILT EXCAVATION	700 CY		
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,600 SY		
005E	6037000000-E	SP	COIR FIBER MAT	500 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	520 LF		
006C	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0061	6071020000-E	SP	POLYACRYLAMIDE (PAM)	110 LB		
0062	6071030000-E	SP	COIR FIBER BAFFLE	300 LF		
006E	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0064	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
006E	6087000000-E	1660	MOWING	2.5 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
007C	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0072	6123000000-E	1670	REFORESTATION	0.5 ACR		
007E	6141000000-E	SP	GENERIC EROSION CONTROL ITEM LIVE STAKING	60 SY		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0074	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+16.70-L-)	Lump Sum	L.S.	
007E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+16.70-L-)	Lump Sum	L.S.	
007E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	51 LF		
0077	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	43 LF		
007E	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	57.8 LF		
007E	8113000000-N	SP	SID INSPECTION	1 EA		
008C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+16.70-L-)	Lump Sum	L.S.	
0081	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	93.8 CY		
008Z	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+16.70-L-)	Lump Sum	L.S.	
008Z	8217000000-E	425	REINFORCING STEEL (BRIDGE)	21,583 LB		
0084	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,528 LB		
008E	8364000000-E	SP	HP12X53 STEEL PILES	250 LF		
008E	8391000000-N	SP	STEEL PILE POINTS	5 EA		
0087	8475000000-E	460	TWO BAR METAL RAIL	440.5 LF		
008E	8517000000-E	460	1'***X ***** CONCRETE PARA- PET (1'-2" X 2'-7 3/4")	455.5 LF		
008S	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,306 TON		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,455 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	2,502.5 LF		
0093	8897000000-N	SP	GENERIC STRUCTURE ITEM CSL TESTING	1 EA		
0951/Aug31/Q67823.0/D426875680000/E93			Total Amount Of Bid For Entire Project :			

Contract No **C202660**

County (ies): **Granville**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General