

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (-L- 16 + 54)	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	350 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	650 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	135 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,300 SY		
0009	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	120 SY		
0011	0335200000-E	SP	15" DRAINAGE PIPE	84 LF		
0012	0335300000-E	SP	18" DRAINAGE PIPE	212 LF		
0013	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0014	0343000000-E	SP	15" SIDE DRAIN PIPE	40 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	1,330 TON		
0016	1275000000-E	600	PRIME COAT	945 GAL		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	430 TON		
0018	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	30 TON		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	26	EA	
002C	2022000000-E	SP	SUBDRAIN EXCAVATION	45	CY	
0021	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	35	CY	
0022	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	200	LF	
0023	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
0024	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6	LF	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3	EA	
002E	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	2	EA	
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
002E	2556000000-E	846	SHOULDER BERM GUTTER	10	LF	
002E	3030000000-E	862	STEEL BM GUARDRAIL	75	LF	
003C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0031	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	4	EA	
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
003C	3628000000-E	876	RIP RAP, CLASS I	111	TON	
0034	3649000000-E	876	RIP RAP, CLASS B	3	TON	
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	857	SY	
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	305	LF	
0037	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4102000000-N	904	SIGN ERECTION, TYPE E	24 EA		
003E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
004C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		
0041	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	494 SF		
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
004E	4430000000-N	1130	DRUMS	45 EA		
004E	4435000000-N	1135	CONES	69 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
004E	4455000000-N	1150	FLAGGER	38 MD		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,260 LF		
005C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	16 EA		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	1,950 LF		
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	405 TON		
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	80 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.75 TON		
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	300 LF		
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6 EA		
006C	6029000000-E	SP	SAFETY FENCE	500 LF		
0061	6030000000-E	1630	SILT EXCAVATION	500 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,725 SY		
006E	6037000000-E	SP	COIR FIBER MAT	975 SY		
0064	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	891 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	120 LF		
006E	6071010000-E	SP	WATTLE	1,030 LF		
0067	6071020000-E	SP	POLYACRYLAMIDE (PAM)	150 LB		
006E	6071030000-E	SP	COIR FIBER BAFFLE	155 LF		
006E	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
007C	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		
0071	6087000000-E	1660	MOWING	4.5 ACR		
0072	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0074	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5 TON		
007E	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0077	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
007E	6123000000-E	1670	REFORESTATION	1 ACR		
STRUCTURE ITEMS						
007E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 54.00-L-)	Lump Sum	L.S.	
008C	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SOIL	33.3 LF		
0081	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	41 LF		
0082	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	11.2 LF		
008E	8113000000-N	SP	SID INSPECTION	1 EA		
0084	8114000000-N	SP	SPT TESTING	2 EA		
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	64.3 CY		
008E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 54.00-L-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	22,476 LB		
008E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,178 LB		
008E	8364000000-E	SP	HP12X53 STEEL PILES	215 LF		
009C	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	260.75 LF		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	735 TON		
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	820 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,170 LF		
009E	8897000000-N	SP	GENERIC STRUCTURE ITEM CSL TESTING	1 EA		

1500/Aug31/Q65975.55/D430176700000/E95

Total Amount Of Bid For Entire Project :

Contract No **C202656**

County (ies): **Montgomery**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General