

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+92.27)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1,300 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	180 CY		
0008	0195000000-E	SP	SELECT GRANULAR MATERIAL	300 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0010	0241000000-E	SP	GENERIC GRADING ITEM REINFORCED SOIL SLOPE	7,050 SY		
0011	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	70 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	200 SY		
0013	0335200000-E	SP	15" DRAINAGE PIPE	140 LF		
0014	0335300000-E	SP	18" DRAINAGE PIPE	96 LF		
0015	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0016	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	280 LF		
0017	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	68 LF		
0018	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0995000000-E	340	PIPE REMOVAL	32 LF		
0020	1121000000-E	520	AGGREGATE BASE COURSE	415 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,860 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,140 TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,270 TON		
0025	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	6,350 TON		
0026	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	685 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	500 TON		
0028	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4 CY		
0029	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8 CY		
0030	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
0031	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0032	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	11 EA		
0034	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0035	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	10 EA		
0036	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	220 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2556000000-E	846	SHOULDER BERM GUTTER	2,015 LF		
003E	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	240 LF		
0039	2612000000-E	848	6" CONCRETE DRIVEWAY	50 SY		
004C	3030000000-E	862	STEEL BM GUARDRAIL	1,975 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0042	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0043	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0044	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,218 LF		
004E	3649000000-E	876	RIP RAP, CLASS B	6 TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	950 SY		
0047	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (7)	3 SF		
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	20 LF		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	359 SF		
005C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0051	4430000000-N	1130	DRUMS	80 EA		
0052	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0053	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,733 LF		
0054	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,988 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	220	LF	
005E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	123	LF	
0057	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	133,500	LF	
005E	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	680	LF	
005E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,700	EA	
006C	5325200000-E	1510	2" WATER LINE	150	LF	
0061	5325400000-E	1510	4" WATER LINE	10	LF	
0062	5325600000-E	1510	6" WATER LINE	505	LF	
0063	5325800000-E	1510	8" WATER LINE	1,840	LF	
0064	5326000000-E	1510	10" WATER LINE	410	LF	
006E	5536000000-E	1515	2" VALVE	1	EA	
006E	5540000000-E	1515	6" VALVE	5	EA	
0067	5546000000-E	1515	8" VALVE	7	EA	
006E	5648000000-N	1515	RELOCATE WATER METER	4	EA	
006E	5649000000-N	1515	RECONNECT WATER METER	5	EA	
007C	5666000000-E	1515	FIRE HYDRANT	2	EA	
0071	5709100000-E	1520	2" FORCE MAIN SEWER	460	LF	
0072	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,800	LF	
0073	5801000000-E	1530	ABANDON 8" UTILITY PIPE	240	LF	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	5802000000-E	1530	ABANDON 10" UTILITY PIPE	190 LF		
0075	5815000000-N	1530	REMOVE WATER METER	3 EA		
0076	5815500000-N	1530	REMOVE FIRE HYDRANT	2 EA		
0077	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	125 LF		
0078	5882000000-N	SP	GENERIC UTILITY ITEM RECONNECT EXISTING SEWER SERVI CE	1 EA		
0079	5882000000-N	SP	GENERIC UTILITY ITEM SEWER VALVE ASSEMBLY	5 EA		
0080	6000000000-E	1605	TEMPORARY SILT FENCE	5,900 LF		
0081	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	520 TON		
0082	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	530 TON		
0083	6012000000-E	1610	SEDIMENT CONTROL STONE	395 TON		
0084	6015000000-E	1615	TEMPORARY MULCHING	7.5 ACR		
0085	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0086	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2 TON		
0087	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,000 LF		
0088	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	20 EA		
0089	6030000000-E	1630	SILT EXCAVATION	970 CY		
0090	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,650 SY		
0091	6037000000-E	SP	COIR FIBER MAT	30 SY		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	7,050	SY	
0093	6042000000-E	1632	1/4" HARDWARE CLOTH	870	LF	
0094	6071010000-E	SP	WATTLE	800	LF	
0095	6071020000-E	SP	POLYACRYLAMIDE (PAM)	220	LB	
0096	6071030000-E	SP	COIR FIBER BAFFLE	305	LF	
0097	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
009E	6084000000-E	1660	SEEDING & MULCHING	6	ACR	
009E	6087000000-E	1660	MOWING	6	ACR	
010C	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0101	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0102	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200	LB	
0103	6108000000-E	1665	FERTILIZER TOPDRESSING	5.5	TON	
0104	6114500000-N	SP	SPECIALIZED HAND MOWING	25	MHR	
010E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	

**STRUCTURE ITEMS**

010E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+92.27-L-)	Lump Sum	L.S.	
0107	8112730000-N	SP	PDA TESTING	1	EA	
010E	8112740000-N	SP	PDA ASSISTANCE	1	EA	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16 + 92.27-L-)	Lump Sum	L.S.	
0110	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,909 SF		
0111	8161000000-E	420	GROOVING BRIDGE FLOORS	6,198 SF		
0112	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	80 CY		
0113	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 92.27-L-)	Lump Sum	L.S.	
0114	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,236 LB		
0115	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	288,000 LS		
0116	8384000000-E	SP	HP14X73 STEEL PILES	840 LF		
0117	8393000000-N	SP	PILE REDRIVES	12 EA		
0118	8503000000-E	460	CONCRETE BARRIER RAIL	375.27 LF		
0119	8531000000-E	462	4" SLOPE PROTECTION	1,165 SY		
0120	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0121	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	

**Contract No**      **C202728**

**County (ies):**    **Beaufort**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General