

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (21 + 11.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	4,125 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	101 CY		
0008	0195000000-E	SP	SELECT GRANULAR MATERIAL	300 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0010	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	45 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	440 SY		
0012	0335200000-E	SP	15" DRAINAGE PIPE	140 LF		
0013	0426000000-E	SP	72" RC PIPE CULVERTS, CLASS III	36 LF		
0014	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	84 LF		
0015	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0016	0995000000-E	340	PIPE REMOVAL	23 LF		
0017	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***** DEPTH (1-1/2")	200 SY		

County : Edgemcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	780	TON	
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	260	TON	
002C	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	610	TON	
0021	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	85	TON	
0022	2000000000-N	806	RIGHT OF WAY MARKERS	9	EA	
0023	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4	CY	
0024	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8	CY	
002E	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100	LF	
002E	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
0027	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6	LF	
002E	2220000000-E	838	REINFORCED ENDWALLS	14.2	CY	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5	EA	
003C	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	18.4	CY	
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4	EA	
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	1	EA	
0033	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	15	LF	
0034	2556000000-E	846	SHOULDER BERM GUTTER	60	LF	
003E	3030000000-E	862	STEEL BM GUARDRAIL	50	LF	
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3	EA	

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
003E	3649000000-E	876	RIP RAP, CLASS B	1	TON	
004C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,055	SY	
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
0042	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	51	LF	
0043	4096000000-N	904	SIGN ERECTION, TYPE D	1	EA	
0044	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1	EA	
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	7	EA	
004E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1	EA	
0047	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1	EA	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	492	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144	SF	
005C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	89	SF	
0051	4430000000-N	1130	DRUMS	44	EA	
0052	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0053	4450000000-N	1150	FLAGGER	240	HR	
0054	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,861	LF	

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,156	LF	
005E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	26	LF	
0057	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	32	LF	
005E	5325600000-E	1510	6" WATER LINE	140	LF	
005E	5672000000-N	1515	RELOCATE FIRE HYDRANT	2	EA	
006C	5816000000-N	1530	ABANDON UTILITY MANHOLE	1	EA	
0061	5882000000-N	SP	GENERIC UTILITY ITEM 6" CHECK VALVE ASSEMBLY	1	EA	
0062	6000000000-E	1605	TEMPORARY SILT FENCE	1,050	LF	
0063	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0064	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150	TON	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	390	TON	
006E	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	
0067	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5	TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	280	LF	
007C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7	EA	
0071	6029000000-E	SP	SAFETY FENCE	800	LF	
0072	6030000000-E	1630	SILT EXCAVATION	400	CY	

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0074	6037000000-E	SP	COIR FIBER MAT	40 SY		
007E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	70 SY		
007E	6042000000-E	1632	1/4" HARDWARE CLOTH	820 LF		
0077	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	130 SY		
007E	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
007E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
008C	6071030000-E	SP	COIR FIBER BAFFLE	200 LF		
0081	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0082	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0083	6087000000-E	1660	MOWING	3 ACR		
0084	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
008E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
008E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0087	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
008E	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
008E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	16 EA		
009C	6123000000-E	1670	REFORESTATION	0.5 ACR		
0091	7216000000-N	SP	MODIFY EXISTING VEHICLE SIGNAL HEAD	2 EA		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	20 LF		
0093	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1 EA		
0094	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	200 LF		
009E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	400 LF		
STRUCTURE ITEMS						
009E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (21 + 11.00-L-)	Lump Sum	L.S.	
0097	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21 + 11.00-L-)	Lump Sum	L.S.	
009E	8108000000-E	SP	4'-0" DIA DRILLED PIERS (4'-0")	201.34 LF		
009E	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	77.34 LF		
010C	8113000000-N	SP	SID INSPECTION	2 EA		
0101	8114000000-N	SP	SPT TESTING	2 EA		
0102	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21 + 11.00-L-)	Lump Sum	L.S.	
010E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	114.7 CY		
0104	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 11.00-L-)	Lump Sum	L.S.	
010E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	37,715 LB		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	8,044 LB		
0107	8364000000-E	SP	HP12X53 STEEL PILES	690 LF		
010E	8475000000-E	460	TWO BAR METAL RAIL	520.5 LF		
010E	8517000000-E	460	1'-***"X ***** CONCRETE PARAPET (1'-2" X 2'-7 3/4")	535.5 LF		
011C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	400 TON		
0111	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	444 SY		
0112	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0113	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	3,210 LF		
0114	8897000000-N	SP	GENERIC STRUCTURE ITEM CSL TESTING	1 EA		

1356/Sep29/Q74158.43/D527855300000/E114

Total Amount Of Bid For Entire Project :

Contract No **C202730**

County (ies): **Edgecombe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General