

County : Greene, Lenoir

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+00) | Lump Sum | L.S. | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 000E | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 000E | 0057000000-E | 226 | UNDERCUT EXCAVATION | 300 CY | | |
| 0007 | 0195000000-E | SP | SELECT GRANULAR MATERIAL | 300 CY | | |
| 000E | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 400 SY | | |
| 000E | 0318000000-E | SP | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 6 TON | | |
| 001C | 0320000000-E | SP | FOUNDATION CONDITIONING FABRIC | 18 SY | | |
| 0011 | 0335200000-E | SP | 15" DRAINAGE PIPE | 12 LF | | |
| 0012 | 0344000000-E | SP | 18" SIDE DRAIN PIPE | 32 LF | | |
| 001E | 0995000000-E | 340 | PIPE REMOVAL | 21 LF | | |
| 0014 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 100 TON | | |
| 001E | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 450 TON | | |
| 001E | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 310 TON | | |
| 0017 | 1575000000-E | SP | ASPHALT BINDER FOR PLANT MIX | 45 TON | | |
| 001E | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 20 TON | | |

County : Greene, Lenoir

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 001E | 2022000000-E | SP | SUBDRAIN EXCAVATION | 23 CY | | |
| 002C | 2033000000-E | SP | SUBDRAIN FINE AGGREGATE | 17 CY | | |
| 0021 | 2044000000-E | SP | 6" PERFORATED SUBDRAIN PIPE | 100 LF | | |
| 0022 | 2070000000-N | SP | SUBDRAIN PIPE OUTLETS | 1 EA | | |
| 0023 | 2077000000-E | SP | 6" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 0024 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 1 EA | | |
| 002E | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 1 EA | | |
| 002E | 2556000000-E | 846 | SHOULDER BERM GUTTER | 110 LF | | |
| 0027 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 187.5 LF | | |
| 002E | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 002E | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 003C | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0031 | 3569000000-E | 867 | BARBED WIRE FENCE RESET | 265 LF | | |
| 0032 | 3649000000-E | 876 | RIP RAP, CLASS B | 5 TON | | |
| 0033 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 460 SY | | |
| 0034 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 379 SF | | |
| 003E | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 94 SF | | |
| 003E | 4445000000-E | 1145 | BARRICADES (TYPE III) | 64 LF | | |
| 0037 | 5325200000-E | 1510 | 2" WATER LINE | 185 LF | | |

County : Greene, Lenoir

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 003E | 5606000000-E | 1515 | 2" BLOW OFF | 1 | | EA |
| 003E | 5648000000-N | 1515 | RELOCATE WATER METER | 4 | | EA |
| 004C | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 725 | | LF |
| 0041 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 225 | | TON |
| 0042 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 45 | | TON |
| 0043 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 60 | | TON |
| 0044 | 6015000000-E | 1615 | TEMPORARY MULCHING | 1.5 | | ACR |
| 004E | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 | | LB |
| 004E | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.25 | | TON |
| 0047 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 200 | | LF |
| 004E | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 4 | | EA |
| 004E | 6029000000-E | SP | SAFETY FENCE | 200 | | LF |
| 005C | 6030000000-E | 1630 | SILT EXCAVATION | 90 | | CY |
| 0051 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 2,300 | | SY |
| 0052 | 6037000000-E | SP | COIR FIBER MAT | 20 | | SY |
| 0053 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 260 | | LF |
| 0054 | 6071030000-E | SP | COIR FIBER BAFFLE | 75 | | LF |
| 005E | 6084000000-E | 1660 | SEEDING & MULCHING | 1.5 | | ACR |
| 005E | 6087000000-E | 1660 | MOWING | 1.5 | | ACR |

County : Greene, Lenoir

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|-------------------------------|-------------|-----------|--------|
| 0057 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 005E | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 005E | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 006C | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 1.25 TON | | |
| 0061 | 6114500000-N | SP | SPECIALIZED HAND MOWING | 10 MHR | | |
| 0062 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 18 EA | | |
| 0063 | 6123000000-E | 1670 | REFORESTATION | 0.1 ACR | | |

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|-----|--|-------------|------|--|
| 0064 | 8021000000-N | SP | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+00.00-L-) | Lump Sum | L.S. | |
| 006E | 8112730000-N | SP | PDA TESTING | 1 EA | | |
| 006E | 8112740000-N | SP | PDA ASSISTANCE | 1 EA | | |
| 0067 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+00.00-L-) | Lump Sum | L.S. | |
| 006E | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 42.2 CY | | |
| 006E | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (17+00.00-L-) | Lump Sum | L.S. | |
| 007C | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 6,738 LB | | |
| 0071 | 8364000000-E | SP | HP12X53 STEEL PILES | 475 LF | | |
| 0072 | 8385200000-E | SP | PP ** X **** GALVANIZED STEEL PILES (24 X 0.5) | 225 LF | | |

County : Greene, Lenoir

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--|--------------|-------|---|----------------|-----------|--------|
| 0073 | 8393000000-N | SP | PILE REDRIVES | 9 EA | | |
| 0074 | 8505000000-E | SP | VERTICAL CONCRETE BARRIER RAIL | 195.34 LF | | |
| 007E | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 217 TON | | |
| 007E | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 241 SY | | |
| 0077 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 007E | 8762000000-E | 430 | 3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS | 1,072.96 LF | | |
| 1606/Sep27/Q17595.35/D351775100000/E78 | | | Total Amount Of Bid For Entire Project : | | | |

Contract No **C202731**

County (ies): **Greene-Lenoir**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General