

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (19 + 20.00-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0007	0195000000-E	SP	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0009	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	10 TON		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	20 SY		
0011	0335200000-E	SP	15" DRAINAGE PIPE	10 LF		
0012	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	24 LF		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	600 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	420 TON		
0015	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	55 TON		
0016	2022000000-E	SP	SUBDRAIN EXCAVATION	45 CY		
0017	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	34 CY		
0018	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	200 LF		
0019	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	75 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	375 SY		
0029	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
003C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	329 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0032	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0033	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,400 LF		
0034	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	15 EA		
003E	6000000000-E	1605	TEMPORARY SILT FENCE	2,350 LF		
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50 TON		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
003E	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
004C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0041	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0042	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0043	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0044	6029000000-E	SP	SAFETY FENCE	400 LF		
004E	6030000000-E	1630	SILT EXCAVATION	120 CY		
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,100 SY		
0047	6037000000-E	SP	COIR FIBER MAT	510 SY		
004E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	250 SY		
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
005C	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	75 SY		
0051	6071010000-E	SP	WATTLE	170 LF		
0052	6071012000-E	SP	COIR FIBER WATTLE	120 LF		
0053	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0054	6071030000-E	SP	COIR FIBER BAFFLE	55 LF		
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	3 ACR		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6087000000-E	1660	MOWING	0.5	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
006C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
0062	6114500000-N	SP	SPECIALIZED HAND MOWING	30	MHR	
0063	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25	EA	
<b>STRUCTURE ITEMS</b>						
0064	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19 + 20.00-L-)	Lump Sum	L.S.	
006E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (19 + 20.00-L-)	Lump Sum	L.S.	
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	42.9	CY	
0067	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19 + 20.00-L-)	Lump Sum	L.S.	
006E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,295	LB	
006E	8364000000-E	SP	HP12X53 STEEL PILES	350	LF	
007C	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	240	LF	
0071	8391000000-N	SP	STEEL PILE POINTS	18	EA	
0072	8393000000-N	SP	PILE REDRIVES	7	EA	
0073	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	355.25	LF	

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	300 TON		
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	333 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,776.25 LF		
0944/Oct03/Q30562.65/D359960822000/E77			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202732**

**County (ies):**   **Harnett**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General