

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	830 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	430 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	5.2 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	266,400 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	300 SY		
0007	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	507 TON		
0008	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	24,645 TON		
0009	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	1,673 TON		
001C	1704000000-E	SP	PATCHING EXISTING PAVEMENT	540 TON		
0011	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	266,355 LF		
0012	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	164,670 LF		
0013	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	100 LF		
0014	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	75 LF		
001E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	4 EA		
001E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,980 LF		
0017	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,554 EA		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	6084000000-E	1660	SEEDING & MULCHING	3.3	ACR	

0813/Oct10/Q730072.5/D50801100000/E18

Total Amount Of Bid For Entire Project :

Contract No **C202857**

County (ies): **Person**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General