

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,213 TON		
0003	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	4,608 SY		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")	3,121 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	534 SY		
0006	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	17,639 TON		
0007	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	514 TON		
0008	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	1,095 TON		
0009	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	13,901 SY		
001C	1839000000-E	660	GENERIC PAVING ITEM ASPHALT SURFACE TREATMENT, MAT COAT, #67 STONE	181,892 SY		
0011	1880000000-E	SP	GENERIC PAVING ITEM 3" PATCHING OF EXISTING PAVE- MENT	40 TON		
0012	1880000000-E	SP	GENERIC PAVING ITEM 8" PATCHING OF EXISTING PAVE- MENT	5,110 TON		
0013	2759000000-N	SP	GENERIC PAVING ITEM RETROFIT EXISTING CURB RAMPS	16 EA		
0014	2830000000-N	858	ADJUSTMENT OF MANHOLES	27 EA		
0015	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	21 EA		
0016	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	109,230 LF		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	103,414 LF		
001E	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	64 LF		
001E	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	326 LF		
002C	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,037 LF		
0021	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	735 LF		
0022	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	372 LF		
002E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	519 LF		
0024	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	40 EA		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	70 EA		
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	32,492 LF		
0027	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	44 LF		
002E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	50 EA		
002E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	900 EA		
003C	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	25 LF		
0031	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1 EA		
0032	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1 EA		
003E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	200 LF		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	25 LF		

1501/Oct10/Q479277.0/D128986100000/E34

Total Amount Of Bid For Entire Project :

Contract No **C202856**

County (ies): **Rockingham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)