

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 67.00-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0195000000-E	SP	SELECT GRANULAR MATERIAL	300 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0008	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	67 TON		
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	748 SY		
0010	0335200000-E	SP	15" DRAINAGE PIPE	352 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	40 TON		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	190 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	280 TON		
0014	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	30 TON		
0015	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0016	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4 CY		
0017	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8 CY		
0018	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
0019	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0023	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	90 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	460 SY		
003C	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	459 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0033	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0034	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,800 LF		
003E	5325800000-E	1510	8" WATER LINE	655 LF		
003E	5546000000-E	1515	8" VALVE	2 EA		
0037	5801000000-E	1530	ABANDON 8" UTILITY PIPE	614 LF		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	202 LF		
003E	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	203 LF		
004C	6000000000-E	1605	TEMPORARY SILT FENCE	1,700 LF		
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	60 TON		
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		
0044	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
004E	6029000000-E	SP	SAFETY FENCE	400 LF		
005C	6030000000-E	1630	SILT EXCAVATION	80 CY		
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,550 SY		
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	550 LF		
0053	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	375 SY		
0054	6071010000-E	SP	WATTLE	55 LF		
005E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
005E	6084000000-E	1660	SEEDING & MULCHING	1 ACR		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6087000000-E	1660	MOWING	0.5 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0062	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0064	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 67.00-L-)	Lump Sum	L.S.	
006E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16 + 67.00-L-)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	54.4 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 67.00-L-)	Lump Sum	L.S.	
006E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,218 LB		
007C	8364000000-E	SP	HP12X53 STEEL PILES	500 LF		
0071	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	360 LF		
0072	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	440 LF		
007E	8393000000-N	SP	PILE REDRIVES	13 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	277.54		
				LF		
0075	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	242		
				TON		
0076	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	269		
				SY		
0077	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0078	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,523.61		
				LF		

1200/Oct03/Q25952.35/D364460840000/E78

Total Amount Of Bid For Entire Project :

Contract No **C202726**

County (ies): **Wilson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General