

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+97.00-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0007	0195000000-E	SP	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0009	0223000000-E	SP	ROCK PLATING	700 SY		
0010	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	3 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	7 SY		
0012	0546000000-E	SP	*** CAA PIPE CULVERTS, ***** THICK (15", 0.060")	20 LF		
0013	0564000000-E	SP	*** CAA PIPE ELBOWS, ***** THICK (15", 0.060")	2 EA		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	260 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	350 TON		
0017	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	35 TON		
0018	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	SP	SUBDRAIN EXCAVATION	45 CY		
0020	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	34 CY		
0021	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	200 LF		
0022	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0023	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0025	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	62.5 LF		
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0030	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0031	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	455 SY		
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6 EA		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	345 SF		
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0036	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,960 LF		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6000000000-E	1605	TEMPORARY SILT FENCE	1,600 LF		
0039	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0040	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	20 TON		
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	45 TON		
0042	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0045	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0046	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0047	6029000000-E	SP	SAFETY FENCE	310 LF		
0048	6030000000-E	1630	SILT EXCAVATION	40 CY		
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0050	6037000000-E	SP	COIR FIBER MAT	385 SY		
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	185 LF		
0052	6071012000-E	SP	COIR FIBER WATTLE	130 LF		
0053	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0054	6087000000-E	1660	MOWING	1 ACR		
0055	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0056	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	610800000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0059	611450000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0060	611700000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
STRUCTURE ITEMS						
0061	803500000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+97.00-L-)	Lump Sum	L.S.	
0062	8112730000-N	SP	PDA TESTING	2 EA		
0063	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0064	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+97.00-L-)	Lump Sum	L.S.	
0065	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	69.4 CY		
0066	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+97.00-L-)	Lump Sum	L.S.	
0067	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,223 LB		
0068	8364000000-E	SP	HP12X53 STEEL PILES	665 LF		
0069	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	1,560 LF		
0070	8393000000-N	SP	PILE REDRIVES	38 EA		
0071	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	381 LF		
0072	8594000000-E	876	RIP RAP, CLASS B	65 TON		
0073	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	258 TON		
0074	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	290 SY		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0076	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,470 LF		
0919/Nov07/Q32106.65/D342734682000/E76			Total Amount Of Bid For Entire Project :			

Contract No **C202742**

County (ies): **Bladen**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General