

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	680 TON		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	149,803 SY		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	6,892 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (8")	1,686 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	18,771 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")	1,067 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	17,127 SY		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	769 TON		
0010	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,178 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	40,131 TON		
0012	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	7,841 TON		
0013	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	3,018 TON		
0014	1577000000-E	SP	POLYMER MODIFIED ASPHALT BIN- DER FOR PLANT MIX	31 TON		
0015	1663000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED	510 TON		
0016	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	282,322 SY		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1839000000-E	660	GENERIC PAVING ITEM ASPHALT SURFACE TREATMENT, MAT COAT, #67 STONE	80,956 SY		
0018	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	76,350 LF		
0019	2830000000-N	858	ADJUSTMENT OF MANHOLES	113 EA		
0020	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	88 EA		
0021	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0022	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	141,222 LF		
0023	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	100,828 LF		
0024	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	136 LF		
0025	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	4,300 LF		
0026	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	3,282 LF		
0027	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,708 LF		
0028	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	86 EA		
0029	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	451 EA		
0030	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	37,521 LF		
0031	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	25 LF		
0032	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	24 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	756 LF		
0034	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	12 EA		
0035	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	129 EA		
0036	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	75 EA		
0037	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,275 EA		
0038	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0039	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	650 LF		
0040	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	39 EA		
0041	7420000000-E	1722	2" RISER WITH WEATHERHEAD	14 EA		
0042	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	21,368 LF		
0043	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	550 LF		

1518/Nov08/Q1005787.0/D154209100000/E43

Total Amount Of Bid For Entire Project :

Contract No **C202896**

County (ies): **Guilford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)