

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18 + 29.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0007	0195000000-E	SP	SELECT GRANULAR MATERIAL	300 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
000E	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	50 TON		
001C	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	840 SY		
0011	0335200000-E	SP	15" DRAINAGE PIPE	24 LF		
0012	0335800000-E	SP	48" DRAINAGE PIPE	76 LF		
001E	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0014	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	24 LF		
001E	0995000000-E	340	PIPE REMOVAL	40 LF		
001E	1121000000-E	520	AGGREGATE BASE COURSE	47 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	550 TON		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	300 TON		
002C	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	45 TON		
0021	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4 CY		
0022	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8 CY		
0023	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
0024	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
002E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2209000000-E	838	ENDWALLS	5 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
002E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2 LF		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
003C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	15 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	62.5 LF		
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	10 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
003E	3649000000-E	876	RIP RAP, CLASS B	1	TON	
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	455	SY	
004C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	256	SF	
0041	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
004E	4435000000-N	1135	CONES	50	EA	
0044	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
004E	4450000000-N	1150	FLAGGER	160	HR	
004E	5325600000-E	1510	6" WATER LINE	875	LF	
0047	5540000000-E	1515	6" VALVE	5	EA	
004E	5800000000-E	1530	ABANDON 6" UTILITY PIPE	870	LF	
004E	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	500	LF	
005C	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	60	LF	
0051	6000000000-E	1605	TEMPORARY SILT FENCE	1,500	LF	
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65	TON	
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	70	TON	
005E	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
006C	6029000000-E	SP	SAFETY FENCE	200 LF		
0061	6030000000-E	1630	SILT EXCAVATION	70 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0063	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	370 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	300 LF		
006E	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
006E	6087000000-E	1660	MOWING	0.5 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
007C	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0071	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0073	6123000000-E	1670	REFORESTATION	0.1 ACR		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0074	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 29.00-L-)	Lump Sum	L.S.	
007E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18 + 29.00-L-)	Lump Sum	L.S.	
007E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38.4 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 29.00-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,134 LB		
007E	8364000000-E	SP	HP12X53 STEEL PILES	475 LF		
008C	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	330 LF		
0081	8393000000-N	SP	PILE REDRIVES	9 EA		
0082	8503000000-E	460	CONCRETE BARRIER RAIL	200.25 LF		
008E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	194 TON		
0084	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	216 SY		
008E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,100 LF		
<hr/>						
1249/Nov07/Q20151.2/D364469660000/E86			<b>Total Amount Of Bid For Entire Project :</b>			

**Contract No**     **C202741**

**County (ies):**   **Lenoir**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**

Signature Sheet (Bid - Acceptance by Department)