

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0038000000-M	SP	SHALLOW UNDERCUT	38 M3		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB-BING	0.4 HA		
0006	0057000000-M	226	UNDERCUT EXCAVATION	100 M3		
0007	0080000000-M	SP	CLASS IV SUBGRADE STABILIZATION	91 MTN		
0008	0134000000-M	240	DRAINAGE DITCH EXCAVATION	680 M3		
0009	0195000000-M	SP	SELECT GRANULAR MATERIAL	84 M3		
0010	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	134 M2		
0011	0255000000-M	SP	GENERIC GRADING ITEM EXCAVATING AND STOCKPILING CONTAMINATED SOIL	10 MTN		
0012	0318000000-M	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	20 MTN		
0013	0320000000-M	SP	FOUNDATION CONDITIONING FABRIC	40 M2		
0014	0342000000-M	SP	****MM SIDE DRAIN PIPE (750MM)	12 M		
0015	0343000000-M	SP	375MM SIDE DRAIN PIPE	8.4 M		
0016	0594000000-M	SP	600MM CS PIPE CULVERTS, 1.63MM THICK	13.2 M		
0017	0995000000-M	340	PIPE REMOVAL	26.2 M		
0018	1121000000-M	520	AGGREGATE BASE COURSE	550 MTN		
0019	1220000000-M	545	INCIDENTAL STONE BASE	50 MTN		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	210	MTN	
0021	1525000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	150	MTN	
0022	1575000000-M	SP	ASPHALT BINDER FOR PLANT MIX	20	MTN	
0023	1693000000-M	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25	MTN	
0024	2000000000-N	806	RIGHT OF WAY MARKERS	7	EA	
0025	2022000000-M	SP	SUBDRAIN EXCAVATION	100	M3	
0026	2033000000-M	SP	SUBDRAIN FINE AGGREGATE	41.4	M3	
0027	2044000000-M	SP	150MM PERFORATED SUBDRAIN PIPE	100	M	
0028	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
0029	2077000000-M	SP	150MM OUTLET PIPE (SUBDRAINS)	2	M	
0030	3030000000-M	862	STEEL BM GUARDRAIL	144.78	M	
0031	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	80.01	M	
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0033	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3	EA	
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1	EA	
0035	3345000000-M	864	REMOVE & RESET EXISTING GUARDRAIL	3.81	M	
0036	3360000000-M	863	REMOVE EXISTING GUARDRAIL	28.5	M	
0037	3628000000-M	876	RIP RAP, CLASS I	100	MTN	
0038	3649000000-M	876	RIP RAP, CLASS B	10	MTN	

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	1,300 M2		
0040	4072000000-M	903	SUPPORTS, 4.5-KG STEEL U-CHANN EL	9 M		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	2 EA		
0043	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	10 EA		
0044	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	42 M2		
0045	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	9 M2		
0046	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	7 M2		
0047	4430000000-N	1130	DRUMS	15 EA		
0048	4435000000-N	1135	CONES	15 EA		
0049	4445000000-M	1145	BARRICADES (TYPE III)	25 M		
0050	4450000000-N	1150	FLAGGER	160 HR		
0051	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	1,026 M		
0052	6000000000-M	1605	TEMPORARY SILT FENCE	600 M		
0053	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	320 MTN		
0054	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	175 MTN		
0055	6012000000-M	1610	SEDIMENT CONTROL STONE	350 MTN		
0056	6015000000-M	1615	TEMPORARY MULCHING	1.5 HA		
0057	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	50 KG		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 MTN		
0059	6024000000-M	1622	TEMPORARY SLOPE DRAINS	65 M		
0060	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0061	6029000000-M	SP	SAFETY FENCE	250 M		
0062	6030000000-M	1630	SILT EXCAVATION	330 M3		
0063	6036000000-M	1631	MATTING FOR EROSION CONTROL	3,000 M2		
0064	6037000000-M	SP	COIR FIBER MAT	685 M2		
0065	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	250 M2		
0066	6042000000-M	1632	6.4MM HARDWARE CLOTH	150 M		
0067	6070000000-N	SP	SPECIAL STILLING BASINS	10 EA		
0068	6071010000-M	SP	WATTLE	85 M		
0069	6071020000-M	SP	POLYACRYLAMIDE (PAM)	45 KG		
0070	6071030000-M	SP	COIR FIBER BAFFLE	45 M		
0071	6071050000-E	SP	*** SKIMMER (38MM)	2 EA		
0072	6084000000-M	1660	SEEDING & MULCHING	1 HA		
0073	6087000000-M	1660	MOWING	1 HA		
0074	6090000000-M	1661	SEED FOR REPAIR SEEDING	25 KG		
0075	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.25 MTN		
0076	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	25 KG		
0077	6108000000-M	1665	FERTILIZER TOPDRESSING	1.25 MTN		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0078	6111000000-M	SP	IMPERVIOUS DIKE	90 M		
0079	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0080	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0081	6141000000-M	SP	GENERIC EROSION CONTROL ITEM LIVE STAKING	325 M2		
CULVERT ITEMS						
0082	8049000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (10+52.500-L-)	Lump Sum	L.S.	
0083	8049000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11+16.500-L-)	Lump Sum	L.S.	
0084	8126000000-N	414	CULVERT EXCAVATION, STA ***** (10+52.500-L-)	Lump Sum	L.S.	
0085	8126000000-N	414	CULVERT EXCAVATION, STA ***** (11+16.500-L-)	Lump Sum	L.S.	
0086	8133000000-M	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	174 MTN		
0087	8196000000-M	420	CLASS A CONCRETE (CULVERT)	230.3 M3		
0088	8245000000-M	425	REINFORCING STEEL (CULVERT)	24,143 KG		
<hr/>						
1340/Oct27/Q36988.25/D349093110000/E88			Total Amount Of Bid For Entire Project :			

Contract No **C202623**

County (ies): **Madison**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General