

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22 + 24.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	680 CY		
0007	0195000000-E	SP	SELECT GRANULAR MATERIAL	200 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	3,500 SY		
000E	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	60 TON		
001C	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	180 SY		
0011	0343000000-E	SP	15" SIDE DRAIN PIPE	260 LF		
0012	0344000000-E	SP	18" SIDE DRAIN PIPE	72 LF		
0013	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	64 LF		
0014	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	128 LF		
001E	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
001E	0995000000-E	340	PIPE REMOVAL	255 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	1,350 TON		
001E	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1275000000-E	600	PRIME COAT	172 GAL		
0020	1330000000-E	607	INCIDENTAL MILLING	120 SY		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	590 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	400 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,140 TON		
0024	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	115 TON		
0025	1869000000-E	710	***** PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (6")	113 SY		
0026	2000000000-N	806	RIGHT OF WAY MARKERS	23 EA		
0027	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4 CY		
0028	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8 CY		
0029	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
0030	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0031	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0033	2355000000-N	840	FRAME WITH GRATE, STD 840.29	7 EA		
0034	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0035	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
003E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	935	LF	
004C	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	400	LF	
0041	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4	EA	
0042	3389000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (350)	4	EA	
004E	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (48")	92	LF	
0044	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (48")	8	EA	
004E	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (48")	2	EA	
004E	3551000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, SINGLE GATE (48")	2	EA	
0047	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 21', 22')	1	EA	
004E	3649000000-E	876	RIP RAP, CLASS B	111	TON	
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,125	SY	
005C	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2	EA	
0051	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	52	LF	
0052	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
005E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	14	EA	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	92	SF	
005E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128	SF	
005E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36	SF	
0057	4430000000-N	1130	DRUMS	40	EA	
005E	4435000000-N	1135	CONES	30	EA	
005E	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	
006C	4450000000-N	1150	FLAGGER	3,200	HR	
0061	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,553	LF	
0062	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,539	LF	
006E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	25	LF	
0064	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,000	LF	
006E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	5,600	LF	
006E	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE II or III (4")	1,324	LF	
0067	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	260	EA	
006E	6000000000-E	1605	TEMPORARY SILT FENCE	3,400	LF	
006E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	310	TON	
007C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,100	TON	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	6012000000-E	1610	SEDIMENT CONTROL STONE	710 TON		
0072	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0073	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0074	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.75 TON		
007E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	480 LF		
007E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	11 EA		
0077	6029000000-E	SP	SAFETY FENCE	600 LF		
007E	6030000000-E	1630	SILT EXCAVATION	1,600 CY		
007E	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,600 SY		
008C	6037000000-E	SP	COIR FIBER MAT	50 SY		
0081	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	250 SY		
0082	6042000000-E	1632	1/4" HARDWARE CLOTH	430 LF		
008E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	100 SY		
0084	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
008E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	180 LB		
008E	6071030000-E	SP	COIR FIBER BAFFLE	400 LF		
0087	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
008E	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
008E	6087000000-E	1660	MOWING	5 ACR		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5 TON		
0094	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	50 EA		
0096	6123000000-E	1670	REFORESTATION	0.5 ACR		

STRUCTURE ITEMS

0097	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (22 + 24.50-L-)	Lump Sum	L.S.	
009E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22 + 24.50-L-)	Lump Sum	L.S.	
009E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 24.50-L-)	Lump Sum	L.S.	
010C	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SOIL	57 LF		
0101	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	49 LF		
0102	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	17.9 LF		
0103	8113000000-N	SP	SID INSPECTION	1 EA		
0104	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (22 + 24.50-L-)	Lump Sum	L.S.	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	11,413 SF		
010E	8161000000-E	420	GROOVING BRIDGE FLOORS	10,812 SF		
0107	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	142.3 CY		
010E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22 + 24.50-L-)	Lump Sum	L.S.	
010E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,787 LB		
011C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,654 LB		
0111	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	1,302.67 LF		
0112	8364000000-E	SP	HP12X53 STEEL PILES	255 LF		
011E	8391000000-N	SP	STEEL PILE POINTS	6 EA		
0114	8475000000-E	460	TWO BAR METAL RAIL	641.67 LF		
011E	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	656.67 LF		
011E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	303 TON		
0117	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	336 SY		
011E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
011E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
012C	8860000000-N	SP	GENERIC STRUCTURE ITEM INSTALL 6" STEEL NATURAL GAS PIPELINE	Lump Sum	L.S.	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	8897000000-N	SP	GENERIC STRUCTURE ITEM CSL TESTING	1		EA

0934/Nov09/Q129347.41/D552360520000/E121

Total Amount Of Bid For Entire Project :

Contract No **C202909**

County (ies): **Nash**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General

Signature Sheet (Bid - Acceptance by Department)