

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 22)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0007	0195000000-E	SP	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	3,220 SY		
0009	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	84 TON		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	190 SY		
0011	0335200000-E	SP	15" DRAINAGE PIPE	40 LF		
0012	0335300000-E	SP	18" DRAINAGE PIPE	52 LF		
0013	0335400000-E	SP	24" DRAINAGE PIPE	160 LF		
0014	0335600000-E	SP	36" DRAINAGE PIPE	316 LF		
0015	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0016	0995000000-E	340	PIPE REMOVAL	189 LF		
0017	1110000000-E	510	STABILIZER AGGREGATE	400 TON		
0018	1121000000-E	520	AGGREGATE BASE COURSE	939 TON		
0019	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	1275000000-E	600	PRIME COAT	683.2	GAL	
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	440	TON	
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	820	TON	
0023	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	70	TON	
0024	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4	CY	
002E	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8	CY	
002E	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100	LF	
0027	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
002E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6	LF	
002E	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	1	EA	
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5	EA	
0031	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2.02	LF	
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2	EA	
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
0034	2556000000-E	846	SHOULDER BERM GUTTER	126	LF	
003E	3030000000-E	862	STEEL BM GUARDRAIL	600	LF	
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	325	LF	
004C	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4	EA	
0041	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	5	EA	
0042	3628000000-E	876	RIP RAP, CLASS I	60	TON	
0043	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	520	SY	
0044	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	224	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	42	SF	
004E	4430000000-N	1130	DRUMS	30	EA	
004E	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
005C	4455000000-N	1150	FLAGGER	42	MD	
0051	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	151	EA	
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	31,686	LF	
0053	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	8,250	LF	
0054	5326200000-E	1510	12" WATER LINE	870	LF	
005E	5558000000-E	1515	12" VALVE	2	EA	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	866	LF	
0057	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	693	LF	
005E	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	77	LF	
005E	6000000000-E	1605	TEMPORARY SILT FENCE	2,875	LF	
006C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	360	TON	
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	275	TON	
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	300	TON	
006E	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	365	LF	
0067	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	11	EA	
006E	6029000000-E	SP	SAFETY FENCE	200	LF	
006E	6030000000-E	1630	SILT EXCAVATION	460	CY	
007C	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,300	SY	
0071	6037000000-E	SP	COIR FIBER MAT	10	SY	
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	755	LF	
007E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	200	SY	
0074	6071012000-E	SP	COIR FIBER WATTLE	150	LF	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	40 LB		
007E	6071030000-E	SP	COIR FIBER BAFFLE	115 LF		
0077	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
007E	6087000000-E	1660	MOWING	3 ACR		
007E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
008C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0083	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0084	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
008E	6123000000-E	1670	REFORESTATION	0.75 ACR		
STRUCTURE ITEMS						
008E	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (16 + 22.00-L-)	Lump Sum	L.S.	
0087	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 22.00-L-)	Lump Sum	L.S.	
008E	8112730000-N	SP	PDA TESTING	1 EA		
008E	8112740000-N	SP	PDA ASSISTANCE	1 EA		
009C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16 + 22.00-L-)	Lump Sum	L.S.	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8156000000-E	SP	CONCRETE WEARING SURFACE	3,836 SF		
0092	8161000000-E	420	GROOVING BRIDGE FLOORS	4,891 SF		
0093	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	51.8 CY		
0094	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 22.00-L-)	Lump Sum	L.S.	
009E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,854 LB		
009E	8364000000-E	SP	HP12X53 STEEL PILES	600 LF		
0097	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	960 LF		
009E	8393000000-N	SP	PILE REDRIVES	12 EA		
009E	8503000000-E	460	CONCRETE BARRIER RAIL	235.5 LF		
010C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	455 TON		
0101	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	505 SY		
0102	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0103	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0104	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,410.02 LF		

Contract No **C202727**

County (ies): **Beaufort**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General