

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12 + 65.75-L-)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20 + 14.00-L-)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0008	0195000000-E	SP	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
001C	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	30 SY		
0012	0335200000-E	SP	15" DRAINAGE PIPE	32 LF		
0013	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	56 LF		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	190 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	310 TON		
0016	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	30 TON		
0017	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4 CY		
0018	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8 CY		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
0020	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0021	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	115 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	150 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0029	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	385 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	435 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	63 SF		
0033	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0034	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,210 LF		
0035	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,210 LF		
0036	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	14 EA		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6000000000-E	1605	TEMPORARY SILT FENCE	1,875	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160	TON	
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5	TON	
004C	6012000000-E	1610	SEDIMENT CONTROL STONE	45	TON	
0041	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
004E	6029000000-E	SP	SAFETY FENCE	1,300	LF	
0047	6030000000-E	1630	SILT EXCAVATION	10	CY	
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,400	SY	
004E	6037000000-E	SP	COIR FIBER MAT	140	SY	
005C	6042000000-E	1632	1/4" HARDWARE CLOTH	220	LF	
0051	6071012000-E	SP	COIR FIBER WATTLE	165	LF	
0052	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	
005E	6087000000-E	1660	MOWING	0.5	ACR	
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0058	6114500000-N	SP	SPECIALIZED HAND MOWING	25 MHR		
0059	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	20 EA		
<b>STRUCTURE ITEMS</b>						
006C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12 + 65.75-L-)	Lump Sum	L.S.	
0061	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20 + 14.00-L-)	Lump Sum	L.S.	
0062	8112730000-N	SP	PDA TESTING	2 EA		
0063	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12 + 65.75-L-)	Lump Sum	L.S.	
0064	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20 + 14.00-L-)	Lump Sum	L.S.	
0065	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	88.4 CY		
0066	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12 + 65.75-L-)	Lump Sum	L.S.	
0067	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20 + 14.00-L-)	Lump Sum	L.S.	
006E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,274 LB		
0069	8384000000-E	SP	HP14X73 STEEL PILES	1,215 LF		
007C	8393000000-N	SP	PILE REDRIVES	24 EA		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	240.5 LF		
0072	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0073	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	550 LF		
0074	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		
007E	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" STEEL SHEET PILES	2,804 SF		
0831/Nov03/Q31385.35/D344327142000/E75			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202737**

**County (ies):**   **Columbus**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**

Signature Sheet (Bid - Acceptance by Department)