

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	4,808 CY		
0003	0241000000-E	SP	GENERIC GRADING ITEM REMOVE ASPHALT ISLAND	200 SY		
0004	1220000000-E	545	INCIDENTAL STONE BASE	550 TON		
0005	1245000000-E	SP	SHOULDER RECONSTRUCTION	20.08 SMI		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	72,208 SY		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	13,423 SY		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	123,048 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	4,535 SY		
0010	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	7,758 TON		
0011	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	19,458 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	26,257 TON		
0013	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,854 TON		
0014	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	250 TON		
0015	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	785 TON		
0016	2591000000-E	848	4" CONCRETE SIDEWALK	60 SY		
0017	2600000000-N	SP	RETROFIT EXISTING CURB RAMP	13 EA		

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2605000000-N	848	CONCRETE CURB RAMP	23 EA		
0019	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	200 SY		
0020	2738000000-E	SP	GENERIC PAVING ITEM INCIDENTAL CONCRETE	75 SY		
0021	2738000000-E	SP	GENERIC PAVING ITEM REMOVE & REPLACE SIDEWALK	85 SY		
0022	2752000000-E	SP	GENERIC PAVING ITEM REMOVE AND REPLACE 2'-0" CURB & GUTTER	210 LF		
0023	2752000000-E	SP	GENERIC PAVING ITEM REMOVE AND REPLACE 2'-6" CURB & GUTTER	900 LF		
0024	2759000000-N	SP	GENERIC PAVING ITEM REMOVE AND REPLACE CURB RAMPS	19 EA		
0025	2830000000-N	858	ADJUSTMENT OF MANHOLES	37 EA		
0026	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	44 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0028	4415000000-N	1115	FLASHING ARROW BOARD	1 EA		
0029	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	1 EA		
0030	4480000000-N	1165	TMA	1 EA		
0031	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	106,710 LF		
0032	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	181,026 LF		
0033	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,400 LF		
0034	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	50 LF		

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	150 LF		
0036	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,411 LF		
0037	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	14 EA		
0038	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	141 EA		
0039	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	294,228 LF		
0040	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	900 LF		
0041	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	150 LF		
0042	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,387 LF		
0043	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	14 EA		
0044	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	141 EA		
0045	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,851 EA		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	1,223 LF		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	307 TON		
0048	6012000000-E	1610	SEDIMENT CONTROL STONE	307 TON		
0049	6015000000-E	1615	TEMPORARY MULCHING	12.23 ACR		
0050	6036000000-E	1631	MATting FOR EROSION CONTROL	110 SY		
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	619 LF		
0052	6071010000-E	SP	WATTLE	210 LF		

County : Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	6084000000-E	1660	SEEDING & MULCHING	14.71		ACR
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	612		LB
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	3.07		TON
0056	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	5		EA
0057	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,020		LF
0058	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	3,425		LF

0822/Dec13/Q876267.09/D218501110000/E58

Total Amount Of Bid For Entire Project :

Contract No **C202859**

County (ies): **Duplin & Sampson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General