

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (26+65.50 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	700 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	87 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	317 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	124 LF		
0011	0335300000-E	305	18" DRAINAGE PIPE	24 LF		
0012	0335400000-E	305	24" DRAINAGE PIPE	28 LF		
0013	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	68 LF		
0014	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	32 LF		
0015	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	44 LF		
0016	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	28 LF		
0017	0995000000-E	340	PIPE REMOVAL	16 LF		
0018	1099500000-E	505	SHALLOW UNDERCUT	175 CY		
0019	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	350 TON		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1121000000-E	520	AGGREGATE BASE COURSE	215 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0022	1330000000-E	607	INCIDENTAL MILLING	200 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,100 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	490 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	620 TON		
0026	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	110 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0028	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0029	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0031	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-E	815	6" OUTLET PIPE	6 LF		
0033	2209000000-E	838	ENDWALLS	9 CY		
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0035	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0036	2556000000-E	846	SHOULDER BERM GUTTER	8 LF		
0037	2612000000-E	848	6" CONCRETE DRIVEWAY	70 SY		
0038	2830000000-N	858	ADJUSTMENT OF MANHOLES	5 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	4 EA		
0040	3030000000-E	862	STEEL BM GUARDRAIL	325 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0042	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0043	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0044	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	1,290 LF		
0045	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	60 EA		
0046	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	70 EA		
0047	3566000000-E	867	WOVEN WIRE FENCE RESET	55 LF		
0048	3578000000-N	SP	GENERIC FENCING ITEM REMOVE & RESET METAL GATE	2 EA		
0049	3628000000-E	876	RIP RAP, CLASS I	34 TON		
0050	3649000000-E	876	RIP RAP, CLASS B	15 TON		
0051	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	579 SY		
0052	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0053	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	334 SF		
0054	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0055	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0056	5326200000-E	1510	12" WATER LINE	584 LF		
0057	5558000000-E	1515	12" VALVE	2 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	5672000000-N	1515	RELOCATE FIRE HYDRANT	2	EA	
0059	5804000000-E	1530	ABANDON 12" UTILITY PIPE	560	LF	
0060	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	38	LF	
0061	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	37	LF	
0062	6000000000-E	1605	TEMPORARY SILT FENCE	1,850	LF	
0063	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	405	TON	
0064	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	265	TON	
0065	6012000000-E	1610	SEDIMENT CONTROL STONE	260	TON	
0066	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0067	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0068	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0069	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0070	6029000000-E	SP	SAFETY FENCE	300	LF	
0071	6030000000-E	1630	SILT EXCAVATION	810	CY	
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500	SY	
0073	6037000000-E	SP	COIR FIBER MAT	40	SY	
0074	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,500	SY	
0075	6042000000-E	1632	1/4" HARDWARE CLOTH	680	LF	
0076	6071010000-E	SP	WATTLE	235	LF	

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100 LB		
0078	6071030000-E	1640	COIR FIBER BAFFLE	260 LF		
0079	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0080	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0081	6087000000-E	1660	MOWING	2 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0086	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0087	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
<b>STRUCTURE ITEMS</b>						
0088	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26+65.50-L-)	Lump Sum	L.S.	
0089	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (26+65.50-L-)	Lump Sum	L.S.	
0090	8156000000-E	SP	CONCRETE WEARING SURFACE	4,735 SF		
0091	8161000000-E	420	GROOVING BRIDGE FLOORS	4,894 SF		
0092	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	10.7 CY		
0093	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	59.4 CY		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26+65.50-L-)	Lump Sum	L.S.	
0095	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,010 LB		
0096	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,037 LB		
0097	8364000000-E	450	HP12X53 STEEL PILES	350 LF		
0098	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	580 LF		
0099	8391000000-N	450	STEEL PILE POINTS	16 EA		
0100	8475000000-E	460	TWO BAR METAL RAIL	290.5 LF		
0101	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" x 2'-9 1/2")	305.5 LF		
0102	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	260 TON		
0103	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	285 SY		
0104	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0105	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,982.5 LF		

0958/Jan05/Q43354.6/D446290220000/E105

Total Amount Of Bid For Entire Project :

**Contract No**     **C202774**

**County (ies):**   **Cabarrus**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General