T.I.P.: B-4061

ONTRACT: C202775

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

TIP NO.		SHEET NO.
B-4061		PMP-1
APPROVED:	1/5/12	17

PAVEMENT MARKING PLAN CATAWBA COUNTY

LOCATION: BRIDGE NO. 90 OVER HAGAN CREEK ON SR 1727 (BOGGS RD)

INDEX

SHEET NO.

DESCRIPTION

PMP-1

PAVEMENT MARKING PLAN TITLE SHEET

PMP-2

FINAL PAVEMENT MARKING SCHEDULE AND PAVEMENT MARKING DETAIL

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE AND MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATOR SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATOR TYPES
1262.01	GUARDRAIL END DELINEATION

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME

MARKING

MARKER

BRIDGE #90

SR 1727 (BOGGS RD)

PAINT

NONE

- B) PLACE TWO APPLICATIONS OF PAINT PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE. PLACE THE SECOND APPLICATION OF PAINT UPON SUFFICIENT DRYING TIME OF THE FIRST.
- C) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- D) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.
- E) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.
- F) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS ON THE BRIDGE DECK PRIOR TO PLACING PAINT PAVEMENT MARKING.

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

Kelvin L. Jordan SIGNING & DELINEATION REGIONAL ENGINEER **
Walid Dakdouk SIGNING & DELINEATION DESIGN ENGINEER**



PAINT (4")
PA WHITE EDGELINE
PI YELLOW DOUBLE CENTER

15 -L- STA. 11+80+/-BEGIN BRIDGE -L- STA. 12+90+/-**END BRIDGE** -L- STA. 13+90+/-END PROJECT

-L- STA 17+20.00

TIE TO EXISTING TO SR 1722 (OLD CATAWBA RD) 11' 11' FAITH BOGGS RD 50' TAPER HAGAN CAREEK BEGIN PROJECT

-L- STA 11+30.00

TIE TO EXISTING TO NC 10 50'TAPER -L- STA. 16+70+/-

FINAL PAVEMENT MARKING SCHEDULE AND PAVEMENT MARKING DETAIL