

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (19+82.53)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	55 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	60 LF		
0012	0335400000-E	305	24" DRAINAGE PIPE	76 LF		
0013	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	20 LF		
0014	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0015	1099500000-E	505	SHALLOW UNDERCUT	200 CY		
0016	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	400 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	325 TON		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	250 TON		
0020	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	32 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	50 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	40 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0024	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE	1 LF		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0027	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1 LF		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0029	2556000000-E	846	SHOULDER BERM GUTTER	55 LF		
0030	3030000000-E	862	STEEL BM GUARDRAIL	150 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0034	3500000000-E	866	WOVEN WIRE FENCE, *** FABRIC (36")	75 LF		
0035	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	4 EA		
0036	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	7 EA		
0037	3557000000-E	866	ADDITIONAL BARBED WIRE	75 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (3)	260 LF		
0039	3575000000-E	SP	GENERIC FENCING ITEM 48" WOODEN RAIL FENCE	255 LF		
0040	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0041	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	830 SY		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	447 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0044	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,000 LF		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	250 LF		
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	110 TON		
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	205 TON		
0050	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	250 LF		
0054	6029000000-E	SP	SAFETY FENCE	300 LF		
0055	6030000000-E	1630	SILT EXCAVATION	290 CY		
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6037000000-E	SP	COIR FIBER MAT	60 SY		
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0059	6070000000-N	1639	SPECIAL STILLING BASINS	8 EA		
0060	6071010000-E	SP	WATTLE	180 LF		
0061	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0062	6071030000-E	1640	COIR FIBER BAFFLE	120 LF		
0063	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0064	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0065	6087000000-E	1660	MOWING	0.5 ACR		
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0070	6114500000-N	1667	SPECIALIZED HAND MOWING	30 MHR		
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

STRUCTURE ITEMS

0072	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+82.53-L-)	Lump Sum	L.S.	
0073	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	182.5 LF		
0074	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	47 LF		

County: Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	106.5 LF		
0076	8113000000-N	411	SID INSPECTIONS	2 EA		
0077	8114000000-N	411	SPT TESTING	2 EA		
0078	8115000000-N	411	CSL TESTING	1 EA		
0079	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (19+82.53-L-)	Lump Sum	L.S.	
0080	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	78.3 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+82.53-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	30,514 LB		
0083	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,868 LB		
0084	8364000000-E	450	HP12X53 STEEL PILES	755 LF		
0085	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	270.75 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	140 TON		
0087	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	155 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0089	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	825 LF		
0090	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	660 LF		

1244/Jan11/Q54032.3/D405490250000/E90

Total Amount Of Bid For Entire Project :

Contract No. **C202779**

County (ies): **Iredell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General