

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22 + 62.5 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,300 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	1,300 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	1,400 SY		
0008	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING AND DISPOSAL OF CONTAMINATED SOIL	4,000 TON		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	80 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	230 SY		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	364 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	236 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	8 LF		
0014	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	56 LF		
0015	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0016	1121000000-E	520	AGGREGATE BASE COURSE	63 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1275000000-E	600	PRIME COAT	42 GAL		
001S	1330000000-E	607	INCIDENTAL MILLING	380 SY		
002C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,020 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,010 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	810 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	145 TON		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	89.6 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	67.2 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	400 LF		
0027	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE	6 LF		
002S	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	11 EA		
003C	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.6 LF		
0031	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0034	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
003E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	230 LF		
003E	2556000000-E	846	SHOULDER BERM GUTTER	20 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2591000000-E	848	4" CONCRETE SIDEWALK	150	SY	
003E	2605000000-N	848	CONCRETE CURB RAMP	2	EA	
003E	3030000000-E	862	STEEL BM GUARDRAIL	150	LF	
004C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0041	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	1	EA	
0042	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1	EA	
004E	3575000000-E	SP	GENERIC FENCING ITEM ALUMINUM ORNAMENTAL FENCE	50	LF	
0044	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,800	SY	
004E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2	EA	
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	143	LF	
0047	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
004E	4102000000-N	904	SIGN ERECTION, TYPE E	6	EA	
004E	4108000000-N	904	SIGN ERECTION, TYPE F	1	EA	
005C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8	EA	
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	82	SF	
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	64	SF	
005E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	188	SF	
0054	4415000000-N	1115	FLASHING ARROW BOARD	2	EA	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
005E	4430000000-N	1130	DRUMS	161 EA		
0057	4445000000-E	1145	BARRICADES (TYPE III)	192 LF		
005E	4507000000-E	1170	WATER FILLED BARRIER	120 LF		
005E	4510000000-N	SP	LAW ENFORCEMENT	48 HR		
006C	4595000000-E	SP	GENERIC TRAFFIC CONTROL ITEM MAINTENANCE & REMOVAL OF EXT DETOUR SIGNS OUTSIDE PROJECT LIMITS	2,290 SF		
0061	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	59 EA		
0062	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	357 LF		
0063	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	86 LF		
0064	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	11 EA		
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,000 LF		
006E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	260 LF		
0067	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	66 LF		
006E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	26 EA		
006E	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	5,288 LF		
007C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	71 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	6000000000-E	1605	TEMPORARY SILT FENCE	2,155 LF		
0072	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0073	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	55 TON		
0074	6012000000-E	1610	SEDIMENT CONTROL STONE	585 TON		
0075	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0076	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0077	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0078	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0079	6029000000-E	SP	SAFETY FENCE	1,400 LF		
008C	6030000000-E	1630	SILT EXCAVATION	60 CY		
0081	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,560 SY		
0082	6037000000-E	SP	COIR FIBER MAT	10 SY		
0083	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	50 SY		
0084	6042000000-E	1632	1/4" HARDWARE CLOTH	590 LF		
008E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	640 SY		
0086	6070000000-N	1639	SPECIAL STILLING BASINS	20 EA		
0087	6071030000-E	1640	COIR FIBER BAFFLE	50 LF		
008E	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0089	6084000000-E	1660	SEEDING & MULCHING	3 ACR		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	6087000000-E	1660	MOWING	3	ACR	
0091	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0092	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0093	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0094	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
009E	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
0097	6123000000-E	1670	REFORESTATION	0.1	ACR	
009E	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	30	LF	
009E	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	10	LF	
010C	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1	EA	
0101	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	560	LF	
0102	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	380	LF	
0103	7636000000-N	1745	SIGN FOR SIGNALS	3	EA	

STRUCTURE ITEMS

0104	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22 + 62.50-L-)	Lump Sum	L.S.	
010E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 62.50-L-)	Lump Sum	L.S.	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8105560000-E	411	4'-0" DIA DRILLED PIERS IN SOIL	220.67 LF		
0107	8105660000-E	411	4'-0" DIA DRILLED PIERS NOT IN SOIL	121 LF		
010E	8111600000-E	411	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	79.8 LF		
0109	8113000000-N	411	SID INSPECTIONS	1 EA		
011C	8114000000-N	411	SPT TESTING	1 EA		
0111	8115000000-N	411	CSL TESTING	1 EA		
0112	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (22+62.50-L-)	Lump Sum	L.S.	
0113	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	29,750 SF		
0114	8161000000-E	420	GROOVING BRIDGE FLOORS	23,474 SF		
011E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	262.5 CY		
011E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+62.50-L-)	Lump Sum	L.S.	
0117	8217000000-E	425	REINFORCING STEEL (BRIDGE)	64,144 LB		
011E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	12,255 LB		
0119	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	972,170 LS		
012C	8384000000-E	450	HP14X73 STEEL PILES	980 LF		
0121	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	746.55 LF		
0122	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,636 TON		
0123	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	1,820 SY		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0125	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0126	8727000000-N	SP	ELECTRICAL CONDUIT SYSTEM FOR SIGNALS AT STA***** (22 + 62.50-L-)	Lump Sum	L.S.	
0127	8860000000-N	SP	GENERIC STRUCTURE ITEM ELECTRICAL CONDUIT SYSTEM FOR UNDERPASS LIGHTING AT STA 22 + 62.50-L-	Lump Sum	L.S.	
0128	8867000000-E	SP	GENERIC STRUCTURE ITEM CLASSIC CONCRETE BRIDGE RAIL	746.55 LF		
0832/Jan13/Q1154272.57/D602006500000/E128			Total Amount Of Bid For Entire Project :			

Contract No **C202783**

County (ies): **Johnston**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General